

CODED PAY ITEM NO.	ITEM	UNIT	URBAN TOTAL QUANTITY	0001				0003				0004				0005				100% STATE				100% STATE				100% STATE				100% STATE					
				ROADWAY		ROADWAY		ROADWAY		ROADWAY		0008				0028		0021		0021				0031		0021		0040		0043		0044					
				STATE	LOCAL	STATE	LOCAL	STATE	LOCAL	STATE	LOCAL	SN	SN	SN	SN	SN	SN	SN	SN	SN	SN	SN	SN	SN	SN	SN	SN	SN	SN	SN	SN	SN	SN				
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	9000	9000																																	
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	4046	4000																																46	
20101000	TEMPORARY FENCE	FOOT	7396	5105																															2291		
20101100	TREE TRUNK PROTECTION	EACH	75	75																																	
20101200	TREE ROOT PRUNING	EACH	50	50																																	
20200100	EARTH EXCAVATION	CU YD	224640	224640																																	
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	20111	20111																																	
20400800	FURNISHED EXCAVATION	CU YD	58510	58510																																	
20700220	POROUS GRANULAR EMBANKMENT	CU YD	4246																																13		
20800150	TRENCH BACKFILL	CU YD	8324	528	222	4682	170	647	333	742																											
21101615	TOPSOIL FURNISH AND PLACE, 4"	SO YD	227225	221015																															6210		
25000100	SEEDING, CLASS 1	ACRE	3.00																																		
25000115	SEEDING, CLASS 1B	ACRE	0.50																																		
25000210	SEEDING, CLASS 2A	ACRE	14.75																																		
25000310	SEEDING, CLASS 4	ACRE	20																																		
25000312	SEEDING, CLASS 4A	ACRE	2.75																																		
25000314	SEEDING, CLASS 4B	ACRE	2.50																																		
25000322	SEEDING, CLASS 5A	ACRE	2.75																																		
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	1898																																107		
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	1898																																107		
25000775	SELECTIVE MOWING STAKES	EACH	213																																		
25100115	MULCH METHOD 2	ACRE	6.00	6.00																																	
25100630	EROSION CONTROL BLANKET	SO YD	222905	179576		33189		1705																											8435		
25100900	TURF REINFORCEMENT MAT	SO YD	494	494																																	
28000200	EARTH EXCAVATION FOR EROSION CONTROL	CU YD	26																																	26	
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	5036	4308		686		35																												7	
28000305	TEMPORARY DITCH CHECKS	FOOT	1751	1591		160																															
28000400	PERIMETER EROSION BARRIER	FOOT	21524	12625		6762		407																												1730	
28000510	INLET FILTERS	EACH	254	102		142		10																													
28001000	AGGREGATE (EROSION CONTROL)	TON	742	742																																	

- INDICATES SPECIAL PROVISION
- △ ITEM TO BE PAID FOR BY ALGONQUIN/LAKE IN THE HILLS FIRE PROTECTION DISTRICT
- ITEM TO BE PAID FOR BY THE VILLAGE OF ALGONQUIN

○ Specialty Items

FILE NAME = ...D160F72-shr-summary-01.dgn	USER NAME = etb	DESIGNED - DTE	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>SUMMARY OF QUANTITIES</b>	O.R. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
	PLOT SCALE = 2.0000' / in.	DRAWN - CTB	REVISED -			0003	18A-2	MCHENRY	825	6	
	PLOT DATE = 5/8/2012	CHECKED - GAB	REVISED -			<b>CONTRACT NO. 60F72</b>					
		DATE - 5/3/2012	REVISED -			SCALE:	SHEET NO. 1 OF 22 SHEETS	STA.	TO STA.	FED. ROAD DIST. NO. 1   ILLINOIS FED. AID PROJECT	