				URBAN	100% STATE	100% LOCAL	100% STATE	100% LOCAL	100% STATE	100% LOCAL	100% STATE				100% LOCAL	100% STATE							100% LOCAL	100% STATE	100% LOCAL	100% STATE	
CODED PAY ITEM NO.	ITEM	UNIT	TOTAL QUANTITY	0001 ROADWAY		0003 ROADWAY		0004 ROADWAY	0005 ROADWAY		0008 BRIDGE				0028 PATH	0021 LIGHTING		0021 TRAFFIC SIGNALS						0031 LANDSCAPING		0021 SAFETY	0040 RETAINING WALLS	0043 UTILITIES		0044 CREEK RELOCATE
				STATE	LOCAL	STATE	LOCAL		STATE	LOCAL	SN 056-0077	SN 056-0081	SN 056-0079	SN 056-0080		STATE	LOCAL	EDGE WOOD DRIVE	HUNT INGTON DRIVE	RAMPS A/B	RAMPS C/D	QUARRY ACCESS	INTERCO NNECT	STATE	LOCAL			STATE	LOCAL	
28100103	STONE RIPRAP, CLASS A2	SQ YD	425																										425
28100105	STONE RIPRAP, CLASS A3	SQ YD	25	20				5																					
28100107	STONE RIPRAP, CLASS A4	SQ YD	128			128																							
28100109	STONE RIPRAP, CLASS A5	SQ YD	1348								646		362	340															
28200200	FILTER FABRIC	SQ YD	3128	1355							646		362	340															425
28500400	ARTICULATED BLOCK REVETMENT MAT	SQ YD	180	180																									
• 30300112	AGGREGATE SUBGRADE IMPROVEMENT 12"	SQ YD	117849	67855		47400	598	1996																					
• 30300124	AGGREGATE SUBGRADE IMPROVEMENT 24"	SQ YD	3545	3545																									
31101200	SUBBASE GRANULAR MATERIAL, TYPE B 4"	SQ YD	1921	233		1625		29	34																				
31101400	SUBBASE GRANULAR MATERIAL, TYPE B 6"	SQ YD	11985	5412		1181									5392														
31101800	SUBBASE GRANULAR MATERIAL, TYPE B 10"	SQ YD	8359	4969		3390																							
31102000	SUBBASE GRANULAR MATERIAL, TYPE C	CU YD	689	689																									
31200502	STABILIZED SUBBASE - HOT-MIX ASPHALT, 4 1/2"	SQ YD	56647	56647																									
35501287	HOT-MIX ASPHALT BASE COURSE, 2 1/4"	SQ YD	8485	4973		3390			122																				
40201000	AGGREGATE FOR TEMPORARY ACCESS	TON	11086			11086																							
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	13983	1965		7378		1037	1099						2504														
40600300	AGGREGATE (PRIME COAT)	TON	35	6		21		3	5																				
40600895	CONSTRUCTING TEST STRIP	EACH	1	1																									
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	65						65																				
40603335	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	1663	709		380			14						560														
40603595	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "F", N90	TON	644						644																				
40701846	HOT-MIX ASPHALT PAVEMENT (FULL-DEPTH), 8 1/4"	SQ YD	12926 1709			9736		1481																					
40701966	HOT-MIX ASPHALT PAVEMENT (FULL-DEPTH), 14 1/4"	SQ YD	1352			754	598																						
40702700	FURNISH PROFILOGRAPH	L SUM	1	1																									
42000416	PORTLAND CEMENT CONCRETE PAVEMENT 9 3/4" (JOINTED)	SQ YD	97445	61763		35682																							
42001300	PROTECTIVE COAT	SQ YD	131273	83453		45190		409							2221														

26

• INDICATES SPECIAL PROVISION
△ ITEM TO BE PAID FOR BY ALGONQUIN/LAKE IN THE HILLS FIRE PROTECTION DISTRICT
□ ITEM TO BE PAID FOR BY THE VILLAGE OF ALGONQUIN

FILE NAME = ...\D160F72-sht-summary-02.dgn	USER NAME = ctb	DESIGNED - DTE	REVISED -
		DRAWN - CTB	REVISED -
	PLOT SCALE = 2.0000 ' / in.	CHECKED - GAB	REVISED -
	PLOT DATE = 5/8/2012	DATE - 5/3/2012	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: | SHEET NO. 2 OF 22 SHEETS | STA. | TO STA.

O.R. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
0003	18A-2	MCHENRY	825	7
		CONTRACT NO. 60F72		
FED. ROAD DIST. NO. 1	ILLINOIS	FED. AID PROJECT		