

CODED PAY ITEM NO.	ITEM	UNIT	TOTAL QUANTITY	100% STATE										100% STATE								100% STATE			100% STATE						
				URBAN		0001		0003		0004		0005		0008				0028	0021		0021				0031		0021	0040	0043		0044
				ROADWAY		ROADWAY		ROADWAY		ROADWAY		BRIDGE				PATH	LIGHTING		TRAFFIC SIGNALS				LANDSCAPING		SAFETY	RETAINING WALLS	UTILITIES		CREEK RELOCATE		
				100% STATE	100% LOCAL	100% STATE	100% LOCAL	100% STATE	100% LOCAL	100% STATE	100% LOCAL	SN 056-0077	SN 056-0081	SN 056-0079	SN 056-0080	STATE	100% LOCAL	EDGE WOOD DRIVE	HUNTINGTON DRIVE	RAMPS A/B	RAMPS C/D	QUARRY ACCESS	INTERCONNECT	STATE			100% LOCAL	STATE		100% LOCAL	STATE
60620000	CONCRETE MEDIAN, TYPE SB-6.24	SQ FT	21515	07A0P 19561	07P0P	07A0P 1954	07P0P	07A0P	07A0P	07P0P	07A0P	07A0P	07A0P	07A0P	07A0P	07A0P	07A0P	07A0P	07A0P	07A0P	07A0P	07A0P	07A0P	07A0P	07A0P	07A0P	07A0P	07A0P	07A0P		
60900515	CONCRETE THRUST BLOCKS	EACH	5	5																											
63000001	STEEL PLATE BEAM GUARD RAIL, TYPE A, 6 FOOT POSTS	FOOT	24			24																									
63000003	STEEL PLATE BEAM GUARD RAIL, TYPE A, 9 FOOT POSTS	FOOT	1148	1059		89																									
63100045	TRAFFIC BARRIER TERMINAL, TYPE 2	EACH	5	4		1																									
63100070	TRAFFIC BARRIER TERMINAL, TYPE 5	EACH	3	3																											
63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	7	5		2																									
63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	7	6		1																									
63200310	GUARDRAIL REMOVAL	FOOT	2049	69		1915																							65		
63304305	TRAFFIC BARRIER TERMINAL REMOVAL, TYPE 1	EACH	1			1																									
63700275	CONCRETE BARRIER, DOUBLE FACE, 42 INCH HEIGHT	FOOT	75	75																											
66400305	CHAIN LINK FENCE, 6'	FOOT	320			320																									
66900200	NON-SPECIAL WASTE DISPOSAL	CU YD	728	728																											
66900450	SPECIAL WASTE PLANS AND REPORTS	L SUM	1	1																											
66900530	SOIL DISPOSAL ANALYSIS	EACH	1	1																											
X6700410	ENGINEER'S FIELD OFFICE, TYPE A (SPECIAL)	CAL MO	30	30																											
67100100	MOBILIZATION	L SUM	1	1																											
67201100	SEALING ABANDONED MONITORING WELLS	EACH	10	3		7																									
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	1																											
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1	1																											
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	55	48													3	1	1	2											
70300210	TEMPORARY PAVEMENT MARKING LETTERS AND SYMBOLS	SQ FT	36.4			36.4																									
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	15421	2004		13417																									
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	107	100		7																									
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	81	45		36																									
70300510	PAVEMENT MARKING TAPE, TYPE III - LETTERS AND SYMBOLS	SQ FT	146			146																									

- INDICATES SPECIAL PROVISION
- △ ITEM TO BE PAID FOR BY ALGONQUIN/LAKE IN THE HILLS FIRE PROTECTION DISTRICT
- ITEM TO BE PAID FOR BY THE VILLAGE OF ALGONQUIN

○ Specialty Items

FILE NAME : ...D160F72-sht-summary-09.dgn

USER NAME = ctb	DESIGNED - DTE	REVISED -
PLOT SCALE = 2.0000' / in.	DRAWN - CTB	REVISED -
PLOT DATE = 5/8/2012	CHECKED - GAB	REVISED -
	DATE - 5/3/2012	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: SHEET NO. 9 OF 22 SHEETS STA. TO STA.

O.R. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
0003	18A-2	MCHENRY	825	14
CONTRACT NO. 60F72				
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT				