					100% STATE												100% STATE										100% STATE										100% STATE		
CODED PAY ITEM NO.	ITEM	UNIT	URBAN TOTAL QUANTITY	0001 ROADWAY		0003 ROADWAY		0004 ROADWAY	0005 ROADWAY		0008 BRIDGE				0028 PATH	0021 LIGHTING		0021 TRAFFIC SIGNALS						0031 LANDSCAPING		0021	0040	0043 UTILITIES		0044
				100% STATE	100% LOCAL	100% STATE	100% LOCAL	100% STATE	100% STATE	100% LOCAL	SN 056-0077	SN 056-0081	SN 056-0079	SN 056-0080		STATE	100% LOCAL	EDGE WOOD DRIVE	HUNT INGTON DRIVE	RAMPS A/B	RAMPS C/D	QUARRY ACCESS	INTERCO NNECT	STATE	100% LOCAL	SAFETY	RETAIN ING WALLS	STATE	100% LOCAL	CREEK RELOCATE
78300100	PAVEMENT MARKING REMOVAL	SQ FT	2132			2132																															
80400100	ELECTRIC SERVICE INSTALLATION	EACH	4													4																						
• 80400200	ELECTRIC UTILITY SERVICE CONNECTION	L SUM	1													1																						
80500010	SERVICE INSTALLATION - GROUND MOUNTED	EACH	2																	1		1																
80500020	SERVICE INSTALLATION - POLE MOUNTED	EACH	2																1		1																	
81023300	CONDUIT ENCASED, CONCRETE, 2" DIA., PVC 2 WIDE X 1 HIGH	FOOT	38													38																						
81028200	UNDERGROUND CONDUIT, GALVANIZED STEEL, 2" DIA.	FOOT	1271													534		384	895	760	741	991	7866															
81028210	UNDERGROUND CONDUIT, GALVANIZED STEEL, 2 1/2" DIA.	FOOT	1895													968		29	251	276	316	55																
81028220	UNDERGROUND CONDUIT, GALVANIZED STEEL, 3" DIA.	FOOT	328																35	26	200	67																
81028240	UNDERGROUND CONDUIT, GALVANIZED STEEL, 4" DIA.	FOOT	4821													2315		93	586	837	449	541																
81100320	CONDUIT ATTACHED TO STRUCTURE, 1" DIA., PVC COATED GALVANIZED STEEL	FOOT	703													703																						
81200120	CONDUIT EMBEDDED IN STRUCTURE, 2" DIA., GALVANIZED STEEL	FOOT	271																				271															
81200230	CONDUIT EMBEDDED IN STRUCTURE, 2" DIA., PVC	FOOT	4915													4915																						
81300220	JUNCTION BOX, STAINLESS STEEL, ATTACHED TO STRUCTURE, 6" X 6" X 4"	EACH	17													17																						
81300530	JUNCTION BOX, STAINLESS STEEL, ATTACHED TO STRUCTURE, 12" X 10" X 6"	EACH	16													16																						
81304600	JUNCTION BOX EMBEDDED IN STRUCTURE 18" X 12" X 6"	EACH	16													16																						
81400100	HANDHOLE	EACH	38															2	5	6	7	4	14															
81400200	HEAVY-DUTY HANDHOLE	EACH	13															2	4	1	2	4																
81400300	DOUBLE HANDHOLE	EACH	9																2	4	1	2																
81603020	UNIT DUCT, 600V, 3-1C NO.10, 1/C NO.10 GROUND, (XLP-TYPE USE), 3/4" DIA. POLYETHYLENE	FOOT	738													738																						
81603040	UNIT DUCT, 600V, 2-1C NO.6, 1/C NO.8 GROUND, (XLP-TYPE USE), 1" DIA. POLYETHYLENE	FOOT	2268													2268																						
81603055	UNIT DUCT, 600V, 3-1C NO.8, 1/C NO.8 GROUND, (XLP-TYPE USE), 1" DIA. POLYETHYLENE	FOOT	3096													3096																						

• INDICATES SPECIAL PROVISION

△ ITEM TO BE PAID FOR BY ALGONQUIN/LAKE IN THE HILLS FIRE PROTECTION DISTRICT

□ ITEM TO BE PAID FOR BY THE VILLAGE OF ALGONQUIN

O Specialty Items

FILE NAME = ...\D160F72-sht-summary-11.dgn	USER NAME = ctb	DESIGNED - DTE	REVISED -
		DRAWN - CTB	REVISED -
	PLOT SCALE = 2.0000 ' / in.	CHECKED - GAB	REVISED -
	PLOT DATE = 5/8/2012	DATE - 5/3/2012	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: | SHEET NO. 11 OF 22 SHEETS | STA. | TO STA.

O.R. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
0003	18A-2	MCHENRY	825	16
		CONTRACT NO. 60F72		
FED. ROAD DIST. NO. P.	ILLINOIS	FED. AID PROJECT		