

100% STATE      100% STATE      100% STATE      100% STATE

CODED PAY ITEM NO.	ITEM	UNIT	TOTAL QUANTITY	URBAN		0001		0003		0004		0005		0008				0028	0021		0021						0031		0021	0040	0043		0044
				ROADWAY		ROADWAY		ROADWAY		ROADWAY		BRIDGE				LIGHTING			TRAFFIC SIGNALS						LANDSCAPING		UTILITIES						
				100% STATE	100% LOCAL	100% STATE	100% LOCAL	100% STATE	100% LOCAL	100% STATE	100% LOCAL	SN 056-0077	SN 056-0081	SN 056-0079	SN 056-0080	STATE	100% LOCAL		EDGE WOOD DRIVE	HUNT INGTON DRIVE	RAMPS A/B	RAMPS C/D	QUARRY ACCESS	INTERCO NNECT	STATE	100% LOCAL	SAFETY	RETAIN ING WALLS			STATE	100% LOCAL	
88500100	INDUCTIVE LOOP DETECTOR	EACH	79																			9	12	9	11	12	26						
88600100	DETECTOR LOOP, TYPE I	FOOT	517																			517											
88600700	PREFORMED DETECTOR LOOP	FOOT	3649																				1458	557	711	923							
△ 88700200	LIGHT DETECTOR	EACH	15																				3	5	4	3							
△ 88700300	LIGHT DETECTOR AMPLIFIER	EACH	4																				1	1	1	1							
88800100	PEDESTRIAN PUSH-BUTTON	EACH	11																				2	9									
89000100	TEMPORARY TRAFFIC SIGNAL INSTALLATION	EACH	1																				1										
△ 89501400	RELOCATE EXISTING EMERGENCY VEHICLE PRIORITY SYSTEM, DETECTOR UNIT	EACH	1																				1										
△ 89501410	RELOCATE EXISTING EMERGENCY VEHICLE PRIORITY SYSTEM, PHASING UNIT	EACH	3																				1									2	
89502300	REMOVE ELECTRIC CABLE FROM CONDUIT	FOOT	10479																			5792		2794								1893	
89502375	REMOVE EXISTING TRAFFIC SIGNAL EQUIPMENT	EACH	4																				1	1								2	
89502376	REBUILD EXISTING HANDHOLE	EACH	1																				1										
89502380	REMOVE EXISTING HANDHOLE	EACH	21																				5	8								8	
89502385	REMOVE EXISTING CONCRETE FOUNDATION	EACH	9																				2	7									
• Z0001202	CONCRETE BLOCK REMOVAL	CU YD	6						6																								
○ Z0007118	UNTREATED TIMBER LAGGING	SQ FT	9057																													9057	
• Z0007430	TEMPORARY SIDEWALK	SQ FT	1106																													1106	
• Z0012450	CONCRETE STEPS	CU YD	2	2																													
• Z0013300	CONCRETE REMOVAL (SPECIAL)	SQ YD	57	55					2																								
• Z0013302	SEGMENTAL CONCRETE BLOCK WALL	SQ FT	10073																													10073	
• Z0013797	STABILIZED CONSTRUCTION ENTRANCE	SQ YD	81																													81	
• Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1																													
• Z0015000	CURB STOPS 1"	EACH	9																													9	
• Z0018010	DRAINAGE SCUPPERS, DS-33	EACH	6												2	2	1	1															
• Z0019600	DUST CONTROL WATERING	UNIT	8500	8500																													
• Z0022800	FENCE REMOVAL	FOOT	55						55																								
• Z0026402	FURNISHING SOLDIER PILES (HP SECTION)	FOOT	172																													172	
• Z0026404	FURNISHING SOLDIER PILES (W SECTION)	FOOT	3294																													3294	

• INDICATES SPECIAL PROVISION  
 △ ITEM TO BE PAID FOR BY ALGONQUIN/LAKE IN THE HILLS FIRE PROTECTION DISTRICT  
 □ ITEM TO BE PAID FOR BY THE VILLAGE OF ALGONQUIN

○ Specialty Items

FILE NAME = ...D:\60F72-sht-summary-15.dgn	USER NAME = ctb	DESIGNED - DTE	REVISED -	<p style="text-align: center;"><b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b></p> <p style="text-align: center;"><b>SUMMARY OF QUANTITIES</b></p>	O.P. RTE. =	SECTION =	COUNTY =	TOTAL SHEETS =	SHEET NO. =
		DRAWN - CTB	REVISED -		0003	18A-2	MCHENRY	825	20
	PLOT SCALE = 2.0000' / in.	CHECKED - GAB	REVISED -		FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT				
	PLOT DATE = 5/8/2012	DATE - 5/3/2012	REVISED -		SCALE:	SHEET NO. 15 OF 22 SHEETS	STA.	TO STA.	CONTRACT NO. 60F72