

100% STATE

100% STATE

100% STATE

100% STATE

CODED PAY ITEM NO.	ITEM	UNIT	TOTAL QUANTITY	URBAN		0001		0003		0004		0005		0008				0028	0021		0021						0031		0021	0040	0043		0044
				ROADWAY		ROADWAY		ROADWAY		ROADWAY		BRIDGE				PATH	LIGHTING		TRAFFIC SIGNALS						LANDSCAPING		RETAINING WALLS	UTILITIES		CREEK RELOCATE			
				100% STATE	100% LOCAL	100% STATE	100% LOCAL	100% STATE	100% LOCAL	100% STATE	100% LOCAL	SN 056-0077	SN 056-0081	SN 056-0079	SN 056-0080	STATE	100% LOCAL	EDGE WOOD DRIVE	HUNTINGTON DRIVE	RAMPS A/B	RAMPS C/D	QUARRY ACCESS	INTERCONNECT	STATE	100% LOCAL	SAFETY	STATE	100% LOCAL	STATE	100% LOCAL	STATE		
* Z0030260	IMPACT ATTENUATORS (FULLY REDIRECTIVE, NARROW), TEST LEVEL 3	EACH	1	1																													
* Z0030275	IMPACT ATTENUATORS, TEMPORARY (SEVERE USE, NARROW), TEST LEVEL 2	EACH	3			3																											
○ Z0033020	LUMINAIRE SAFETY CABLE ASSEMBLY	EACH	125																														
○ Z0033028	MAINTENANCE OF LIGHTING SYSTEM	CAL MO	18																														
○ Z0033056	OPTIMIZE TRAFFIC SIGNAL SYSTEM	EACH	2																														
* Z0034210	MECHANICALLY STABILIZED EARTH RETAINING WALL	SQ FT	36884											9311	5773	2846	5334														13620		
* Z0042002	POROUS GRANULAR EMBANKMENT, SUBGRADE	CU YD	20831	20831																													
* Z0044298	PRESSURE CONNECTION TO EXISTING WATER-MAIN	EACH	1																												1		
* Z0046304	PIPE UNDERDRAINS FOR STRUCTURES, 4"	FOOT	3293																												3293		
* Z0048900	RAILROAD TRACK REMOVAL	FOOT	395	395																													
* Z0056608	STORM SEWER (WATER MAIN REQUIREMENTS) 12 INCH	FOOT	432	48		384																											
* Z0056610	STORM SEWER (WATER MAIN REQUIREMENTS) 15 INCH	FOOT	109	62		47																											
* Z0056616	STORM SEWER (WATER MAIN REQUIREMENTS) 24 INCH	FOOT	135	84		51																											
* Z0056900	SANITARY SEWER 8"	FOOT	1117			192	65	233	627																								
* Z0057000	SANITARY SEWER 10"	FOOT	535			535																											
* Z0057400	SANITARY SEWER 21"	FOOT	23						23																								
* Z0062456	TEMPORARY PAVEMENT	SQ YD	5699			5699																											
* Z0067500	STEEL CASINGS 16"	FOOT	608																												608		
* Z0067700	STEEL CASINGS 20"	FOOT	120																												120		
* Z0073510	TEMPORARY TRAFFIC SIGNAL TIMING	EACH	2																														
Z0076600	TRAINEES	HOUR																															
* Z0077900	WOOD POST AND RAIL FENCE	FOOT	684																													684	
○ A2000086	TREE, ACER X FREEMANII (ARMSTRONG FREEMAN MAPLE), 2-1/2" CALIPER, BALLED AND BURLAPPED	EACH	16																													16	
A2001020	TREE, ACER RUBRUM (RED MAPLE), 2-1/2" CALIPER, BALLED AND BURLAPPED	EACH	16																													16	
○ A2001720	TREE, ACER SACCHARUM (SUGAR MAPLE), 2-1/2" CALIPER, BALLED AND BURLAPPED	EACH	9																													9	
○ A2002020	TREE, AESCULUS GLABRA (OHIO BUCKEYE), 2-1/2" CALIPER, BALLED AND BURLAPPED	EACH	2																													2	

- * INDICATES SPECIAL PROVISION
- △ ITEM TO BE PAID FOR BY ALGONQUIN/LAKE IN THE HILLS FIRE PROTECTION DISTRICT
- ITEM TO BE PAID FOR BY THE VILLAGE OF ALGONQUIN

○ Specialty Items

FILE NAME : ...\\D168F72-shr-summary-16.dgn	USER NAME : ctb	DESIGNED - DTE	REVISED -
		DRAWN - CTB	REVISED -
		CHECKED - GAB	REVISED -
		DATE - 5/3/2012	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: SHEET NO. 16 OF 22 SHEETS STA. TO STA.

O.R. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
0003	18A-2	MCHENRY	825	21
CONTRACT NO. 60F72				
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT				