	CODED PAY ITEM NO.	ITEM	UNIT	URBAN TOTAL QUANTITY	0001 ROADWAY 100% STATE	0001 ROADWAY 100% LOCAL	0003 ROADWAY 100% STATE	0003 ROADWAY 100% LOCAL	0004 ROADWAY 100% STATE	0005 ROADWAY 100% STATE	0005 ROADWAY 100% LOCAL	0008 BRIDGE SN 056-0077	0008 BRIDGE SN 056-0081	0008 BRIDGE SN 056-0079	0008 BRIDGE SN 056-0080	0028 PATH	0021 LIGHTING STATE	0021 LIGHTING 100% LOCAL	0021 TRAFFIC SIGNALS EDGE WOOD DRIVE	0021 TRAFFIC SIGNALS HUNT INGTON DRIVE	0021 TRAFFIC SIGNALS RAMPS A/B	0021 TRAFFIC SIGNALS RAMPS C/D	0021 TRAFFIC SIGNALS QUARRY ACCESS	0021 TRAFFIC SIGNALS INTERCO NNECT	0031 LANDSCAPING STATE	0031 LANDSCAPING 100% LOCAL	0021 SAFETY	0040 RETAIN ING WALLS	0043 UTILITIES STATE	0043 UTILITIES 100% LOCAL	0044 CREEK RELOCATE
					100% STATE													100% LOCAL													
																	100% STATE													
O •	C2002636	SHRUB, EUONYMUS ALATA COMPACTUS', (DWARF BURNING BUSH), 3' HEIGHT, BALLED AND BURLAPPED	EACH	37																						37				
O •	C2004841	SHRUB, PHYSOCARPUS OPULIFOLIUS 'CENTER GLOW', (CENTER GLOW NINEBARK), 3' HEIGHT, BALLED AND BURLAPPED	EACH	37																						37				
O •	C2011424	SHRUB, SYRINGA VULGARIS, (COMMON PURPLE LILAC), 2' HEIGHT, BALLED AND BURLAPPED	EACH	43																						43				
O •	C2011425	SHRUB, SYRINGA VULGARIS ALBA, (COMMON WHITE LILAC), 2' HEIGHT, BALLED AND BURLAPPED	EACH	25																						25				
•	X0327412	RAILROAD TIES TO BE REMOVED	FOOT	345	168		177																							
O •	87704403	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE WITH DUAL MAST ARMS, 34 FT. AND 48 FT.	EACH	1																	1									
O □ •	X8510850	PAINT NEW COMBINATION MAST ARM AND POLE, (SPECIAL)	EACH	1																	1									
O △ •	X8770135	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 42 FT. (SPECIAL)	EACH	1																1										
•	X5610900	DUCTILE IRON WATER MAIN 8 RESTRAINED JOINT TYPE	FOOT	144																									144	
•	X0327413	TEMPORARY PEDESTRIAN ENCLOSURE	LSUM	1	1																									
O •	X2502019	SEEDING, ~~EMERGENT MIX~~ CLASS 4B (SPECIAL)	ACRE	0.25																										0.25
O •	X2502024	SEEDING, ~~WET PRAIRIE MIX~~ CLASS 4B (MODIFIED)	ACRE	0.5																										0.5
O •	X2501800	SEEDING, ~~MESIC PRAIRIE MIX~~ CLASS 4 (MODIFIED)	ACRE	1.00																										1
O •	X2502014	SEEDING, ~~SAVANNA MIX~~ CLASS 4A (MODIFIED)	ACRE	1.00																						0.5				0.5
•	X2810900	CHANNEL BED AGGREGATE	SQ YD	1835																										1835
•	X2810950	POINT BAR AGGREGATE	SQ YD	134																										134

* INDICATES SPECIAL PROVISION
△ ITEM TO BE PAID FOR BY ALGONQUIN/LAKE IN THE HILLS FIRE PROTECTION DISTRICT
□ ITEM TO BE PAID FOR BY THE VILLAGE OF ALGONQUIN

O Specialty Items

FILE NAME = ...\D160F72-sht-summary-22.dgn	USER NAME = ctb	DESIGNED - DTE	REVISED -
		DRAWN - CTB	REVISED -
	PLOT SCALE = 2.0000 ' / in.	CHECKED - GAB	REVISED -
	PLOT DATE = 5/8/2012	DATE - 5/3/2012	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: | SHEET NO. 22 OF 22 SHEETS | STA. | TO STA.

O.R. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
0003	18A-2	MCHENRY	825	23D
		CONTRACT NO. 60F72		
FED. ROAD DIST. NO. 1	ILLINOIS	FED. AID PROJECT		