

INDEX OF SCHEDULES	
ITEM	SHEET NO.
PAVEMENT	39
SUBGRADE	40
SIDEWALK & DRIVEWAYS	40
BARRIERS	41
MAINTENANCE OF TRAFFIC	42 & 43
MAINTENANCE OF TRAFFIC	44 & 44A
PAVEMENT MARKINGS	45
SIGNAGE	46
LANDSCAPING	46
EARTH EXCAVATION	47
EMBANKMENT	48
P.G.E.	49

PAVEMENT											
STATION	HOT-MIX ASPHALT BASE CSE, 2.25"	HOT-MIX ASPHALT PAVEMENT, (FULL-DEPTH), 14.25"	POLYMERIZED HOT-MIX ASPHALT SURFACE CSE, MIX "F", N90	HOT-MIX ASPHALT SURFACE CSE, MIX "D", N50	HOT-MIX ASPHALT PAVEMENT, (FULL-DEPTH), 8.25"	PORTLAND CEMENT CONCRETE PAVEMENT 9.75" (JOINTED)	AGGREGATE SHOULDERS, TYPE A 6"	AGGREGATE SHOULDERS, TYPE B 6"	HOT-MIX ASPHALT SHOULDERS, 6"	PORTLAND CEMENT CONCRETE SHOULDERS, 9.75"	
	(SQ YD)	(SQ YD)	(TON)	(TON)	(SQ YD)	(SQ YD)	(SQ YD)	(SQ YD)	(SQ YD)	(SQ YD)	
IL ROUTE 31	87+35 TO 99+00	122	1352	644	14	804					
	99+00 TO 112+00	831			93	9402					
	112+00 TO 126+00					9201		69		526	
	126+00 TO 140+00					3547				1092	
	140+00 TO 153+00					8453				1755	
	153+00 TO 166+00					9199				201	
	166+00 TO 180+00				29	13711			23		
	180+00 TO 214+28.36				95	6723					
HUNTINGTON DR	209+97.84 TO 216+14.76	107			86	1765	607				
SOUTH MAIN ST	217+25 TO 221+08					954	455				
LEGION DR	0+23 TO 3+40					578		30			
RAILROAD ST	300+75 TO 303+98.02					903					
ALGONQUIN RD	50+00 TO 59+50	2452			275	7213					
	59+50 TO 68+14.20					9590			54		
RAMP A	0+32.87 TO 2+50					1392		10			
	2+50 TO 9+00					3082		145		291	
	9+00 TO 21+50					3310		279		558	
	21+50 TO 28+75.28					1758	1181	43		86	
RAMP B	2+93.46 TO 10+00					1608				163	
	10+00 TO 13+50					172		28		71	
	13+50 TO 15+16.46					828		12			
RAMP C	0+66.06 TO 2+50					488		22			
	2+50 TO 7+00					172		33		115	
	7+00 TO 12+11.48					1099		163		447	
RAMP D	3+14.82 TO 10+50					1635		134			
	10+50 TO 16+00					2160		196		468	
	16+00 TO 17+54.85					836		26		268	
NORTH MAIN ST	50+00 TO 57+23.89					4290					
FRONTAGE RD	0+80.52 TO 5+41.09	4			42	1285					
GREENWOOD CT	20+27 TO 21+75.41					424					
QUARRY ACCESS	60+00 TO 61+50					746		173			
	61+50 TO 67+86.49					1877		220			
MCCD PRAIRIE PATH	0+00 TO 26+13.88				321						
ACCESS DRIVE	60+00 TO 65+65										
	65+65 TO 73+29.13										
TOWNE PARK		4969			708						
TOTALS		8485	1352	644	1663	12926	97445	1181	1583	77	6041