

### ELEVATION AT N. ABUTMENT

# SECTION B-B

### FIXED BEARING

(No. Required = 10)

Anchor bolts shall be ASTM F1554 all-thread (or an Engineer-approved alternate material) of the grade(s) and diameter(s) specified. The corresponding specified grade of AASHTO M314 anchor bolts may be used in lieu of ASTM F1554.

Anchor bolts at fixed bearings may be either cast in place or installed in holes drilled after the supported member is in place.


Anchor bolts for side retainers may be cast in place or installed in holes drilled before or after members are in


Drilled and set anchor bolts shall be installed according to Article 521.06 of the Standard Specifications.

Side retainers and other steel members required for the elastomeric bearing assembly shall be included in the cost of Elastomeric Bearing Assembly, Type I.

The structural steel plates of the Bearing Assembly shall conform to the requirements of AASHTO M 270 Grade 50.

## TYPE I ELASTOMERIC EXP. BRG.






PINTLE

## BEARING ASSEMBLY

Shim plates shall not be placed under Bearing Assembly.



# SIDE RETAINER

Equivalent rolled angle with stiffeners will be allowed in lieu of welded plates.

### BILL OF MATERIAL

Item	Unit	Total
Elastomeric Bearing Assembly Type I	Each	10
Anchor Bolts, 1"	Each	20
Anchor Bolts, 1 <sup>l</sup> <sub>4</sub> "	Each	20



450 E Devon Ave, Suite 300 Itasca, Illinois 60143 Tel: 630.773.3900 Fax: 630.773.3975

DRAWN - M. LANGE REVISED DESIGNED - D. ATKINS REVISED CHECKED - G. HATLESTAD REVISED - 5/3/2012 REVISED

STATE OF ILLINOIS **DEPARTMENT OF TRANSPORTATION**  BEARING DETAILS
ILLINOIS ROUTE 31 OVER CRYSTAL CREEK STRUCTURE NO. 056-0077 SHEET NO. SA20 OF SA33 SHEETS

SECTION COUNTY MCHENRY 825 480 0003 18A-2 CONTRACT NO. 60F72