

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE		
				80% FED 20% STATE	80% FED 20% STATE	80% FED 20% STATE
				ROADWAY AND DRAINAGE	RETAINING WALL SN 022-W045	PUMP STATION 47
				0004	0040	0040
				URBAN	URBAN	URBAN
50300225	CONCRETE STRUCTURES	CU YD	900		283	617
50300285	FORM LINER TEXTURED SURFACE	SQ FT	4,263		4,263	
50300300	PROTECTIVE COAT	SQ YD	611		611	
50500505	STUD SHEAR CONNECTORS	EACH	1,548		1,548	
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	96,760		25,810	70,950
50800515	BAR SPLICERS	EACH	12			12
50901750	PARAPET RAILING	FOOT	344		344	
5422C030	PIPE CULVERTS, CLASS C, TYPE 2, 30" (TEMPORARY)	FOOT	38	38		
5422C036	PIPE CULVERTS, CLASS C, TYPE 2, 36" (TEMPORARY)	FOOT	12	12		
5422C048	PIPE CULVERTS, CLASS C, TYPE 2, 48" (TEMPORARY)	FOOT	109	109		
550A0190	STORM SEWERS, CLASS A, TYPE 1, 48"	FOOT	40	40		
550A0450	STORM SEWERS, CLASS A, TYPE 2, 36"	FOOT	499	499		
550A0470	STORM SEWERS, CLASS A, TYPE 2, 42"	FOOT	16	16		
550A0480	STORM SEWERS, CLASS A, TYPE 2, 48"	FOOT	516	516		

URBAN

* SPECIALTY ITEM

USER NAME * #USER*	DESIGNED - DMS	REVISED - 04-06-2012	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES			F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
DESIGNED - KEA	REVISED -	338/IL 59					2011-035-1	DUPAGE	181	5	
PLOT SCALE * #SCALE*	CHECKED - PJO	REVISED -		SCALE:	SHEET NO. 1 OF 6 SHEETS	STA.	TO STA.	CONTRACT NO. 60P41			
PLOT DATE * #DATE*	DATE - 03-22-2012	REVISED -		ILLINOIS FED. AID PROJECT							