

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE		
				80% FED 20% STATE	80% FED 20% STATE	80% FED 20% STATE
				ROADWAY AND DRAINAGE	RETAINING WALL SN 022-W045	PUMP STATION 47
				0004	0040	0040
				URBAN	URBAN	URBAN
550B0380	STORM SEWERS, CLASS B, TYPE 2, 18"	FOOT	7	7		
550B0430	STORM SEWERS, CLASS B, TYPE 2, 30"	FOOT	24	24		
550B0450	STORM SEWERS, CLASS B, TYPE 2, 36"	FOOT	29	29		
55100500	STORM SEWER REMOVAL, 12"	FOOT	10	10		
55100900	STORM SEWER REMOVAL, 18"	FOOT	10	10		
55101400	STORM SEWER REMOVAL, 30"	FOOT	566	566		
55101600	STORM SEWER REMOVAL, 36"	FOOT	647	647		
* 55201600	STORM SEWERS JACKED IN PLACE, 48"	FOOT	110	110		
59100100	GEOCOMPOSITE WALL DRAIN	SQ YD	543		543	
59300100	CONTROLLED LOW-STRENGTH MATERIAL	CU YD	129			129
60221100	MANHOLES, TYPE A, 5' -DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	5	5		
60223800	MANHOLES, TYPE A, 6' -DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	1	1		
60224445	MANHOLES, TYPE A, 7' -DIAMETER, TYPE 1 FRAME, OPEN LID	EACH	5	5		
60224446	MANHOLES, TYPE A, 7' -DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	2	2		

* SPECIALTY ITEM

URBAN

USER NAME = #USER#	DESIGNED - DHS	REVISED - 04-06-2012
	DRAWN - KEA	REVISED -
PLOT SCALE = #SCALE#	CHECKED - PJO	REVISED -
PLOT DATE = #DATE#	DATE - 03-22-2012	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: SHEET NO. 1 OF 6 SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
338/IL 59	2011-035-I	DUPAGE	181	6
CONTRACT NO. 60P41			ILLINOIS FED. AID PROJECT	