

TOP SOIL FURNISH AND PLACE 2"			
FROM STA	TO STA	LT/RT	QUANTITY (SQ YD)
RESTORATION:			
3958+35	3959+00	LT	219
3959+32	3964+38	LT	1034
PROJECT TOTAL			1253

SEEDING, CLASS 2A		
FROM STA	TO STA	AREA (AC)
3958+35	3959+00	0.05
3959+32	3964+38	0.21
PROJECT TOTAL		0.26

MULCH METHOD 2			
FROM STA	TO STA	LT/RT	QUANTITY (AC)
RESTORATION:			
3958+35	3959+00	LT	0.05
3959+32	3964+38	LT	0.21
PROJECT TOTAL			0.26

TEMPORARY EROSION CONTROL SEEDING			
FROM STA	TO STA	AREA (AC)	QUANTITY (POUND)
3958+35	3959+00	0.05	5
3959+32	3964+38	0.21	21
PROJECT TOTAL			26

PERIMETER EROSION BARRIER				
FROM		TO		QUANTITY (FOOT)
STATION	O/S	STATION	O/S	
3958+35	35' LT	3958+53	54' LT	18
3959+33	54' LT	3964+21	38' LT	488
3958+41	68' LT	3960+03	100' LT	188
3960+24	90' LT	3964+27	132' LT	410
PROJECT TOTAL				1104

INLET FILTERS			
STATION	OFFSET	LT/RT	QUANTITY (EACH)
3960+41	47.3'	LT	1
3961+32	42.1'	LT	1
3962+22	36.6'	LT	1
3963+01	35.4'	LT	1
3963+81	35.1'	LT	1
PROJECT TOTAL			5

PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH			
FROM STA	TO STA	LT/RT	QUANTITY (SQ YD)
20+57	25+07		942.7
PROJECT TOTAL			942.7

CLASS C PATCHES, TYPE IV, 10"			
FROM STA	TO STA	LT/RT	QUANTITY (SQ YD)
3963+61	3964+21	LT	27
PROJECT TOTAL			27

DRIVEWAY PAVEMENT REMOVAL			
FROM STA	TO STA	LT/RT	QUANTITY (SQ YD)
3958+82	3963+92		704
PROJECT TOTAL			704

COMBINATION CURB AND GUTTER REMOVAL			
FROM STA	TO STA	LT/RT	QUANTITY (FOOT)
3963+60	3964+20	LT	60
PROJECT TOTAL			60

STORM SEWERS													
FROM STA	TO STA	PIPE NO.	LT/RT	QUANTITY (FT)								JACKED IN PLACE, 48"	TRENCH BACKFILL
				CLASS A, TYPE 1 48"	CLASS A, TYPE 2 36"	CLASS A, TYPE 2 42"	CLASS A, TYPE 2 48"	CLASS B, TYPE 2 18"	CLASS B, TYPE 2 30"	CLASS B, TYPE 2 36"			
STAGE 1													
3958+45	3958+73	102	LT									29	
3958+73	3962+96	103	LT				413						434
STAGE 2													
3964+08	3964+20	206	LT					7					3
3958+53	3958+76	201	LT						24				
3958+76	3963+05	202	LT		420								291
3963+05	3963+37	203	LT		36								34
3963+37	3963+59	203A	LT		19								19
3963+76	3964+08	205	LT		24								37
3963+76	3963+76	204	LT			16							27
STAGE 3													
3965+23	3965+67	303C	LT	40									
3962+96	3963+30	300	LT				34						47
3963+30	3963+60	301	LT				51						74
3963+60	3963+98	302	LT				11						16
3963+98	3964+05	303A	LT				7						7
3964+08	3965+23	303B	LT									110	
PROJECT TOTAL				40	499	16	516	7	24	29	110	989	

STORM SEWER REMOVAL						
FROM STA	TO STA	LT/RT	QUANTITY (FOOT)			
			12"	18"	30"	36"
STAGE 1						
3958+50	3961+21	LT			266	
3961+21	3963+92	LT			265	
3963+92	3964+29	LT			35	
3958+43	3958+45	LT				3
3958+45	3959+73	LT				126
3959+73	3962+53	LT				271
3962+53	3963+53	LT				97
3963+53	3963+52	LT				39
3963+52	3964+09	LT				57
3964+09	3964+10	LT				41
STAGE 2						
3963+68	3963+81	LT	10			
3964+08	3964+20	LT		10		
3964+08	3964+08	LT				8
STAGE 3						
3964+08	3964+08	LT				5
PROJECT TOTAL			10	10	566	647

PIPE CULVERT, CLASS C (TEMPORARY)						
FROM STA	TO STA	PIPE NO.	LT/RT	QUANTITY (FOOT)		
				TYPE 2 30"	TYPE 2 36"	TYPE 2 48"
3964+09	3964+23	107	LT	7		
3964+23	3964+25	108	LT	31		
3964+09	3964+10	109	LT		12	
3962+96	3963+04	104	LT			14
3963+04	3963+60	105	LT			52
3963+60	3964+09	106	LT			43
PROJECT TOTAL				38	12	109

AGGREGATE SHOULDERS TYPE A, 6"			
FROM STA	TO STA	LT/RT	QUANTITY (SQ YD)
21+28	25+27		622
PROJECT TOTAL			622

REMOVING MANHOLES			
STATION	OFFSET	LT/RT	QUANTITY (EACH)
STAGE 1			
3959+73	69.5'	LT	1
3961+21	69.5'	LT	1
3962+53	87.4'	LT	1
3963+92	70.1'	LT	1
3964+23	85.9'	LT	1
STAGE 2			
3963+81	35.1'	LT	1
STAGE 3			
3964+10	91.9'	LT	1
3965+64	69.4'	LT	1
PROJECT TOTAL			8

COMBINATION CURB & GUTTER, TYPE B-6.18			
FROM STA	TO STA	LT/RT	QUANTITY (FOOT)
3963+60	3964+20	LT	60
PROJECT TOTAL			60

TEMPORARY CONCRETE BARRIER			
FROM STA	TO STA	LT/RT	QUANTITY (FT)
3959+50	3967+00	LT	750
PROJECT TOTAL			750

USER NAME : *USER*	DESIGNED - <i>DMS</i>	REVISED -
	DRAWN - <i>KEA</i>	REVISED -
PLOT SCALE : *SCALE*	CHECKED - <i>PJO</i>	REVISED -
PLOT DATE : *DATE*	DATE - <i>03-22-2012</i>	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SCHEDULE OF QUANTITIES	
SCALE:	SHEET NO. 1 OF 2 SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
338/IL 59	2011-035-I	DUPAGE	181	7
CONTRACT NO. 60P41			ILLINOIS FED. AID PROJECT	