

SUMMARY OF QUANTITIES			URBAN		CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	ROADWAY 0004	TRAFFIC SIGNALS 0021				
44000200	DRIVEWAY PAVEMENT REMOVAL	SO YD	300	300					
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	156	156					
44201803	CLASS D PATCHES, TYPE II, 13 INCH	SO YD	100	100					
44201807	CLASS D PATCHES, TYPE III, 13 INCH	SO YD	100	100					
44201809	CLASS D PATCHES, TYPE IV, 13 INCH	SO YD	200	200					
44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	1865	1865					
48101500	AGGREGATE SHOULDERS, TYPE B 6"	SO YD	877	877					
48203029	HOT-MIX ASPHALT SHOULDERS, 8"	SO YD	704	704					
50104400	CONCRETE HEADWALL REMOVAL	EACH	2	2					
50105220	PIPE CULVERT REMOVAL	FOOT	144	144					
54213657	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 12"	EACH	2	2					
54213660	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 15"	EACH	4	4					
54214713	PRECAST REINFORCED CONCRETE FLARED END SECTIONS - ELLIPTICAL, EQUIVALENT ROUND-SIZE 18"	EACH	2	2					

SUMMARY OF QUANTITIES			URBAN		CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	ROADWAY 0004	TRAFFIC SIGNALS 0021				
542A0217	PIPE CULVERTS, CLASS A, TYPE 1 12"	FOOT	26.5	26.5					
542A0220	PIPE CULVERTS, CLASS A, TYPE 1 15"	FOOT	52	52					
542A5473	PIPE CULVERTS, CLASS A, TYPE 1 EQUIVALENT ROUND-SIZE 18"	FOOT	38	38					
550A0050	STORM SEWERS, CLASS A, TYPE 1 12"	FOOT	6	6					
55100500	STORM SEWER REMOVAL 12"	FOOT	12	12					
60100060	CONCRETE HEADWALLS FOR PIPE DRAINS	EACH	2	2					
60107600	PIPE UNDERDRAINS 4"	FOOT	400	400					
60108100	PIPE UNDERDRAINS 4" (SPECIAL)	FOOT	30	30					
60200105	CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, OPEN LID	EACH	3	3					
60201340	CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 24 FRAME AND GRATE	EACH	1	1					
60206905	CATCH BASINS, TYPE C, TYPE 1 FRAME, OPEN LID	EACH	2	2					
60208240	CATCH BASINS, TYPE C, TYPE 24 FRAME AND GRATE	EACH	2	2					
60500050	REMOVING CATCH BASINS	EACH	3	3					

FILE NAME =	USER NAME = gulloume1p	DESIGNED -	REVISED -	STATE OF ILLINOIS	SUMMARY OF QUANTITIES	F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
2711	27-N-2	LAKE	53			4				
SHEET NO. OF SHEETS STA. TO STA.		CONTRACT NO. 60P63								
PLOT SCALE = 100,000' / 1"		FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT								
PLOT DATE = 4/3/2012										