

SCHEDULE OF QUANTITIES

DESIGNATION	UNIT	TOTAL QUANTITY
ELECTRIC SERVICE INSTALLATION	EACH	1
ELECTRIC UTILITY SERVICE CONNECTION	L SUM	1
UNDERGROUND CONDUIT, GALVANIZED STEEL, 3" DIA.	FOOT	222
UNIT DUCT, 600V, 2-1C NO.6, 1/C NO.8 GROUND, (XLP-TYPE USE), 1" DIA. POLYETHYLENE	FOOT	385
UNIT DUCT, 600V, 3-1C NO.6, 1/C NO.8 GROUND, (XLP-TYPE USE), 1" DIA. POLYETHYLENE	FOOT	2700
LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, 400 WATT	EACH	12
LIGHTING CONTROLLER, PEDESTAL MOUNTED, 240VOLT, 60AMP	EACH	1
LIGHT POLE, ALUMINUM, 47.5 FT. M.H., 15 FT. MAST ARM	EACH	12
LIGHT POLE FOUNDATION, 24" DIAMETER	FOOT	108
BREAKAWAY DEVICE, TRANSFORMER BASE, 15 INCH BOLT CIRCLE	EACH	12
REMOVAL OF POLE FOUNDATION	EACH	3
RELOCATE EXISTING LIGHTING UNIT	EACH	3
* MAINTENANCE OF LIGHTING SYSTEM	CAL MO	4
* LIGHT POLE FOUNDATION, SPECIAL	FOOT	27
* LUMINAIRE SAFETY CABLE ASSEMBLY	EACH	12

\* DESIGNATES SPECIAL PROVISIONS

FILE NAME = k:\projects\projects 2011\millena\_various\ill rte 72 at beverly rd\160P90-Lighting 2.dgn  
 USER NAME = BUSENAME



GANDHI AND ASSOCIATES, INC.  
 ENGINEERS AND PLANNERS  
 6035 N. NORTHWEST HIGHWAY  
 SUITE 306  
 CHICAGO, ILLINOIS 60631 TEL. (773) 774-5910

DESIGNED - SM	REVISED -
DRAWN - SM	REVISED -
CHECKED - PKG/MA	REVISED -
DATE - 4/30/2012	REVISED -

**STATE OF ILLINOIS  
 DEPARTMENT OF TRANSPORTATION**

**IL 72 - HIGGINS RD  
 AT BEVERLY RD AND AT ROCK ROAD DR**

**SCHEDULE OF QUANTITIES**

SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
341	2011-071-N	COOK/KANE	56	35
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT			CONTRACT NO. 60P90	

k:\projects\projects 2011\millena\_various\ill rte 72 at beverly rd\160P90-Lighting 2.dgn