

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE										
				ILL. ROUTE 21 (MILWAUKEE AVE.) AT ILL. ROUTE 43 (HARLEM AVE.)	ILL. ROUTE 21 (MILWAUKEE AVE.) AT HOWARD ST.	ILL. ROUTE 43 (HARLEM AVE.) AT HOWARD ST.	ILL. ROUTE 21 (MILWAUKEE AVE.) AT OAKTON ST.	ILL. ROUTE 21 (MILWAUKEE AVE.) AT MAIN ST.	ILL. ROUTE 43 (HARLEM AVE.) AT OAKTON ST.	ILL. ROUTE 43 (OAKTON ST.) AT ILL. ROUTE 43 (WAUKEGAN RD.)	US ROUTE 14 (CADWELL AVE.) AT OAKTON ST.	INTERCONNECT	ILL. ROUTE 21 (MILWAUKEE AVE.) AT MAIN ST. LIGHTING	
				90% FEDERAL 10% STATE	90% FEDERAL 5% STATE 2.5% CITY 2.5% VILLAGE	90% FEDERAL 5% STATE 1.25% CITY 3.75% VILLAGE	90% FEDERAL 10% STATE	90% FEDERAL 5% STATE 5% VILLAGE	90% FEDERAL 10% STATE	90% FEDERAL 10% STATE	90% FEDERAL 10% STATE	90% FEDERAL 10% STATE	90% FEDERAL 10% STATE	90% FEDERAL 10% STATE
				0021 URBAN	0021 URBAN	0021 URBAN	0021 URBAN	0021 URBAN	0021 URBAN	0021 URBAN	0021 URBAN	0021 URBAN	0021 URBAN	0021 URBAN
78300100	PAVEMENT MARKING REMOVAL	50 FT	5897	469	458	608	-	-	1803	1857	702	-	-	
80500020	SERVICE INSTALLATION - POLE MOUNTED	EACH	6	1	1	1	1	-	1	-	1	-	-	
81028200	UNDERGROUND CONDUIT, GALVANIZED STEEL, 2" DIA.	FOOT	8152	1187	654	1099	1251	763	1283	-	1111	496	308	
81028210	UNDERGROUND CONDUIT, GALVANIZED STEEL, 2 1/2" DIA.	FOOT	477	78	16	7	58	56	103	66	93	-	-	
81028220	UNDERGROUND CONDUIT, GALVANIZED STEEL, 3" DIA.	FOOT	624	126	33	85	64	59	86	30	141	-	-	
81028240	UNDERGROUND CONDUIT, GALVANIZED STEEL, 4" DIA.	FOOT	3507	750	389	264	546	315	613	-	630	-	-	
81100600	CONDUIT ATTACHED TO STRUCTURE, 2" DIA. GALVANIZED STEEL	FOOT	128	-	-	-	-	-	-	-	128	-	-	
81400100	HANDHOLE	EACH	43	7	6	7	5	5	6	-	7	-	-	
81400200	HEAVY-DUTY HANDHOLE	EACH	24	2	2	3	5	4	4	-	4	-	-	
81400300	DOUBLE HANDHOLE	EACH	16	3	2	2	3	1	3	-	2	-	-	
81702415	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 3-1/C NO. 6	FOOT	877	-	-	-	-	-	-	-	-	-	877	
81800200	AERIAL CABLE, 2-1/C NO. 4 WITH MESSENGER WIRE	FOOT	542	-	-	-	-	-	-	-	-	-	542	
82102250	LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, 250 WATT	EACH	2	-	-	-	-	-	-	-	-	-	2	
85000200	MAINTENANCE OF EXISTING TRAFFIC SIGNAL INSTALLATION	EACH	2	-	-	-	-	-	-	-	-	2	-	
85700200	FULL- ACTUATED CONTROLLER AND TYPE IV CABINET	EACH	2	1	-	1	-	-	-	-	-	-	-	
85700300	FULL- ACTUATED CONTROLLER AND TYPE V CABINET	EACH	1	-	1	-	-	-	-	-	-	-	-	
86000100	MASTER CONTROLLER	EACH	1	-	-	-	-	-	-	-	-	1	-	
86000105	MASTER CONTROLLER (SPECIAL)	EACH	1	-	-	-	-	-	-	-	-	1	-	
86400100	TRANSCEIVER - FIBER OPTIC	EACH	8	1	1	1	1	1	1	1	1	-	-	
87300925	ELECTRIC CABLE IN CONDUIT, TRACER, NO. 14 1C	FOOT	10463	-	-	-	-	-	-	-	-	10463	-	
87301215	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 2C	FOOT	10832	2071	1151	1158	1625	1266	1820	1741	-	-	-	
87301225	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 3C	FOOT	15130	2386	1567	1496	2038	1596	2393	2523	1131	-	-	
87301245	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 5C	FOOT	15099	2882	1868	1485	1947	1172	1757	769	3219	-	-	
87301255	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 7C	FOOT	13193	1419	702	1165	1848	1498	2463	2039	2059	-	-	
87301305	ELECTRIC CABLE IN CONDUIT, LEAD-IN, NO. 14 1 PAIR	FOOT	21624	4136	1972	2681	3902	2539	3056	-	3338	-	-	
87301805	ELECTRIC CABLE IN CONDUIT, SERVICE, NO. 6 2C	FOOT	747	228	32	132	160	44	113	-	38	-	-	
87301900	ELECTRIC CABLE IN CONDUIT, GROUNDING, NO. 6 1C EQUIPMENT CONDUCTOR	FOOT	6703	1033	498	650	915	625	996	1061	925	-	-	
87502440	TRAFFIC SIGNAL POST, GALVANIZED STEEL 10 FT.	EACH	2	1	1	-	-	-	-	-	-	-	-	
87502480	TRAFFIC SIGNAL POST, GALVANIZED STEEL 14 FT.	EACH	3	-	1	-	-	-	-	1	1	-	-	
87502500	TRAFFIC SIGNAL POST, GALVANIZED STEEL 16 FT.	EACH	20	2	-	1	4	4	4	3	2	-	-	
87502520	TRAFFIC SIGNAL POST, GALVANIZED STEEL 18 FT.	EACH	2	2	-	-	-	-	-	-	-	-	-	
87700150	STEEL MAST ARM ASSEMBLY AND POLE, 22 FT.	EACH	1	1	-	-	-	-	-	-	-	-	-	

FILE NAME =	USER NAME = .GAL	DESIGNED - MA, PKG	REVISED -
#FILE#		DRAWN - EA, SM, MG	REVISED -
	PLOT SCALE = 9SCALE	CHECKED - PKG	REVISED -
	PLOT DATE = 3/23/2012	DATE - 03/21/2012	REVISED -

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES (SHEET 2 OF 5)			
SCALE: NONE	SHEET NO. OF SHEETS	STA.	TO STA.

RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
3513	2011-210-TS	COOK	089	004
FINAL			CONTRACT NO. 60R44	
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT				