

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE										
				ILL. ROUTE 21 (MILWAUKEE AVE.) AT ILL. ROUTE 43 (HARLEM AVE.)	ILL. ROUTE 21 (MILWAUKEE AVE.) AT HOWARD ST.	ILL. ROUTE 43 (HARLEM AVE.) AT HOWARD ST.	ILL. ROUTE 21 (MILWAUKEE AVE.) AT OAKTON ST.	ILL. ROUTE 21 (MILWAUKEE AVE.) AT MAIN ST.	ILL. ROUTE 43 (HARLEM AVE.) AT OAKTON ST.	ILL. ROUTE 43 (OAKTON ST.) AT ILL. ROUTE 43 (WAUKEGAN RD.)	US ROUTE 14 (CADWELL AVE.) AT OAKTON ST.	INTERCONNECT	ILL. ROUTE 21 (MILWAUKEE AVE.) AT MAIN ST. LIGHTING	
				90% FEDERAL 10% STATE	90% FEDERAL 5% STATE 2.5% CITY 2.5% VILLAGE	90% FEDERAL 5% STATE 1.25% CITY 3.75% VILLAGE	90% FEDERAL 10% STATE	90% FEDERAL 5% STATE 5% VILLAGE	90% FEDERAL 10% STATE	90% FEDERAL 10% STATE	90% FEDERAL 10% STATE	90% FEDERAL 10% STATE	90% FEDERAL 10% STATE	90% FEDERAL 10% STATE
				0021 URBAN	0021 URBAN	0021 URBAN	0021 URBAN	0021 URBAN	0021 URBAN	0021 URBAN	0021 URBAN	0021 URBAN	0021 URBAN	0021 URBAN
88060180	COMBINATION SIGNAL HEAD, LED, 2- FACE, 1- 5 SECTION OPTICALLY PROGRAMMED, 1- 3 SECTION, BRACKET MOUNTED	EACH	2	2	-	-	-	-	-	-	-	-	-	-
88102717	PEDESTRIAN SIGNAL HEAD, LED, 1-FACE, BRACKET MOUNTED WITH COUNTDOWN TIMER	EACH	33	6	2	2	8	4	7	4	-	-	-	
88102747	PEDESTRIAN SIGNAL HEAD, LED, 2-FACE, BRACKET MOUNTED WITH COUNTDOWN TIMER	EACH	9	1	3	3	-	2	-	-	-	-	-	
88102757	PEDESTRIAN SIGNAL HEAD, LED, 3-FACE, BRACKET MOUNTED WITH COUNTDOWN TIMER	EACH	5	-	-	-	-	-	1	4	-	-	-	
88200210	TRAFFIC SIGNAL BACKPLATE, LOUVERED, ALUMINUM	EACH	93	10	11	13	12	10	12	13	12	-	-	
88500100	INDUCTIVE LOOP DETECTOR	EACH	80	10	8	11	12	10	9	11	9	-	-	
88600100	DETECTOR LOOP, TYPE I	FOOT	4678	625	654	676	648	756	704	-	615	-	-	
88700200	LIGHT DETECTOR	EACH	16	2	2	2	2	2	2	-	4	-	-	
88700300	LIGHT DETECTOR AMPLIFIER	EACH	7	1	1	1	1	1	1	-	1	-	-	
88800100	PEDESTRIAN PUSH-BUTTON	EACH	61	8	8	8	8	8	9	12	-	-	-	
89000100	TEMPORARY TRAFFIC SIGNAL INSTALLATION	EACH	7	1	1	1	1	1	1	-	1	-	-	
89501400	RELOCATE EXISTING EMERGENCY VEHICLE PRIORITY SYSTEM, DETECTOR UNIT	EACH	1	-	-	-	-	-	-	1	-	-	-	
89501410	RELOCATE EXISTING EMERGENCY VEHICLE PRIORITY SYSTEM, PHASING UNIT	EACH	1	-	-	-	-	-	-	1	-	-	-	
89502300	REMOVE ELECTRIC CABLE FROM CONDUIT	FOOT	18287	-	-	-	-	-	-	3880	-	13862	545	
89502375	REMOVE EXISTING TRAFFIC SIGNAL EQUIPMENT	EACH	8	1	1	1	1	1	1	1	1	-	-	
89502376	REBUILD EXISTING HANDHOLE	EACH	1	-	-	-	-	-	1	-	-	-	-	
89502380	REMOVE EXISTING HANDHOLE	EACH	65	8	5	6	9	10	13	-	14	-	-	
89502382	REMOVE EXISTING DOUBLE HANDHOLE	EACH	9	1	1	1	3	1	1	-	1	-	-	
89502385	REMOVE EXISTING CONCRETE FOUNDATION	EACH	66	9	9	9	9	9	9	3	9	-	-	
X0324085	EMERGENCY VEHICLE PRIORITY SYSTEM LINE SENSOR CABLE, NO. 20 3/C	FOOT	3212	259	237	282	357	275	394	277	1131	-	-	
X0326148	TEMPORARY WOOD POLE, 60 FT., CLASS 4, 15 FT. MAST ARM	EACH	1	-	-	-	-	-	-	-	-	-	1	
X4402020	CONCRETE MEDIAN SURFACE REMOVAL	SO FT	2026	-	-	-	-	-	478	1111	437	-	-	
X4403300	CONCRETE MEDIAN REMOVAL	SO FT	126	-	-	-	-	-	126	-	-	-	-	
X8100863	INTERCEPT EXISTING CONDUIT	EACH	4	-	-	-	-	-	-	-	-	-	4	
X8210005	TEMPORARY LUMINAIRE, HIGH PRESSURE SODIUM VAPOR, HORIZONTAL MOUNT, 250 WATT	EACH	2	-	-	-	-	-	-	-	-	-	2	
X8570226	FULL-ACTUATED CONTROLLER CABINET, TYPE IV, SPECIAL	EACH	4	-	-	-	1	1	1	-	1	-	-	
X8570231	FULL-ACTUATED CONTROLLER CABINET, TYPE V, SPECIAL	EACH	1	-	-	-	-	-	-	1	-	-	-	
X8620200	UNINTERRUPTIBLE POWER SUPPLY, SPECIAL	EACH	8	1	1	1	1	1	1	1	1	-	-	

100% COST TO VILLAGE OF NILES

FILE NAME =	USER NAME = GAI.	DESIGNED - MA, PKG	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>SUMMARY OF QUANTITIES (SHEET 4 OF 5)</b>				F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
#FILE#	PLOT SCALE = #SCALE#	DRAWN - EA, SM, MG	REVISED -						3513	2011-210-TS	COOK	089	006
	PLOT DATE = 3/22/2012	CHECKED - PKG	REVISED -		SCALE: NONE SHEET NO. OF SHEETS STA. TO STA.				FED. ROAD DIST. NO. - [ILLINOIS] FED. AID PROJECT				
		DATE - 03/21/2012	REVISED -						CONTRACT NO. 60R44				