

SUMMARY OF QUANTITIES				CONSTRUCTION CODE								
				GOLF ROAD AT LAWLER AVENUE	GOLF ROAD AT LAVERGNE AVENUE	GROSS POINT ROAD AT CHURCH STREET	U.S. RTE 41 (SKOKIE BOULEVARD) AT CHURCH STREET	U.S. RTE 41 (SKOKIE BOULEVARD) AT GROSS POINT ROAD	INTERCONNECT	LIGHTING - GROSS POINT ROAD AT CHURCH STREET	LIGHTING - U.S. RTE 41 (SKOKIE BOULEVARD) AT GROSS POINT ROAD	
CODE NO.	ITEM	UNIT	TOTAL	90% FEDERAL 5% STATE 5% VILLAGE OF SKOKIE	90% FEDERAL 5% STATE 5% VILLAGE OF SKOKIE	90% FEDERAL 5% STATE 5% VILLAGE OF SKOKIE	90% FEDERAL 10% STATE	90% FEDERAL 10% STATE	90% FEDERAL 10% STATE	90% FEDERAL 10% VILLAGE OF SKOKIE	90% FEDERAL 10% VILLAGE OF SKOKIE	
				TRAFFIC SIGNALS 0021 URBAN	TRAFFIC SIGNALS 0021 URBAN	TRAFFIC SIGNALS 0021 URBAN	TRAFFIC SIGNALS 0021 URBAN	TRAFFIC SIGNALS 0021 URBAN	INTERCONNECT 0021 URBAN	LIGHTING 0021 URBAN	LIGHTING 0021 URRBAN	
89000100	TEMPORARY TRAFFIC SIGNAL INSTALLATION	EACH	5	1	1	1	1	1				
89502300	REMOVE ELECTRIC CABLE FROM CONDUIT	FOOT	9,306						3,990	3,400	1,916	
89502375	REMOVE EXISTING TRAFFIC SIGNAL EQUIPMENT	EACH	5	1	1	1	1	1				
89502380	REMOVE EXISTING HANDHOLE	EACH	49	11	8	10	10	10				
89502385	REMOVE EXISTING CONCRETE FOUNDATION	EACH	41	9	6	8	9	9				
*X0324085	EMERGENCY VEHICLE PRIORITY SYSTEM LINE SENSOR CABLE, NO. 20 3/C	FOOT	1,879	413	536	335	248	347				
X0324599	ROD AND CLEAN EXISTING CONDUIT	FOOT	1,358						1,358			
X8570226	FULL-ACTUATED CONTROLLER AND TYPE IV CABINET, SPECIAL	EACH	5	1	1	1	1	1				
X8620200	UNINTERRUPTABLE POWER SUPPLY, SPECIAL	EACH	5	1	1	1	1	1				
X8710024	FIBER OPTIC CABLE IN CONDUIT, NO. 62.5/125, MM12F SM24F	FOOT	3,627						3,627			
Z0007430	TEMPORARY SIDEWALK	SQ FT	5,155	655	500	1,700	1,500	800				
Z0030850	TEMPORARY INFORMATION SIGNING	SQ FT	257.00	51.40	51.40	51.40	51.40	51.40				
Z0033020	LUMINAIRE SAFETY CABLE ASSEMBLY	EACH	7							4	3	
Z0033028	MAINTENANCE OF LIGHTING SYSTEM	CAL MO	3							1.5	1.5	
Z0033040	ELECTRIC SERVICE DISCONNECT, LIGHTING AND TRAFFIC SIGNAL	EACH	2			1		1				
Z0033044	RE-OPTIMIZE TRAFFIC SIGNAL SYSTEM LEVEL 1	EACH	5						5			
Z0073510	TEMPORARY TRAFFIC SIGNAL TIMING	EACH	5	1	1	1	1	1				
X8250505	LIGHTING CONTROLLER, SPECIAL	EACH	2							1	1	
81301900	ELECTRIC CABLE IN CONDUIT, GROUNDING, NO. 6 1C EQUIPMENT CONDUCTOR,	FOOT	3,006	525	598	680	517	686				

\* 100% OF THE COST SHALL BE PAID BY VILLAGE OF SKOKIE (07POL, 01, 0021) \*\* SPECIALTY ITEM

\* 66900200 NON-SPECIAL WASTE DISPOSAL CUYD 18 7 11  
 \*\* 66900450 SPECIAL WASTE PLANS AND REPORTS LSUM 1 0.20 0.20 0.20 0.20 0.20  
 \*\* 66900530 SOIL DISPOSAL ANALYSIS EACH 3 1 2

FILE NAME = 4085.877 - TR1.dwg

USER NAME = ZACH WALLSTEN  
 DESIGNED - JRD  
 DRAWN - ZCW  
 CHECKED - KLB  
 PLOT SCALE = 1" = .0833'  
 PLOT DATE = 3/22/2012

REVISED -  
 REVISED -  
 REVISED -  
 REVISED -

STATE OF ILLINOIS  
 DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES  
 (SHEET 5 OF 5)

SCALE N.A. SHEET NO. OF SHEETS STA. TO STA.

FILE # 4085.877  
 SECTION 2011-209-TS  
 COUNTY COOK  
 SHEET NO. 52  
 SHEET NO. 7  
 CONTRACT # 60R47  
 ILLINOIS FED. AID PROJECT

Rev. 6-1-12