SUMMARY OF QUANTITIES

CODE NO	ITEM	UNIT	URBAN TOTAL QUANTITIES	CONSTRUCTION TYPE CODE 100% STATE 0005					
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	18	18					
40600300	AGGREGATE (PRIME COAT)	TON	87	87					
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	66	66					
40600895	CONSTRUCTING TEST STRIP	EACH	1	1					
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	1305	1305					
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	4872	4872					
44000157	HOT-MIX ASPHALT SURFACE REMOVAL, 2"	SQ YD	43496	43496					
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6					
67100100	MOBILIZATION	L SUM	1	1					
70300100	SHORT TERM PAVEMENT MARKING	FOOT	5348	5348					
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	1783	1783					
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	1290	1290					
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	53710	53710					

SUMMARY OF QUANTITIES

CODE NO	ITEM	UNIT	URBAN TOTAL QUANTITIES	CONSTRUCTION TYPE CODE 100% STATE 0005					
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	5110	5110					
* 78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	530	530					
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	750	750					
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	846	846					
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	2368	2368					
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	2368	2368					
* 88600600	DETECTOR LOOP REPLACEMENT	FOOT	1297	1297					
Z0030850	TEMPORARY INFORMATION SIGNING	SQ FT	1080	1080					

* SPECIALTY ITEM

FILE NAME = c:\pw_work\pwidot\pencept\d0303602\D395l2-Design.dgn	USER NAME = pencept	DESIGNED -	REVISED -
		DRAWN -	REVISED -
	PLOT SCALE = 100.0000 ' / in.	CHECKED -	REVISED -
	PLOT DATE = 4/5/2012	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: | SHEET NO. OF SHEETS | STA. TO STA.

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
VAR.	2012-011 RS	LAKE	30	3

CONTRACT NO. 60T57

FED. ROAD DIST. NO. 1 | ILLINOIS | FED. AID PROJECT