

DATE _____ BY _____
 SURVEYED _____ PLOTTED _____
 FINAL SURVEY _____ NOTE BOOK _____
 NO. _____

DATE _____ BY _____
 SURVEYED _____ PLOTTED _____
 ORIGINAL SURVEY _____ NOTE BOOK _____
 NO. _____

INDEX TO SCHEDULES OF QUANTITIES		
NO.	DESCRIPTION	SHEET NO.
1	SCHEDULE OF EROSION CONTROL ITEMS	16
2	SCHEDULE OF AGGREGATE BASE COURSE	16
3	SCHEDULE OF BITUMINOUS MATERIALS (PRIME COAT)	16
4	SCHEDULE OF SEEDING	16
5	SCHEDULE OF HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N50	16
6	SCHEDULE OF HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N70	17
7	SCHEDULE OF TOPSOIL FURNISH AND PLACE	17
8	SCHEDULE OF HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	17
9	SCHEDULE OF HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	17
10	SCHEDULE OF TEMPORARY PAVEMENT	17
11	SCHEDULE OF SEDIMENT CONTROL, DRAINAGE STRUCTURE INLET FILTER CLEANING	17
12	SCHEDULE OF RAISED REFLECTIVE PAVEMENT MARKERS	17
13	SCHEDULE OF COMBINATION CURB AND GUTTER, TYPE B-6.24	17
14	SCHEDULE OF STORM SEWER REMOVAL AND TRENCH BACKFILL	17
15	SCHEDULE OF EARTH EXCAVATION AND FURNISHED EXCAVATION	18-21
16	SCHEDULE OF CONCRETE CURB, TYPE B	22
17	SCHEDULE OF CATCH BASINS	22
18	SCHEDULE OF PROTECTIVE COAT	22
19	SCHEDULE OF TREE REMOVAL	22
20	SCHEDULE OF PRECAST REINFORCED CONCRETE FLARED END SECTIONS	22
21	SCHEDULE OF STORM SEWERS AND TRENCH BACKFILL	23
22	SCHEDULE OF PIPE UNDERDRAINS	23
23	SCHEDULE OF DRAINAGE STRUCTURES TO BE CLEANED	23
24	SCHEDULE OF CLEANING DRAINAGE SYSTEM	23
25	SCHEDULE OF DRIVEWAY PAVEMENT REMOVAL	23
26	SCHEDULE OF TEMPORARY PAVEMENT MARKING	24
27	SCHEDULE OF INLETS	24
28	SCHEDULE OF PERMANENT PAVEMENT MARKINGS	24
29	SCHEDULE OF AGGREGATE SUBGRADE	24
30	SCHEDULE OF MANHOLES	24
31	SCHEDULE OF STONE RIPRAP AND FILTER FABRIC	24
32	SCHEDULE OF ITEMS TO BE REMOVED	24
33	SCHEDULE OF GRATING FOR CONCRETE FLARED END SECTIONS	25
34	SCHEDULE OF ITEMS TO BE ADJUSTED	25
35	SCHEDULE OF PAVEMENT MARKING TAPE	25
36	SCHEDULE OF REMOVAL ITEMS	25
37	SCHEDULE OF PAVEMENT MARKING REMOVAL	25
38	SCHEDULE OF MEDIAN ITEMS	25

2		SCHEDULE OF AGGREGATE BASE COURSE		
		(35100300) TYPE A 4"	(35100500) TYPE A 6"	(35100700) TYPE A 8"
FROM	TO	(SQ YD)	(SQ YD)	(SQ YD)
19+71	23+00	314		
23+00	28+00	445		
28+00	33+00	288		
33+00	38+00	437	25	
38+00	43+80	483	75	92
43+80	1+30	158		
1+30	5+00	333		
5+00	9+00	181	236	
9+00	14+00	204	639	
14+00	19+00	274	389	
19+00	24+00	387	124	
107+00	110+20		54	
PROJECT TOTAL		3,504	1,542	92

3		SCHEDULE OF BITUMINOUS MATERIALS (PRIME COAT) (40600100)	
FROM	TO	AREA (SQ YD)	VOLUME (GAL)
19+71	23+00	2,491	1,505
23+00	28+00	3,774	2,267
28+00	33+00	4,848	2,958
33+00	38+00	3,200	1,920
38+00	43+80	5,126	3,083
43+80	1+30	2,218	1,356
1+30	5+00	3,590	2,180
5+00	9+00	4,901	3,047
9+00	14+00	4,558	2,733
14+00	19+00	3,531	2,119
19+00	24+00	3,065	1,840
101+80	105+00	1,872	1,127
107+00	110+20	1,770	1,067
PROJECT TOTAL		27,202	

4		SCHEDULE OF SEEDING						
		(25000210) CLASS 2A	(25000314) CLASS 4B	(X2500920) CLASS 1A (SPECIAL)	(X2501800) CLASS 4 (MODIFIED)	(X2501820) CLASS 5 (MODIFIED)	(25200110) SODDING, SALT TOLERANT	(25100115) MULCH, METHOD 2
FROM	TO	(ACRE)	(ACRE)	(ACRE)	(ACRE)	(ACRE)	(SQ YD)	(ACRE)
19+71	32+00	0.5	0.0	0.2	0.0	0.0	0	0.7
32+00	11+00	2.0	0.1	1.4	0.8	1.1	392	5.4
11+00	24+00	0.6	0.0	0.6	0.0	0.0	372	1.2
101+80	110+20	0.6	0.0	0.2	0.0	0.0	0	0.8
TOTAL		3.7	0.1	2.3	0.8	1.1	764	8.1
PROJECT TOTAL		3.75	0.25	2.50	1.00	1.25	764	8.25

*QUANTITIES ROUNDED UP TO THE NEAREST 0.25 ACRE TO REFLECT BDE DEGREE OF ACCURACY.

1		SCHEDULE OF EROSION CONTROL ITEMS					
		(Z0023204) SEDIMENT CONTROL, SILT FENCE	(28000305) TEMPORARY DITCH CHECKS	(28000500) INLET AND PIPE PROTECTION	(X2511630) EROSION CONTROL BLANKET (SPECIAL)	(28000510) INLET FILTERS	(28000250) TEMPORARY EROSION CONTROL SEEDING
FROM	TO	(FOOT)	(FOOT)	(EACH)	(SQ YD)	(EACH)	(POUND)
19+71	32+00	1,057	0	0	6,320	18	70
32+00	11+00	2,547	504	9	50,332	52	540
11+00	24+00	1,068	252	4	11,829	19	120
101+80	110+20	571	0	0	6,515	2	80
PROJECT TOTAL		5,243	756	13	74,997	91	810

5		SCHEDULE OF HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N50 (40603080)			
		AREA @ 2-1/2"	AREA @ 4-1/2"	TOTAL VOLUME	WEIGHT (115 LB/SQ YD-IN)
FROM	TO	(SQ YD)	(SQ YD)	(SQ YD-IN)	(TON)
19+71	23+00	167	147	1,078	62
23+00	28+00	444	0	1,111	64
28+00	33+00	288	0	719	42
33+00	38+00	437	0	1,092	63
38+00	43+80	478	0	1,196	69
43+80	1+30	32	0	80	5
1+30	5+00	278	0	696	41
5+00	9+00	180	5	475	28
9+00	14+00	204	0	511	30
14+00	19+00	274	0	685	40
19+00	24+00	387	5	992	58
101+80	105+00	0	5	24	2
107+00	110+20	0	0	0	0
PROJECT TOTAL				504	

CIVILTECH
 450 E Devon Ave, Suite 300
 Itasca, Illinois 60143
 Tel: 630.773.3900 Fax: 630.773.3975
 www.civiltechinc.com

DESIGNED - JRR
 DRAWN - JRR
 CHECKED - RTM
 DATE - 10/24/2011

REVISED -
 REVISED -
 REVISED -
 REVISED -

STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

SHEET NO. 1 OF 10 SHEETS

F.A.U. SECTION COUNTY TOTAL SHEETS SHEET NO.
 RTE. 364 02-00051-08-WR LAKE 188 16
 CONTRACT NO. 63649
 FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT