

DATE _____ BY _____
 SURVEYED _____
 PLOTTED _____
 NOTE BOOK _____
 AREAS CHECKED _____
 NO. _____

DATE _____ BY _____
 SURVEYED _____
 PLOTTED _____
 NOTE BOOK _____
 AREAS CHECKED _____
 NO. _____

33 SCHEDULE OF GRATING FOR CONCRETE FLARED END SECTIONS					
STATION	OFFSET	STRUCTURE #	24" (54247130)	36" (54247170)	42" (54247180)
32+61	37.1' LT	20		1	
36+10	39.0' LT	30		1	
36+10	74.6' RT	38			1
4+32	110.5' RT	79		1	
8+97	56.1' LT	95	1		
8+62	111.4' RT	96	1		
14+00	53.6' LT	120	1		
14+04	87.2' RT	121	1		
34+50	104.7' RT	29		1	
36+05	84.9' RT	39	1		
35+42	114.1' RT	41	1		
PROJECT TOTAL			6	4	1

34 SCHEDULE OF ITEMS TO BE ADJUSTED					
STATION	60250200	60255500	60260100	60265700	
FROM	TO	CATCH BASINS	MANHOLES	INLETS	VALVE VAULTS
19+71	23+00	2	1		
23+00	28+00				
28+00	33+00				1
33+00	38+00				
38+00	43+80				
43+08	1+30		1		
1+30	5+00		2		
5+00	9+00				
9+00	14+00				
14+00	19+00				
19+00	23+45	1	1	3	
101+80	105+00				
107+00	110+20	1	1	1	
PROJECT TOTAL		4	6	4	1

35 SCHEDULE OF PAVEMENT MARKING TAPE					
STATION	TYPE III, LETTERS AND SYMBOLS (70300510)	TYPE III, 4" (70300520)	TYPE III, 6" (70300540)	TYPE III, 12" (70300560)	
FROM	TO	AREA (SQ FT)	LENGTH (FOOT)	LENGTH (FOOT)	LENGTH (FOOT)
14+39	19+00	73	3,929	267	130
19+00	19+71		890		16
23+00	27+05	37	2,911	122	280
99+89	101+80		2,963	26	48
110+00	112+50		3,269		50
PROJECT TOTAL		110	13,963	415	524

36 SCHEDULE OF REMOVAL ITEMS									
STATION	PAVEMENT REMOVAL (44000100)	HOT-MIX ASPHALT SURFACE REMOVAL, 1" (44000153)	HOT-MIX ASPHALT SURFACE REMOVAL, 2" (44000157)	CURB REMOVAL (44000300)	COMB. C & G REMOVAL (44000500)	PAVED SHOULDER REMOVAL (44004250)	CONCRETE MEDIAN REMOVAL (X4403300)	GUARDRAIL REMOVAL (63200310)	
FROM	TO	(SQ YD)	(SQ YD)	(SQ YD)	(FOOT)	(FOOT)	(SQ YD)	(SQ FT)	(FOOT)
19+71	23+00	2,039				171	202		276
23+00	28+00	2,276				300	160		
28+00	33+00	3,297				578	204		
33+00	38+00	1,844							
38+00	43+80	2,344				30			
43+80	1+30	1,357				194	688		
1+30	5+00	2,030				194	522		544
5+00	9+00	3,221					581		784
9+00	14+00	2,121					498		171
14+00	19+00	1,728		362			436		
19+00	24+00	179		2,264					
101+80	105+00	206	1,619						
107+00	110+20	1,765				640			
TOTAL		24,407	1,619	2,626	388	4,444	566	1,328	447

37 SCHEDULE OF PAVEMENT MARKING REMOVAL (78300100)		
FROM	TO	AREA (SQ FT)
14+39	19+00	602
19+00	19+71	163
23+00	27+00	328
34+00	3+00	464
99+89	101+80	524
110+00	112+50	492
PROJECT TOTAL		2,574

ADDITIONAL 6,722 SQ YD CONTINGENCY QUANTITY PROVIDED TO ACCOMMODATE TRAFFIC DURING STAGE 1

38 SCHEDULE OF MEDIAN ITEMS				
STATION	CONCRETE MEDIAN SURFACE, 4 INCH (60618300)	CONCRETE MEDIAN, TYPE SB-6.24 (MODIFIED) (X6060200)	CORRUGATED MEDIAN (60624600)	
FROM	TO	(SQ FT)	(SQ FT)	(SQ FT)
23+00	28+00			
28+00	33+00			227
38+00	43+80		2,268	
43+08	1+30		116	506
1+30	5+00	147	996	
5+00	9+00		1,421	225
9+00	14+00		1,695	
14+00	19+00			332
PROJECT TOTAL		147	6,496	1,290