

**GENERAL NOTES**

GENERAL NOTES

ALL CONSTRUCTION SHALL BE IN ACCORDANCE WITH THE "STANDARD SPECIFICATIONS FOR ROAD AND BRIDGE CONSTRUCTION," ADOPTED JANUARY 1, 2012, THE SUPPLEMENTAL SPECIFICATIONS AND RECURRING SPECIAL PROVISIONS," ADOPTED JANUARY 1, 2012 AND THE LATEST EDITION OF THE "ILLINOIS MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES FOR STREETS AND HIGHWAYS" (IMUTCD).

THE CONTRACTOR SHALL CONTACT THE TRAFFIC CONTROL SUPERVISOR AT (847) 705-4470 A MINIMUM OF 72 HOURS IN ADVANCE OF BEGINNING WORK.

UTILITIES

THE CONTRACTOR SHALL COOPERATE WITH THE CITY OF ELGIN IN ANY UNDERGROUND UTILITY CONSTRUCTION WHICH THE CITY MAY WANT TO PLACE DURING THE CONTRACTOR'S OPERATIONS. NO UNDERGROUND WORK IS SCHEDULED WITH THIS PROJECT.

THE CONTRACTOR SHALL BE RESPONSIBLE FOR CONTACTING THE OWNERS OF ALL EXISTING FACILITIES SO THAT THE UTILITIES AND THEIR APPURTENANCES MAY BE LOCATED AND ADJUSTED OR MOVED, IF NECESSARY, PRIOR TO THE START OF CONSTRUCTION OPERATIONS. THE CONTRACTOR SHALL COOPERATE WITH ALL UTILITY OWNERS AS PROVIDED FOR IN THE STANDARD SPECIFICATIONS.

THE LOCATIONS OF EXISTING DRAINAGE STRUCTURES, STORM AND SANITARY SEWERS, WATER SERVICE LINES AND OTHER UTILITY LINES ARE APPROXIMATE, AND THE DEPARTMENT DOES NOT GUARANTEE THEIR ACCURACY. THEIR EXACT HORIZONTAL AND VERTICAL LOCATIONS ARE TO BE DETERMINED IN THE FIELD BY THE CONTRACTOR AT HIS OWN EXPENSE.

THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE PROTECTION OF ALL UNDERGROUND OR SURFACE UTILITIES EVEN THOUGH THEY MAY NOT BE SHOWN ON THE PLANS. ANY UTILITY THAT IS DAMAGED DURING CONSTRUCTION SHALL BE REPAIRED OR REPLACED TO THE SATISFACTION OF THE ENGINEER. THIS WORK SHALL BE AT THE CONTRACTOR'S EXPENSE.

BEFORE STARTING ANY EXCAVATION, THE CONTRACTOR SHALL CALL "J.U.L.I.E." AT 800-892-0123 FOR FIELD LOCATIONS OF BURIED ELECTRIC, TELEPHONE, GAS AND CABLE TELEVISION FACILITIES. (48 HOURS NOTIFICATION IS REQUIRED.)

STAKING

THE CONTRACTOR SHALL PROTECT AND CAREFULLY PRESERVE ALL SECTIONS OR SUBSECTION MONUMENTS OR PROPERTY OR REFERENCE MARKERS UNTIL THE ENGINEER, THEIR AGENT OR AN AUTHORIZED SURVEYOR HAS WITNESSED OR OTHERWISE REFERENCED THEIR LOCATIONS.

WATER, STORM SEWER AND SANITARY SEWER

WHENEVER DURING CONSTRUCTION OPERATIONS ANY LOOSE MATERIAL IS DEPOSITED IN THE FLOW LINE OF DRAINAGE STRUCTURES SUCH THAT THE NATURAL FLOW OF WATER IS OBSTRUCTED, IT SHALL BE REMOVED AT THE CLOSE OF EACH WORKING DAY. AT THE CONCLUSION OF CONSTRUCTION OPERATIONS, ALL UTILITY STRUCTURES WILL BE FREE FROM DIRT AND DEBRIS. THE WORK SPECIFIED ABOVE WILL NOT BE PAID FOR SEPERATELY BUT SHALL INCLUDED IN THE COST OF MOBILIZATION.

ANY EXISTING OR PROPOSED STORM SEWER DAMAGED BY THE CONTRACTOR DURING CONSTRUCTION SHALL BE REPLACED BY THE CONTRACTOR AND IS INCLUDED IN THE COST OF MOBILIZATION.

MAINTENANCE OF TRAFFIC

ALL TRAFFIC CONTROL PROTECTION SHALL PAID FOR AS A LUMP SUM.

**INDEX OF SHEETS**

- 1 COVER SHEET
- 2 GENERAL NOTES, INDEX & STANDARDS
- 3 SUMMARY OF QUANTITIES
- 4 PROPOSED PLAN - ABBOTT MIDDLE SCHOOL
- 5 PROPOSED PLAN - CENTURY OAKS ELEMENTARY SCHOOL
- 6 PROPOSED PLAN - CHANNING ELEMENTARY SCHOOL
- 7 PROPOSED PLAN - COLEMAN ELEMENTARY SCHOOL
- 8 PROPOSED PLAN - CREEKSIDE ELEMENTARY SCHOOL
- 9 PROPOSED PLAN - ELLIS MIDDLE SCHOOL
- 10 PROPOSED PLAN - GARFIELD ELEMENTARY SCHOOL
- 11 PROPOSED PLAN - HARRIET GIFFORD ELEMENTARY SCHOOL
- 12 PROPOSED PLAN - HIGHLAND ELEMENTARY SCHOOL
- 13 PROPOSED PLAN - HILLCREST ELEMENTARY SCHOOL
- 14 PROPOSED PLAN - HUFF ELEMENTARY SCHOOL
- 15 PROPOSED PLAN - KIMBALL MIDDLE SCHOOL
- 16 PROPOSED PLAN - LARSEN MIDDLE SCHOOL
- 17 PROPOSED PLAN - LORDS PARK ELEMENTARY SCHOOL
- 18 PROPOSED PLAN - LOWRIE ELEMENTARY SCHOOL
- 19 PROPOSED PLAN - MCKINLEY ELEMENTARY SCHOOL
- 20 PROPOSED PLAN - SHERIDAN ELEMENTARY SCHOOL
- 21 PROPOSED PLAN - WASHINGTON ELEMENTARY SCHOOL
- 22 TRAFFIC CONTROL AND PROTECTION FOR SIDE ROADS, INTERSECTIONS, AND DRIVEWAYS (TC-10)
- 23 DISTRICT ONE TYPICAL PAVEMENT MARKINGS (TC-13)

**HIGHWAY STANDARDS**

- 000001-06 STANDARD SYMBOLS, ABBREVIATIONS AND PATTERNS
- 701201-04 LANE CLOSURE, 2L, 2W, DAY ONLY, FOR SPEEDS ≥ 45 MPH
- 701301-04 LANE CLOSURE, 2L, 2W, SHORT TIME OPERATIONS
- 701311-03 LANE CLOSURE 2L, 2W MOVING OPERATIONS-DAY ONLY
- 701427 LANE CLOSURE, MULTILANE, INTERMITTENT OR MOVING OPER., FOR SPEEDS ≤ 40 MPH
- 701601-07 URBAN LANE CLOSURE, MULTILANE, 1W OR 2W WITH NONTRAVERSABLE MEDIAN
- 701701-08 URBAN LANE CLOSURE, MULTILANE INTERSECTION
- 701801-05 SIDEWALK, CORNER OR CROSSWALK CLOSURE
- 701901-02 TRAFFIC CONTROL DEVICES
- 780001-03 TYPICAL PAVEMENT MARKINGS

**DISTRICT STANDARDS**

- TC-10 TRAFFIC CONTROL AND PROTECTION FOR SIDE ROADS, INTERSECTIONS, AND DRIVEWAYS
- TC-13 DISTRICT ONE TYPICAL PAVEMENT MARKINGS

FILE NAME = W:\Projects\2010\1000031\_Elgin\Garfield\Acadd\Civil\Dgn\Shet\GENOTES.dgn



|                       |               |                   |
|-----------------------|---------------|-------------------|
| USER NAME = nporris   | DESIGNED -    | REVISED - 2/15/12 |
| PLOT SCALE = N/A      | DRAWN -       | REVISED -         |
| PLOT DATE = 2/14/2012 | CHECKED -     | REVISED -         |
|                       | DATE - 2/3/12 | REVISED -         |

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

|   |                          |      |         |        |              |           |
|---|--------------------------|------|---------|--------|--------------|-----------|
| <b>GENERAL NOTES, INDEX &amp; STANDARDS</b>     |                          | RTE. | SECTION | COUNTY | TOTAL SHEETS | SHEET NO. |
| SCALE: N/A                                      | SHEET NO. 2 OF 23 SHEETS | STA. | TO STA. | KANE   | 23           | 2         |
| FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT |                          |      |         |        |              |           |

**CONTRACT NO. 63675**