SUMMARY OF QUANTITIES

SPECIAL PROVISION	SPECIALTY ITEM	CODE NO.	ITEM DESCRIPTION	UNIT	URBAN TOTAL QUANTITY	FEDERAL = 75% STATE = 12.5% VILLAGE = 12.5% ROADWAY 0004	TRAFFIC SIGNAL 0021	TRAINEES 0042	FEDERAL = 0% STATE = 0% VILLAGE = 100% ROADWAY (CROSS STREET FROM RICHARD TO JOY) 0004	EMERGENCY VEHICLE PREEMPTION 0021
Δ	*	66900530	SOIL DISPOSAL ANALYSIS	EACH	5	5				
		67100100	MOBILIZATION	L SUM	1	1				
		70106800	CHANGEABLE MESSAGE SIGN	CAL MO	4	4				
		70300100	SHORT TERM PAVEMENT MARKING	FOOT	1,050	930			120	
		70300210	TEMPORARY PAVEMENT MARKING LETTERS AND SYMBOLS	SQ FT	270	270				
		70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	5,410	4,730			680	
		70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	530	530				
		70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	100	100				
		70300520	PAVEMENT MARKING TAPE, TYPE III 4"	FOOT	2,100	2,100				
		70300540	PAVEMENT MARKING TAPE, TYPE III 6"	FOOT	36	36				
		70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	1,068	1,028			40	
		72000100	SIGN PANEL - TYPE 1	SQ FT	86	57	29			
		72400100	REMOVE SIGN PANEL ASSEMBLY - TYPE A	EACH	1	1				
		72400500	RELOCATE SIGN PANEL ASSEMBLY - TYPE A	EACH	5	5				
		72400500	RELOCATE SIGN PANEL ASSEMBLY - TYPE B	EACH	1	1				
		72800100	TELESCOPING STEEL SIGN SUPPORT	FOOT	128	128				
	*	78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	432	432				
	*	78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	2,579	1,719			860	
	*	78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	1,912	1,762			150	
	*	78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	66	66				
	*	78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	822	771			51	
	*	78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	265	252			13	
	*	78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	22	22				
	*	78100300	REPLACEMENT REFLECTOR	EACH	34	34				
	*	78200410	GUARDRAIL MARKERS, TYPE A	EACH	12	12				
	*	78200530	BARRIER WALL MARKERS, TYPE C	EACH	8	8				
	*	78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	2	2				
		78300100	PAVEMENT MARKING REMOVAL	SQ FT	115	115				
		78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	34	34				
	*	80500020	SERVICE INSTALLATION - POLE MOUNTED	EACH	1		1			
	*	81028200	UNDERGROUND CONDUIT, GALVANIZED STEEL, 2" DIA.	FOOT	1,077		1,077			
	*	81028210	UNDERGROUND CONDUIT, GALVANIZED STEEL, 2 1/2" DIA.	FOOT	105		105			
	*	81028220	UNDERGROUND CONDUIT, GALVANIZED STEEL, 3" DIA.	FOOT	44		44			
	*	81028240	UNDERGROUND CONDUIT, GALVANIZED STEEL, 4" DIA.	FOOT	372		372			
	*	81400100	HANDHOLE	EACH	6		6			
	*	81400200	HEAVY-DUTY HANDHOLE	EACH	3		3			
	*	81400300	DOUBLE HANDHOLE	EACH	1		1			
	*	85000200	MAINTENANCE OF EXISTING TRAFFIC SIGNAL INSTALLATION	EACH	1		1			
	*	86400100	TRANSCEIVER - FIBER OPTIC	EACH	1		1			
	*	87300925	ELECTRIC CABLE IN CONDUIT, TRACER, NO. 14 1C	FOOT	4,193		4,193			
	*	87301215	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 2C	FOOT	912		912			
	*	87301225	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 3C	FOOT	1,252		1,252			
	*	87301245	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 5C	FOOT	1,250		1,250			
	*	87301255	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 7C	FOOT	1,617		1,617			
	*	87301305	ELECTRIC CABLE IN CONDUIT, LEAD-IN, NO. 14 1 PAIR	FOOT	3,683		3,683			
	*	87301805	ELECTRIC CABLE IN CONDUIT, SERVICE, NO. 6 2 C	FOOT	46		46			
	*	87301900	ELECTRIC CABLE IN CONDUIT, EQUIPMENT GROUNDING CONDUCTOR, NO. 8 1C	FOOT	560		560			

SPECIAL PROVISION	SPECIALTY ITEM	CODE NO.	ITEM DESCRIPTION	UNIT	URBAN TOTAL QUANTITY	FEDERAL = 75% STATE = 12.5% VILLAGE = 12.5% ROADWAY 0004	TRAFFIC SIGNAL 0021	TRAINEES 0042	FEDERAL = 0% STATE = 0% VILLAGE = 100% ROADWAY (CROSS STREET FROM RICHARD TO JOY) 0004	EMERGENCY VEHICLE PREEMPTION 0021
	*	87502500	TRAFFIC SIGNAL POST, GALVANIZED STEEL 16 FT.	EACH	2		2			
	*	87700230	STEEL MAST ARM ASSEMBLY AND POLE, 38 FT.	EACH	2		2			
	*	87700270	STEEL MAST ARM ASSEMBLY AND POLE, 46 FT.	EACH	1		1			
	*	87700280	STEEL MAST ARM ASSEMBLY AND POLE, 48 FT.	EACH	1		1			
	*	87800100	CONCRETE FOUNDATION, TYPE A	FOOT	8		8			
	*	87800150	CONCRETE FOUNDATION, TYPE C	FOOT	4		4			
	*	87800415	CONCRETE FOUNDATION, TYPE E 36-INCH DIAMETER	FOOT	48		48			
	*	87900200	DRILL EXISTING HANDHOLE	EACH	3		3			
	*	88030020	SIGNAL HEAD, LED, 1-FACE, 3-SECTION, MAST-ARM MOUNTED	EACH	6		6			
	*	88030100	SIGNAL HEAD, LED, 1-FACE, 5-SECTION, BRACKET MOUNTED	EACH	4		4			
	*	88030110	SIGNAL HEAD, LED, 1-FACE, 5-SECTION, MAST-ARM MOUNTED	EACH	4		4			
	*	88102717	PEDESTRIAN SIGNAL HEAD, LED, 1-FACE, BRACKET MOUNTED WITH COUNTDOWN TIMER	EACH	4		4			
	*	88102747	PEDESTRIAN SIGNAL HEAD, LED, 2-FACE, BRACKET MOUNTED WITH COUNTDOWN TIMER	EACH	1		1			
	*	88200210	TRAFFIC SIGNAL BACKPLATE, LOUVERED, ALUMINUM	EACH	10		10			
	*	88500100	INDUCTIVE LOOP DETECTOR	EACH	12		12			
	*	88600100	DETECTOR LOOP, TYPE I	FOOT	965		965			
	*	88800100	PEDESTRIAN PUSH-BUTTON	EACH	6		6			
	*	89000100	TEMPORARY TRAFFIC SIGNAL INSTALLATION	EACH	1		1			
Δ	*	89501400	RELOCATE EXISTING EMERGENCY VEHICLE PRIORITY SYSTEM, DETECTOR UNIT	EACH	2					2
Δ	*	89501410	RELOCATE EXISTING EMERGENCY VEHICLE PRIORITY SYSTEM, PHASING UNIT	EACH	1					1
	*	89502300	REMOVE ELECTRIC CABLE FROM CONDUIT	FOOT	8,145		8,145			
Δ	*	89502375	REMOVE EXISTING TRAFFIC SIGNAL EQUIPMENT	EACH	1		1			
	*	89502380	REMOVE EXISTING HANDHOLE	EACH	9		9			
	*	89502385	REMOVE EXISTING CONCRETE FOUNDATION	EACH	9		9			
	*	B2002222	TREE, CRATAEGUS VIRDIS WINTER KING (WINTER KING GREEN HAWTHORN), 3" CALIPER, BALLED AND BURLAPPED	EACH	6	6				
Δ		X0322936	REMOVE EXISTING FLARED END SECTION	EACH	1	1				
Δ	*	X0324065	EMERGENCY VEHICLE PRIORITY SYSTEM LINE SENSOR CABLE, NO. 20 3/C	FOOT	306		306			
Δ		X4401196	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SQ YD	2,277	2,277				
Δ		X4402020	CONCRETE MEDIAN SURFACE REMOVAL	SQ FT	33	33				
Δ	*	X6026050	SANITARY MANHOLES TO BE ADJUSTED	EACH	3	3				
Δ	*	X6026056	SANITARY MANHOLES TO BE ADJUSTED WITH NEW TYPE 1 FRAME, CLOSED LID	EACH	1	1				
Δ		X6029510	CATCH BASINS, TYPE C, WITH SPECIAL FRAME AND GRATE	EACH	1	1				
Δ		XX008677	GUTTER OUTLET (SPECIAL)	EACH	1	1				
Δ		X8370050	CONCRETE BARRIER WALL (SPECIAL)	FOOT	97	97				
Δ		X7010216	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	L SUM	1	1				
Δ		X7240500	RELOCATE EXISTING SIGNS	EACH	1	1				
Δ	*	X8570226	FULL-ACTUATED CONTROLLER AND TYPE IV CABINET, SPECIAL	EACH	1		1			
Δ	*	X8820200	UNINTERRUPTABLE POWER SUPPLY, SPECIAL	EACH	1		1			
	*	X8710024	FIBER OPTIC CABLE IN CONDUIT, NO. 62.5/125, MM12F SM24F	FOOT	4,216		4,216			
		XX007183	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-3.12	FOOT	76					76
Δ		XX008200	STABILIZED DRIVEWAY PAVEMENT	SQ YD	145	145				
Δ		Z0030850	TEMPORARY INFORMATION SIGNING	SQ FT	70	70				
Δ	*	Z0033046	RE-OPTIMIZE TRAFFIC SIGNAL SYSTEM LEVEL 2	EACH	1		1			
Δ		Z0042002	POROUS GRANULAR EMBANKMENT, SUBGRADE	CU YD	180	180				
Δ	*	Z0073510	TEMPORARY TRAFFIC SIGNAL TIMING	EACH	1		1			
Δ		Z0076600	TRAINEES	HOUR	1,000			1,000		

Δ SEE SPECIAL PROVISIONS
* SPECIALTY ITEMS

COPYRIGHT © 2012 ENGINEERING ENTERPRISES, INC.

Engineering Enterprises, Inc.
CONSULTING ENGINEERS
52 Wheeler Road
Sugar Grove, Illinois 60554
630.466.6700 / www.eeiweb.com

USER NAME = | DESIGNED - | REVISED - | PLOT SCALE = | DRAWN - | REVISED - | PLOT DATE = | CHECKED - | REVISED - | DATE - | REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: N/A | SHEET NO. 2 OF 2 SHEETS | STA. N/A TO STA. N/A

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
326	10-00023-00-ES	KANE	70	5

CONTRACT NO. 63700

FED. ROAD DIST. NO. 1 | ILLINOIS | FED. AID PROJECT NO. M-9003(717)

Plotted: March 26, 2012 @ 1:31 PM By: Kris Pung - Tue, 05 SeD - 22x34

Plot H: S:\BURO\J\63700\DWG\DWG FINAL ENV\637002-EVP