

SUMMARY OF QUANTITIES

PAYCODE	ITEM DESCRIPTION	UNIT	TOTAL	ROADWAY 80% FEDERAL 20% LOCAL 0004	SIGNALS 80% FEDERAL 20% LOCAL 0021	LIGHTING 80% FEDERAL 20% LOCAL 0021
67100100	MOBILIZATION	L SUM	1	1		
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	1		
70102622	TRAFFIC CONTROL AND PROTECTION, STANDARD 701502	L SUM	1	1		
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1		
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1	1		
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DAY	60	60		
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	12	12		
70300210	TEMPORARY PAVEMENT MARKING LETTERS AND SYMBOLS	SQ FT	295	295		
70300220	TEMPORARY PAVEMENT MARKING-LINE 4"	FOOT	6,505	6,505		
70300240	TEMPORARY PAVEMENT MARKING-LINE 6"	FOOT	1,185	1,185		
70300280	TEMPORARY PAVEMENT MARKING-LINE 24"	FOOT	75	75		
70300520	PAVEMENT MARKING TAPE, TYPE III 4"	FOOT	1,000	1,000		
72000100	SIGN PANEL-TYPE 1	SQ FT	70	55	15	
72000200	SIGN PANEL-TYPE 2	SQ FT	21		21	
72800100	TELESCOPING STEEL SIGN SUPPORT	FOOT	200	200		
* 78008200	POLYUREA PAVEMENT MARKING TYPE I - LETTERS AND SYMBOLS	SQ FT	255	255		
* 78008210	POLYUREA PAVEMENT MARKING TYPE I - LINE 4"	FOOT	1,395	1,395		
* 78008230	POLYUREA PAVEMENT MARKING TYPE I - LINE 6"	FOOT	2,970	2,970		
* 78008250	POLYUREA PAVEMENT MARKING TYPE I - LINE 12"	FOOT	650	650		
* 78008270	POLYUREA PAVEMENT MARKING TYPE I - LINE 24"	FOOT	75	75		
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	97	97		
78300100	PAVEMENT MARKING REMOVAL	SQ FT	790	790		
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	66	66		
* 81028200	UNDERGROUND CONDUIT, GALVANIZED STEEL, 2" DIA.	FOOT	986		986	
* 81028210	UNDERGROUND CONDUIT, GALVANIZED STEEL, 2 1/2" DIA.	FOOT	98		28	70
* 81028220	UNDERGROUND CONDUIT, GALVANIZED STEEL, 3" DIA.	FOOT	47		47	
* 81028240	UNDERGROUND CONDUIT, GALVANIZED STEEL, 4" DIA.	FOOT	508		508	
* 81400100	HANDHOLE	EACH	4		4	
* 81400300	DOUBLE HANDHOLE	EACH	1		1	
* 81603081	UNIT DUCT, 600V, 3-1C NO.2, 1/C NO.4 GROUND, (XLP-TYPE USE), 1 1/2" DIA. POLYETHYLENE	FOOT	3,084			3,084
* 83600355	LIGHT POLE FOUNDATION, METAL, 15" BOLT CIRCLE, 8" X 6"	EACH	7			7
* 83800205	BREAKAWAY DEVICE, TRANSFORMER BASE, 15 INCH BOLT CIRCLE	EACH	7			7
* 84200500	REMOVAL OF LIGHTING UNIT, SALVAGE	EACH	9		2	7
* 84200804	REMOVAL OF POLE FOUNDATION	EACH	7			7
* 84400105	RELOCATE EXISTING LIGHTING UNIT	EACH	7			7
* 85000200	MAINTENANCE OF EXISTING TRAFFIC SIGNAL INSTALLATION	EACH	2		2	
* 87301215	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 2C	FOOT	707.5		707.5	
* 87301225	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 3C	FOOT	1,197		1,197	
* 87301245	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 5C	FOOT	614.5		614.5	
* 87301255	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 7C	FOOT	3,100		3,100	
* 87301305	ELECTRIC CABLE IN CONDUIT, LEAD-IN, NO. 14 1 PAIR	FOOT	1,802		1,802	
* 87301900	ELECTRIC CABLE IN CONDUIT, EQUIPMENT GROUNDING CONDUCTOR, NO. 6 1C	FOOT	1,247		1,247	
* 87502500	TRAFFIC SIGNAL POST, GALVANIZED STEEL 16 FT.	EACH	2		2	
* 87700340	STEEL MAST ARM ASSEMBLY AND POLE, 58 FT.	EACH	1		1	
* 87700408	STEEL MAST ARM ASSEMBLY AND POLE, 64 FT.	EACH	1		1	
* 87800100	CONCRETE FOUNDATION, TYPE A	FOOT	8		8	

COMPANY NAME: HRGreen
 PROJECT CONTACT: jnelhus
 CLIENT: 4/11/2012 3:43:17 PM
 DATE PLOTTED: 0177-sum.dgn
 FILE NAME: pdfplot
 PLOT DRIVER: standard-trans.tbl
 PEN TABLE:



USER NAME = jnelhus	DESIGNED - JRM	REVISED -
PLOT SCALE = N.T.S.	CHECKED - TEH	REVISED -
PLOT DATE = 4/11/2012	DATE - 4/11/12	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

**SUMMARY OF QUANTITIES
IL 59 & SHOE FACTORY RD**

SCALE: N.T.S. SHEET NO. 2 OF 3 SHEETS STA. TO STA.

F.A.P. RTE. 338	SECTION 10-00084-00-CH	COUNTY COOK	TOTAL SHEETS 63	SHEET NO. 4
CONTRACT NO. 63711				
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT				