

MAINLINE PAVING SCHEDULE												
STA. TO STA.	AREA	HMA SURF REM 2 1/4"	HMA SURF REM 3 3/4"	POLY HMA SURF CSE MIX C N50	LEVEL BINDER (MM) N50	HMA BINDER CSE N50	BIT MATL PRIME COAT	AGG PRIME COAT	MIX FOR CRACKS JTS & FLGWYS	LEVEL BINDER (HM) N50	TEMP RAMP	
	SQ YD	SQ YD	SQ YD	TON	TONS	TONS	GAL	TON	TON	TON	SQ YD	
13+18 TO 20+20	1872		1872	158		236	243	7	1	1	75	
20+20 TO 22+55												
22+55 TO 29+34	1962		1962	165		247	255	8	1	1	73	
29+34 TO 29+79												
29+79 TO 33+10	1618		1618	136		204	210	6	1	1	123	
33+10 TO 33+53												
33+53 TO 44+70	5709	5709		480	240		742	23	2	3	39	
44+70 TO 47+04	832	832		70	35		108	3	1	1		
47+04 TO 48+69												
2402+90 TO 2404+05	944	944		80	40		123	4	1	1	27	
2404+05 TO 2405+60	448	448		38	19		58	2	1	1		
2405+60 TO 2408+25.28	1185	1185		100	50		154	5	1	1	115	
TOTALS	14569	9118	5452	1227	384	687	1894	58	9	9	452	

ADJUSTMENT SCHEDULE		
LOCATION	MANHOLE ADJUSTMENT	WATER VALVE ADJUSTMENT
	EACH	EACH
STA. 14+78 30' LT	1	
STA. 15+96 10' RT		1
STA. 19+51 3' LT	1	
STA. 27+11 18' RT	1	
STA. 27+17 36' RT	1	
STA. 26+98 37' LT	1	
STA. 28+12 4' LT	1	
STA. 29+28 10' RT		1
STA. 29+31 21' RT	1	
STA. 29+81 21' RT	1	
STA. 31+56 33' LT	1	
STA. 37+00 3' RT	1	
STA. 42+51 24' LT	1	
STA. 44+37 3' RT	1	
WASSON ST		
STA. 2406+57 2' RT	1	
TOTAL	13	2

SIDEROAD SCHEDULE											
STATION	SIDE	DESCRIPTION	EXISTING MATERIAL	WIDTH	AREA	HMA SURFACE REM 1 1/2"	INC. HMA SURFACE	BIT MAT'L (PR CT)	AGG (PR CT)	TEMP RAMP	
				FOOT	SQ YD	SQ YD	TON	GAL	TON	SQ YD	
14+78	LT	Armory St.	HMA	26	81.1	81.1	6.8	6.5	0.2	14.4	
24+42	RT	Pleasant St.	HMA	18.5	145.4	145.4	12.2	11.6	0.3	10.3	
27+02	LT	Oak St.	HMA	28.4	152.9	152.9	12.8	12.2	0.3	15.8	
27+16	RT	City Hall Alley	HMA	19	74.4	74.4	6.2	6.0	0.1	10.6	
28+19	LT	Alley	HMA	33.7	65.8	65.8	5.5	5.3	0.1	18.7	
31+49	LT	Alley	HMA	14	24.9	24.9	2.1	2.0	0.1	7.8	
35+16	LT	Alley	HMA	21	29.6	29.6	2.5	2.4	0.1	11.7	
36+98	RT	Monroe St.	HMA	30.5	116.9	116.9	9.8	9.4	0.2	16.9	
36+98	LT	Monroe St.	HMA	38.5	143.1	143.1	12.0	11.4	0.3	21.4	
38+82	LT	Alley	HMA	15	21.5	21.5	1.8	1.7	0.1	8.3	
40+68	RT	Vermillion St.	HMA	30	140.6	140.6	11.8	11.2	0.3	16.7	
40+68	LT	Vermillion St.	HMA	41	146.1	146.1	12.3	11.7	0.3	22.8	
42+51	LT	Alley	HMA	20	26.7	26.7	2.2	2.1	0.1	11.1	
44+70	RT	Sterling St.	HMA	30.5	112.2	112.2	9.4	9.0	0.2	16.9	
44+70	LT	Sterling St.	HMA	42	152.8	152.8	12.8	12.2	0.3	23.3	
48+09	RT	Wasson St.	HMA	20.5	145.6	145.6	12.2	11.6	0.3	11.4	
2406+49.62	RT	Half St.	HMA	17.5	113.4	113.4	9.5	9.1	0.2	9.7	
TOTAL					1693	1693	143	136	4.0	248	