

MEDIAN, CURB, & SIDEWALK SCHEDULE

DESCRIPTION	SUGGESTED STANDARD #	COMB CURB & GUTTER REM	CC&G TYPE B-6.12	CC&G TYPE B-6.24	CONC CURB TY B	SIDEWALK REM	PCC SIDEWALK 4"	DETECTABLE WARNING	INLET ADJUSTMENT	SEEDING	NIT FERT NUT	POT FERT NUT	PHOS FERT NUT	EROSION CONTROL BLANKET
		FOOT	FOOT	FOOT	FOOT	SQ FT	SQ FT	SQ FT	EACH	ACRE	LB	LB	LB	SQ YD
Vermillion Bridge Levy														
Northside	424006	10	-	-	10	91	91	8	-	0.0035	0.32	0.32	0.32	17
Southside	424006	10	-	-	10	174	191	8	-	0.0045	0.41	0.41	0.41	22
Pleasant Street														
Westside	424011	20	20	-	-	68.5	83	8	-	0.0017	0.15	0.15	0.15	8
Eastside	424011	20	20	-	-	78.5	95	8	-	0.0019	0.17	0.17	0.17	9
Oak Street														
SW Quad	424001-06	13	13	-	-	63	76	8	-	0.0014	0.13	0.13	0.13	7
SE Quad	424001-06	15	15	-	-	36	42	8	-	0.0008	0.07	0.07	0.07	4
NW Quad (N OF ALLEY)	N/A	10	13	-	-	-	-	-	-	0.0000	0.00	0.00	0.00	-
NW Quad (S OF ALLEY)	N/A	7	20	-	-	22	26	-	-	-	-	-	-	-
NE Quad	N/A	15	15	-	-	-	-	-	-	0.0000	0.00	0.00	0.00	-
Alley between Bloomington Street and Park Street														
Westside	424026	12	12	-	-	94	94	8	-	-	-	-	-	-
Eastside	424026	12	12	-	-	136	136	8	-	-	-	-	-	-
Alley at Streator Home Building and Loan														
Westside	424026	8	8	-	-	27	33	8	-	0.0006	0.06	0.06	0.06	3
Eastside	424026	8	8	-	-	27	33	8	-	0.0006	0.06	0.06	0.06	3
Monroe Street														
NW Quad	424021	18	18	-	-	173	173	32	1	0.0012	0.11	0.11	0.11	6
NE Quad	424001-06	28	28	-	-	198	198	16	1	-	-	-	-	-
SW Quad	424021	22	22	-	-	110	110	32	1	0.0023	0.20	0.20	0.20	11
SE Quad	424001-06	28	28	-	-	128	128	16	1	0.0017	0.15	0.15	0.15	8
Alley between Monroe Street and Vermillion Street														
Westside	424026	15	15	-	-	68	71	8	-	0.0014	0.13	0.13	0.13	7
Eastside	424026	15	15	-	-	70	75	8	-	0.0014	0.13	0.13	0.13	7
Vermillion Street														
NW Quad	424001-06	23	23	-	-	161	161	16	1	0.0010	0.09	0.09	0.09	5
NE Quad	424001-06	23	23	-	-	163	163	16	1	-	-	-	-	-
SW Quad	424001-06	28	28	-	-	163	163	16	1	-	-	-	-	-
SE Quad	424001-06	15	15	-	-	170	170	16	-	0.0006	0.06	0.06	0.06	3
Alley between Vermillion Street and Sterling Street														
Westside	424026	8	8	-	-	33	39	8	-	0.0010	0.09	0.09	0.09	5
Eastside	424026	13	13	-	-	47	53	8	-	-	-	-	-	-
Sterling Street														
NW Quad	424021	15	15	-	-	202	202	32	1	0.0008	0.07	0.07	0.07	4
NE Quad	424021	26	26	-	-	222	232	32	1	0.0008	0.07	0.07	0.07	4
SW Quad	424021	18	18	-	-	169	178	32	-	0.0014	0.13	0.13	0.13	7
SE Quad	424001-06	29	29	-	-	272	272	16	1	0.0021	0.19	0.19	0.19	10
Wasson Street														
SW Quad	424001-06	16	-	16	-	153	183	16	-	0.0008	0.07	0.07	0.07	4
SE Quad	424001-06	16	-	16	-	145	165	16	-	0.0008	0.07	0.07	0.07	4
Main St.														
Median Island	424031	-	-	-	-	10	10	16	-	-	-	-	-	-
TOTAL		516	480	32	20	3474	3646	432	10	0.03	2.94	2.94	2.94	158

FILE NAME =	USER NAME = duncenbd	DESIGNED -	REVISED -
c:\pwwork\pwwork\duncenbd\0285100\0366882-sht-schedule.dgn		DRAWN -	REVISED -
		CHECKED -	REVISED -
		DATE -	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SCHEDULES

SCALE: SHEET NO. 2 OF 3 SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
653	TR5-3 & 8R5-4	LASALLE	23	12
ILLINOIS FED. AID PROJECT			CONTRACT NO. 66B82	