

TRAFFIC SIGNAL GENERAL NOTES

THE CONTRACTOR SHALL CONTACT THE APPROPRIATE CITY A MINIMUM OF 72 HOURS PRIOR TO BEGINNING WORK.

- A. BOURBONNAIS 815-937-3570
- B. BRADLEY 815-932-2125
- C. CHANNAHON 815-467-6644
- D. COAL CITY 815-634-8608
- E. DEKALB 815-748-2030
- F. FAIRBURY 815-692-2743
- G. GENOA 815-784-2327
- H. GIBSON CITY 815-784-5872
- I. KANKAKEE 815-933-0480
- J. LASALLE 815-223-7041
- K. MANTENO 815-929-4800
- L. MENDOTA 815-539-7459
- M. MINOOKA 815-467-2151
- N. MOMENCE 805-472-2001
- O. MORRIS 815-942-0103
- P. OGLESBY 815-883-3389
- Q. OSWEGO 630-554-3618
- R. OTTAWA 815-431-1579, EXT. 20
- S. PAXTON 217-379-4022
- T. PERU 815-223-0061
- U. PLANO 630-552-8275
- V. PONTIAC 815-844-6752
- W. PRINCETON 815-875-2631
- X. SANDWICH 815-786-9321
- Y. SPRING VALLEY 815-664-4221
- Z. STREATOR 815-672-2517
- AA. SYCAMORE 815-895-4515
- AB. YORKVILLE 630-553-4350
- AC. WATERMAN 815-264-3652
- AD. WATSEKA 815-432-2711

THE TRAFFIC SIGNAL SECTION AT THE ILLINOIS DEPARTMENT OF TRANSPORTATION, DISTRICT 3, SHALL BE NOTIFIED AT 815-434-8506 AT LEAST 72 HOURS PRIOR TO TURNING ON ANY FLASHER OR CONTROLLER UNITS.

THE CONTRACTOR SHALL BE RESPONSIBLE FOR PROTECTING UTILITY PROPERTY DURING CONSTRUCTION OPERATIONS AS OUTLINED IN ARTICLE 107.31 OF THE STANDARD SPECIFICATIONS. A MINIMUM OF 48 HOURS ADVANCED NOTICE IS REQUIRED FOR NON-EMERGENCY WORK. THE JULIE NUMBER IS 800-892-0123.

ALL TRAFFIC CONTROL AND OTHER ADVISORY SIGNS NEEDED FOR CONSTRUCTION ARE TO BE FURNISHED BY THE CONTRACTOR IN ACCORDANCE WITH SECTION 701 OF THE STANDARD SPECIFICATIONS.

ALL THREADS OF BOLTS USED IN THE ASSEMBLY OF TRAFFIC SIGNAL COMPONENTS SHALL BE COATED WITH A NON-LEAD BASED ANTI-SEIZE COMPOUND, SIMILAR TO LEAD PLATE, PRIOR TO ASSEMBLY.

ALL HARDWARE SHALL BE TIGHTENED AND WELL SECURED; CABLES SHALL BE NEATLY WOUND IN HANDHOLES. CABLES SHALL BE NEATLY TRAINED IN THE CONTROLLER CABINET.

ALL UNINTERRUPTIBLE POWER SUPPLIES SHALL BE EQUIPPED WITH ALPHA GUARD MONITORS.

CONTRACTOR PERSONNEL AND EQUIPMENT SHALL NOT BE LOCATED WITHIN 50' OF THE CENTERLINE OF ANY RAILROAD TRACK.

ALL EXCAVATED MATERIAL WILL REMAIN ON SITE

APPROVED PROVIDERS FOR LED SIGNAL MODULES ARE:
GENERAL ELECTRIC
DIALIGHT

SEE TABLE FOR PART NUMBERS

DIALIGHT

	PART NO.		PART NO.
RED BALL	433-1210-003XL 433-1270-003XL	RED ARROW	432-1314-001XOD 432-1374-001XOD
YELLOW BALL	433-3230-901XL 433-3270-901XL	YELLOW ARROW	431-3334-901XOD 431-3374-901XOD
GREEN BALL	433-2220-001XL 433-2270-001XL	GREEN ARROW	432-2324-001XOD 432-2374-001XOD

COUNTDOWN PEDESTRIAN 430-6479-001X

GENERAL ELECTRIC

	PART NO.		PART NO.
RED BALL	DR6-RTFB-77A DR6-RCFB-77A	RED ARROW	DR6-RTAAN-17A
YELLOW BALL	DR6-YTFB-77A DR6-YCFB-77A	YELLOW ARROW	DR6-YTAAN-17A DR6-YTAAN-17A-YX
GREEN BALL	DR6-GTFB-77A DR6-GCFB-77A	GREEN ARROW	DR6-GTAAN-17A DR6-GCAAN-17A

COUNTDOWN PEDESTRIAN PS7-CFF1-26A-J
PS7-CFF1-46A-J

COMMITMENTS

NONE

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION
DISTRICT THREE

REVIEWED BY: *Bruce C. Haskins*
DISTRICT OPERATIONS ENGINEER

DATE: March 30, 2012

EXAMINED BY: *Herb Jung*
DISTRICT CONSTRUCTION ENGINEER

Wayne Phillips
DISTRICT MATERIALS ENGINEER

Don Baroni
DISTRICT STUDIES & PLANS ENGINEER

FILE NAME = D366C13-SHT-TS-GENNOTES.DGN	USER NAME = --	DESIGNED - --	REVISED - ----	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	TRAFFIC SIGNAL GENERAL NOTES	F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
		DRAWN - ARR/NV	REVISED - ----			--	D-3 LED RETROFIT 2012-5	--	62	2	
		CHECKED - JKC	REVISED - ----			CONTRACT NO. 66C13					
		DATE - 04/12	REVISED - ----			ILLINOIS FED. AID PROJECT					
					SCALE: N/A	SHEET NO. ___ OF ___ SHEETS		STA. _____ TO STA. _____			