

CONSTRUCTION TYPE CODE 0021			
ITEM NO.	DESCRIPTION	UNIT	TOTAL QUANTITY
67100100	MOBILIZATION	L SUM	1
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1
70102622	TRAFFIC CONTROL AND PROTECTION, STANDARD 701502	L SUM	1
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1
70102630	TRAFFIC CONTROL AND PROTECTION, STANDARD 701601	L SUM	1
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1
86200300	UNINTERRUPTABLE POWER SUPPLY, EXTENDED	EACH	6
87200400	SPAN WIRE	FOOT	300
87200500	TETHER WIRE	FOOT	300
88102825	PEDESTRIAN SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, BRACKET MOUNTED WITH COUNT DOWN TIMER	EACH	618
88800100	PEDESTRIAN PUSH-BUTTON	EACH	799
89502210	MODIFY EXISTING CONTROLLER CABINET	EACH	6
89502375	REMOVE EXISTING TRAFFIC SIGNAL EQUIPMENT	EACH	179
Z0033002	LED SIGNAL FACE RETROFIT, RED BALL	EACH	167
Z0033004	LED SIGNAL FACE RETROFIT, GREEN BALL	EACH	165
Z0033008	LED SIGNAL FACE RETROFIT, YELLOW BALL	EACH	166
Z0033010	LED SIGNAL FACE RETROFIT, YELLOW ARROW	EACH	83
Z0033012	LED SIGNAL FACE RETROFIT, GREEN ARROW	EACH	85
X8620310	REMOVE AND REPLACE BATTERIES FOR UNINTERRUPTABLE POWER SUPPLY EXTENDED	EACH	50

NOTE: FOR QUANTITY BREAKOUTS SEE SHEETS 3 & 4

FILE NAME = 0366C13-SHT-TS-S00.DGN

USER NAME = --

DESIGNED - --

REVISED - ---

PLOT SCALE = N/A

DRAWN - ARR/NV

REVISED - ---

PLOT DATE = 04/12

CHECKED - JKC

REVISED - ---

DATE - 04/12

REVISED - ---

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

TRAFFIC SIGNAL SUMMARY OF QUANTITIES

SCALE: N/A

SHEET NO. ___ OF ___ SHEETS STA. _____ TO STA. _____

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
--	D-3 LED RETROFIT 2012-5	--	62	Z.A.
CONTRACT NO. 66C13			ILLINOIS FED. AID PROJECT	