

**SUMMARY OF QUANTITIES**

QUANTITY  
HSIP I-74 RURAL  
90% FEDERAL  
10% STATE  
0021

CODE NO.	ITEM	UNIT	QUANTITY		
			CHAMPAIGN	VERMILION	TOTAL
20200100	EARTH EXCAVATION	CU YD	2125	865	2990
20400800	FURNISHED EXCAVATION	CU YD	13160	4530	17690
25000210	SEEDING, CLASS 2A	ACRE	13	5	18
25000350	SEEDING, CLASS 7	ACRE	13	5	18
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	1180	440	1620
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	1180	440	1620
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	1180	440	1620
25100115	MULCH, METHOD 2	ACRE	13	5	18
25100630	EROSION CONTROL BLANKET	SQ YD	52	56	108
28000305	TEMPORARY DITCH CHECKS	FOOT	1518	264	1782
28000500	INLET AND PIPE PROTECTION	EACH	49	13	62
28100201	STONE RIPRAP, CLASS A1	TON	234	67	301
44004000	PAVED DITCH REMOVAL	FOOT	1738	0	1738
48101200	AGGREGATE SHOULDERS, TYPE B	TON	4630	1715	6345

QUANTITY  
HSIP I-74 RURAL  
90% FEDERAL  
10% STATE  
0021

CODE NO.	ITEM	UNIT	QUANTITY		
			CHAMPAIGN	VERMILION	TOTAL
50104400	CONCRETE HEADWALL REMOVAL	EACH	132	45	177
54217690	REINFORCED CONCRETE PIPE TEE, 30" PIPE WITH 24" RISER	EACH	2	0	2
54244405	FLUSH INLET BOX FOR MEDIAN, STANDARD 542546	EACH	38	4	42
54246405	INLET BOX, STANDARD 542531	EACH	11	4	15
54248510	CONCRETE COLLAR	CU YD	20.1	5	25.1
550A0070	STORM SEWERS, CLASS A, TYPE 1 15"	FOOT	10	0	10
550A0090	STORM SEWERS, CLASS A, TYPE 1 18"	FOOT	2245	24	2269
550A0120	STORM SEWERS, CLASS A, TYPE 1 24"	FOOT	105	17	122
550A0140	STORM SEWERS, CLASS A, TYPE 1 30"	FOOT	17	8	25
550A0160	STORM SEWERS, CLASS A, TYPE 1 36"	FOOT	0	6	6
55100700	STORM SEWER REMOVAL 15"	FOOT	8	0	8
55100900	STORM SEWER REMOVAL 18"	FOOT	17	2	19
55101200	STORM SEWER REMOVAL 24"	FOOT	86	17	103

\* SPECIALTY ITEM

\*CHAMPAIGN & VERMILION

**McDonough-Whitlow, P.C.**  
Consulting Engineers & Land Surveyors  
138 East Wood Street  
Hillboro, IL 62049  
Phone: 217.532.9233  
Fax: 217.532.6300  
PROFESSIONAL DESIGN No. 184-002754

FILE NAME = 070966-003-S00.dgn	USER NAME = JLM	DESIGNED - JAH	REVISED -
		DRAWN - JLM	REVISED -
		CHECKED - TMM	REVISED -
		DATE -	REVISED -

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

**SUMMARY OF QUANTITIES**

SCALE: NONE SHEET NO. 1 OF 2 SHEETS STA. TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
74	MEDIAN CABLE 2012-1		130	3
CONTRACT NO. 70966			ILLINOIS FED. AID PROJECT	