SCHEDULE OF QUANTITIES

CLASS A PATCH 10 " I 39 MAINLINE SOUTHBOUND											
STATION	LOCATION	LANE	LENGTH	WIDTH	TYPE I	TYPE II	TYPE III	TYPE IV	SAWCUTS	TIE BARS 3/4"	PATCHING REINFORCEMENT
					44200549	44200553	44200557	44200559	44213200	44213204	44213000
			(FT)	(FT)	(SQ. YD.)	(SQ. YD.)	(SQ. YD.)	(SQ. YD.)	(FT)	(EACH)	(SQ. YD.)
357+34	I-39 MAINLINE (RURAL)	SBDL	6.0	6.0	4.0				42.0		4.0
358+82	I-39 MAINLINE (RURAL)	SBDL	20.0	6.0		13.3			84.0	20.0	13.3
359+67	I-39 MAINLINE (RURAL)	SBDL	8.0	6.0		5.3			48.0		5.3
360+10	I-39 MAINLINE (RURAL)	SBDL	6.0	6.0	4.0				42.0		4.0
360+98	I-39 MAINLINE (RURAL)	SBDL	6.0	6.0	4.0				42.0		4.0
361+29	I-39 MAINLINE (RURAL)	SBDL	10.0	12.0		13.3			78.0		13.3
362+65	I-39 MAINLINE (RURAL)	SBDL	6.0	6.0	4.0				42.0		4.0
363+30	I-39 MAINLINE (RURAL)	SBDL	8.0	12.0		10.7			72.0		10.7
363+50	I-39 MAINLINE (RURAL)	SBDL	6.0	6.0	4.0				42.0		4.0
364+00	I-39 MAINLINE (RURAL)	SBDL	6.0	6.0	4.0				42.0		4.0
364+10	I-39 MAINLINE (RURAL)	SBDL	6.0	6.0	4.0				42.0		4.0
365+22	I-39 MAINLINE (RURAL)	SBDL	70.0	6.0				46.7	234.0	70.0	46.7
365+94	I-39 MAINLINE (RURAL)	SBDL	6.0	6.0	4.0				42.0		4.0
366+21	I-39 MAINLINE (RURAL)	SBDL	20.0	6.0		13.3			84.0	20.0	13.3
367+18	I-39 MAINLINE (RURAL)	SBDL	8.0	6.0		5.3			48.0		5.3
368+45	I-39 MAINLINE (RURAL)	SBDL	6.0	6.0	4.0				42.0		4.0
370+21	I-39 MAINLINE (RURAL)	SBDL	6.0	6.0	4.0				42.0		4.0
371+55	I-39 MAINLINE (RURAL)	SBDL	10.0	12.0		13.3			78.0		13.3
372+81	I-39 MAINLINE (RURAL)	SBDL	8.0	12.0		10.7			72.0		10.7
374+11	I-39 MAINLINE (RURAL)	SBDL	6.0	6.0	4.0				42.0		4.0
374+90	I-39 MAINLINE (RURAL)	SBDL	6.0	6.0	4.0				42.0		4.0
375+75	I-39 MAINLINE (RURAL)	SBDL	6.0	6.0	4.0				42.0		4.0
376+21	I-39 MAINLINE (RURAL)	SBDL	6.0	6.0	4.0				42.0		4.0
377+30	I-39 MAINLINE (RURAL)	SBDL	6.0	12.0		8.0			66.0		8.0
467+90	I-39 MAINLINE (RURAL)	SBDL	6.0	12.0		8.0			66.0		8.0
503+00	I-39 MAINLINE (RURAL)	SBDL	20.0	12.0				26.7	108.0	20.0	26.7
506+40	I-39 MAINLINE (RURAL)	SBDL	6.0	6.0	4.0				42.0		4.0
534+50	I-39 MAINLINE (RURAL)	SBDL	8.0	12.0		10.7			72.0		10.7
SOUTHBOUND SUBTOTALS OF CLASS A PATCH, 10 INCH					60.0	112.0		73.3	1740.0	130.0	245.3
SOUTHBOUND SUBTOTALS OF CLASS A PATCH, 10 INCH TOTALS					108.0	383.0	36.7	173.3	4860.0	395.0	701.3

NOTE:

PATCHING QUANTITIES IN ADDITION TO THOSE SHOWN IN THE SCHEDULES HAVE BEEN INCLUDED IN THE SUMMARY OF QUANTITIES, TO BE PLACED AT LOCATIONS DETERMINED BY THE ENGINEER.