

SUMMARY OF QUANTITIES

LOCATION OF WORK:
 COUNTY:
 FUNDING BREAKOUT:
 CONSTRUCTION TYPE CODE:

URBAN
 FAP 71 (IL 54)
 DEWITT CO.
 TWO LANE
 100 % STATE
 0005

RURAL
 FAP 717 (IL 10)
 DEWITT CO.
 RURAL TWO LANE
 100 % STATE
 0005

CODE NO.	DESCRIPTION	UNIT	TOTAL QUANTITY	QUANTITY	QUANTITY
44200934	CLASS B PATCHES, TYPE II, 8 INCH	SQ YD	642.0	401.0	241.0
44200942	CLASS B PATCHES, TYPE III, 8 INCH	SQ YD	41.0	0.0	41.0
44200944	CLASS B PATCHES, TYPE IV, 8 INCH	SQ YD	126.0	60.0	66.0
44201299	DOWEL BARS, 1 1/2"	EACH	1,758.0	1,075.0	683.0
44213100	PAVEMENT FABRIC	SQ YD	166.0	60.0	106.0
44213200	SAW CUTS	FT	4,401.0	2,531.0	1,870.0
44213208	TIE BARS, 1 1/4"	EACH	81.0	15.0	66.0
67100100	MOBILIZATION	L SUM	1.0	0.5	0.5
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1.0	0.5	0.5

* SPECIALTY ITEMS

FILE NAME =	USER NAME = coombessf	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
71&717	D5 PATCHING 2013-2	DEWITT	11			3				
CONTRACT NO. 70974										
ILLINOIS FED. AID PROJECT										
PLOT SCALE = 48.0000 ' / in. PLOT DATE = 3/29/2012		CHECKED -	REVISED -	SCALE:	SHEET NO. OF SHEETS	STA.	TO STA.			