

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
75	84-12; 11-3	*	729	12
STA.		TO STA.		
FED. ROAD DIST. NO. 5 ILLINOIS FED. AID PROJECT				
• SANGAMON AND CHRISTIAN				

LOCATION OF WORK	CHRISTIAN COUNTY		SANGAMON COUNTY	
	80% FEDERAL / 20% STATE		80% FEDERAL / 20% STATE	
	ROADWAY	STRUCTURES	ROADWAY	
	STA. 1415+00.00 TO STA. 1665+04.46	SNO11-2514 SNO11-2515 SNO11-7052 SNO11-7053 MINOR CIP STRUCTURES	STA. 0+00.00 TO STA. 130+00.00	

SUMMARY OF QUANTITIES				CONSTRUCTION TYPE CODE		
CODE NO.	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	0001	0008	0001
54244405	FLUSH INLET BOX FOR MEDIAN, STANDARD 542546	EACH	6			6
54245205	INLET BOX, STANDARD 542511	EACH	4	1		3
550A0120	STORM SEWERS, CLASS A, TYPE 1 24"	FOOT	196	196		
550A0410	STORM SEWERS, CLASS A, TYPE 2 24"	FOOT	94	94		
550B0090	STORM SEWERS, CLASS B, TYPE 1 18"	FOOT	3,804	100		3,704
550B0340	STORM SEWERS, CLASS B, TYPE 2 12"	FOOT	500	250		250
550B0380	STORM SEWERS, CLASS B, TYPE 2 18"	FOOT	8,263	1,055		7,208
550B0680	STORM SEWERS, CLASS B, TYPE 3 18"	FOOT	5,735	812		4,923
55200600	STORM SEWERS JACKED IN PLACE, 18"	FOOT	638			638
59300100	CONTROLLED LOW-STRENGTH MATERIAL	CU YD	20	20		
60100060	CONCRETE HEADWALL FOR PIPE DRAINS	EACH	351	221		130
60100915	PIPE DRAINS 6"	EACH	250	125		125
60100925	PIPE DRAINS 8"	EACH	250	125		125
60100935	PIPE DRAINS 10"	EACH	250	125		125

Default L:\BDOT\030660\dr-ow\sherefs\0672829-ghr-500.dgn 4/25/2012

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: N/A
DATE: 03/06/2012

DRAWN BY: B.J.D.
CHECKED BY: J.M.M.