

SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	L25EC	L25EC	L53EC
				CONSTR. CODE	CONSTR. CODE	CONSTR. CODE
				0005	0014	0021
				ROADWAY 80% FEDERAL 20% STATE	BRIDGE 80% FEDERAL 20% STATE	SAFETY (I-55/IL 104) 90% FEDERAL 10% STATE
40200800	AGGREGATE SURFACE COURSE, TYPE B	TON	27.0	27.0		
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	117.0	116.0		1.0
40600300	AGGREGATE (PRIME COAT)	TON	518.0	515.0		3.0
40600635	LEVELING BINDER (MACHINE METHOD), N70	TON	4941.0	4941.0		
40600645	LEVELING BINDER (MACHINE METHOD), N90	TON	1885.0	1,803.0		82.0
40600895	CONSTRUCTING TEST STRIP	EACH	2.0	2.0		
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	2511.0	2,511.0		
40600985	PORTLAND CEMENT CONCRETE SURFACE REMOVAL - BUTT JOINT	SQ YD	606.0	606.0		
40600990	TEMPORARY RAMP	SQ YD	279.0	279.0		
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	9881.0	9881.0		
40603345	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N90	TON	2863.0			2863.0
40603545	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N90	TON	2,886.0	2,740.0	23.0	123.0
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	224.0	224.0		
44000157	HOT-MIX ASPHALT SURFACE REMOVAL, 2"	SQ YD	31036.0	31036.0		
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	7783.0	7,028.0		755.0

✱SPECIALTY ITEM

FILE NAME =	USER NAME = sparksgu	DESIGNED - ETJ	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES		F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
c:\pwwork\pwwork\sparksgu\d0245433\0672E12.sht-500.dgn		DRAWN - ETJ	REVISED -		753	(140RS-6, 141RS-7)I	SANGAMON	98	4		
PLOT SCALE = 100.0000' / in.		CHECKED - RTS	REVISED -		SCALE: SHEET 2 OF 6 SHEETS STA. TO STA.		CONTRACT NO. 72E12		ILLINOIS FED. AID PROJECT		
PLOT DATE = Apr-09-2012 04:21:42PM		DATE - 01-05-12	REVISED -								