

SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	L25EC	L25EC	LS3EC
				CONSTR. CODE	CONSTR. CODE	CONSTR. CODE
				0005	0014	0021
				ROADWAY 80% FEDERAL 20% STATE	BRIDGE 80% FEDERAL 20% STATE	SAFETY (I-55/IL 104) 90% FEDERAL 10% STATE
44004250	PAVED SHOULDER REMOVAL	SQ YD	764.0	439.0		325.0
44200144	PAVEMENT PATCHING, TYPE II, 12 INCH	SQ YD	150.0	150.0		
44200148	PAVEMENT PATCHING, TYPE III, 12 INCH	SQ YD	150.0	150.0		
48101200	AGGREGATE SHOULDERS, TYPE B	TON	2448.0	2432.0		16.0
48203021	HOT-MIX ASPHALT SHOULDERS, 6"	SQ YD	67.0	67.0		
48203033	HOT-MIX ASPHALT SHOULDERS, 9"	SQ YD	333.0			333.0
50102400	CONCRETE REMOVAL	CU YD	1.3		1.3	
50300255	CONCRETE SUPERSTRUCTURES	CU YD	1.3		1.3	
50300260	BRIDGE DECK GROOVING	SQ YD	707.0		707.0	
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	90.0		90.0	
60107700	PIPE UNDERDRAINS 6"	FOOT	374.0			374.0
60608600	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-6.06	FOOT	6828.0	6828.0		
60610400	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-6.24	FOOT	477.0	477.0		
60618300	CONCRETE MEDIAN SURFACE, 4 INCH	SQ FT	5217.0	5,217.0		
60624600	CORRUGATED MEDIAN	SQ FT	1416.0	1,416.0		

*SPECIALTY ITEM

FILE NAME =	USER NAME = sparksgw	DESIGNED - ETJ	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
es:\pw\work\pwidot\sparksgw\d0245433\0672E12.sht-500.dgn	DRAWN - ETJ	REVISOR -				753	(140RS-6, 14IRS-7)I	SANGAMON	98	5	
PLOT SCALE = 100.0000' = 1" = 100'	CHECKED - RTS	REVISOR -				SCALE: SHEET 3 OF 6 SHEETS STA. TO STA.		CONTRACT NO. 72E12			
PLOT DATE = Apr-09-2012 03:26:57PM	DATE - 01-05-12	REVISOR -				ILLINOIS FED. AID PROJECT					