

# SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	L25EC	L2SEC	LS3EC
				CONSTR. CODE	CONSTR. CODE	CONSTR. CODE
				0005	0014	0021
				ROADWAY 80% FEDERAL 20% STATE	BRIDGE 80% FEDERAL 20% STATE	SAFETY (I-55/IL 104) 90% FEDERAL 10% STATE
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	4.0	3.0		1.0
67100100	MOBILIZATION	L SUM	1.0	0.8		0.2
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1.0	1.0		
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1.0	1.0		
70100100	TRAFFIC CONTROL AND PROTECTION, STANDARD 701316	EACH	1.0	1.0		
70100500	TRAFFIC CONTROL AND PROTECTION, STANDARD 701326	L SUM	1.0	0.8		0.2
70100825	TRAFFIC CONTROL AND PROTECTION, STANDARD 701456	L SUM	1.0	.8		0.2
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	15.0	10.0		5.0
<b>70106500</b>	<b>TEMPORARY BRIDGE TRAFFIC SIGNALS</b>	<b>EACH</b>	<b>1.0</b>	<b>1.0</b>		
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	4.0	4.0		
70300100	SHORT TERM PAVEMENT MARKING	FOOT	<del>38,400.0</del>	<del>32,400.0</del>		<del>6,000.0</del>
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SO FT	<del>4,230.0</del>	<del>3,565.0</del>		<del>665.0</del>
X 72800100	TELESCOPING STEEL SIGN SUPPORT	FOOT	1400.0	1400.0		
X 78001120	PAINT PAVEMENT MARKING - LINE 5"	FOOT	85032.0	85032.0		
X 78004200	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - INLAID - LETTERS AND SYMBOLS	SO FT	572.1	540.9		31.2

X SPECIALTY ITEM

FILE NAME =	USER NAME = sparksgu	DESIGNED - ETJ	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>SUMMARY OF QUANTITIES</b>	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
cr:\pwork\pwidot\sparksgu\d0245433\0678E12-sh-500.dgn		DRAWN - ETJ	REVISED -			753	(140R5-6, 141R5-7)I	SANGAMON	98	6
PLOT SCALE = 100.0000' / 1" =		CHECKED - RTS	REVISED -		SCALE:					
PLOT DATE = Apr-09-2012 03:26:58PM		DATE - 01-05-12	REVISED -		SHEET 4 OF 6 SHEETS	STA.	TO STA.			CONTRACT NO. 72E12
										ILLINOIS FED. AID PROJECT