

PAVING SCHEDULE (Cont' d)			LENGTH	PAVEMENT WIDTH	SHOULDER WIDTH	AREA	EXCAVATING AND GRADING EXISTING SHOULDER	AGGREGATE SHOULDERS, TYPE B	BITUMINOUS MATERIALS (PRIME COAT)	AGGREGATE (PRIME COAT)	HOT-MIX ASPHALT SURFACE REMOVAL (BUTT-JOINT)	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	HOT-MIX ASPHALT SURFACE REMOVAL (VARIABLE DEPTH)	LEVELING BINDER (MACHINE METHOD), N70	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N70	INCIDENTAL HOT-MIX ASPHALT SURFACING
STATION	TO	STATION	FEET	FEET	FEET	SQ YD	UNIT	TON	GALLON	TON	SQ. YD.	SQ. YD.	SQ. YD.	TON	TON	TON
1143+65.00	TO	1195+82.00	5,217.0	26.0	8.0	15,071.3	104.3	396.1	1,507.1	30.1	0.0	0.0	15071.3	633.0	1,387.5	17.5
1195+82.00	TO	1234+59.00	3,877.0	26.0	8.0	11,200.2	77.5	294.4	1,120.0	22.4	0.0	0.0	11200.2	470.4	1,031.2	57.8
1234+59.00	TO	1280+07.96	4,549.0	26.0	8.0	13,141.4	91.0	345.4	1,314.2	26.3	0.0	0.0	13141.4	551.9	1,209.9	21.8
1280+07.96	TO	1282+27.96	220.0	26.0	8.0	635.6	4.4	16.7	63.6	1.3	0.0	0.0	635.6	26.7	58.5	0.0
1282+27.96	TO	1295+34.37	1,306.4	26.0	8.0	3,774.1	26.1	99.2	377.4	7.5	0.0	0.0	3774.1	158.5	347.5	0.0
1295+34.37	=	1295+38.60	0.0	0.0	8.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
1295+38.60	TO	1295+55.43	16.8	Variable	8.0	46.7	0.3	1.3	4.7	0.1	0.0	0.0	46.7	2.0	4.3	0.0
1295+55.43	TO	1295+90.43	35.0	Variable	8.0	97.2	0.7	0.0	9.7	0.2	0.0	0.0	97.2	4.1	9.0	0.0
1295+90.43	TO	1300+40.60	450.2	24.0	0.0	1,200.5	0.0	0.0	120.1	2.4	0.0	1200.5	0.0	50.4	111.3	0.0
1300+40.60	=	1300+36.37	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
1300+36.37	TO	1306+22.20	585.8	24.0	0.0	1,562.2	0.0	0.0	156.2	3.1	0.0	1562.2	0.0	65.6	144.9	0.0
1306+22.20	=	1306+28.50	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
1306+28.50	TO	1317+32.26	1,103.8	24.0	0.0	2,943.4	0.0	0.0	294.3	5.9	0.0	2943.4	0.0	123.6	273.0	0.0
SHEET TOTALS			17,361			49,673	304	1,153	4,967	99	0	5,706	43,967	2,086	4,577	97
PROJECT TOTALS			54,505			193,747	1,323	5,021	19,375	387	80	12,676	180,991	8,137	17,872	336

FILE NAME =	USER NAME = steffenmk	DESIGNED -	REVISED -
ct:\pw\work\p\dot\stevfenmk\dms52759\d74247-sht-sch.dgn		DRAWN -	REVISED -
	PLOT SCALE = 100.0000' / 1in.	CHECKED -	REVISED -
	PLOT DATE = 3/23/2012	DATE -	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SCHEDULE OF QUANTITIES

SCALE: NA SHEET NO. 4 OF 8 SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
116	(126,127)RS-5	EDWARDS	51	16
CONTRACT NO. 74247			ILLINOIS FED. AID PROJECT	