

PAVEMENT MARKING SCHEDULE (Cont'd)			LENGTH	SHORT-TERM PAVEMENT MARKING	TEMPORARY PAVEMENT MARKING-LINE 4" (YELLOW)	TEMPORARY PAVEMENT MARKING-LINE 4" (DBL YELLOW)	TEMPORARY PAVEMENT MARKING-LINE 4" (YELLOW SKIP-DASH)	TEMPORARY PAVEMENT MARKING-LINE 4" (WHITE)	WORK ZONE PAVEMENT MARKING REMOVAL	PAINT PAVEMENT MARKING-LINE 4" (YELLOW)	PAINT PAVEMENT MARKING-LINE 4" (DBL YELLOW)	PAINT PAVEMENT MARKING-LINE 4" (YELLOW SKIP-DASH)	PAINT PAVEMENT MARKING-LINE 4" (WHITE)	THERMOPLASTIC PAVEMENT MARKING-LINE 4" (YELLOW SKIP-DASH)	RAISED REFLECTIVE PAVEMENT MARKER, BI-DIRECTIONAL (AMBER)
STATION	TO	STATION	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	SQ FT	FOOT	FOOT	FOOT	FOOT	FOOT	EACH
1122+39.00	TO	1131+57.00	918.0	367.2	918.0	0.0	229.5	1,784.0	1,008.0	918.0	0.0	229.5	1,784.0	0.0	11
1131+57.00	TO	1132+93.00	136.0	54.4	0.0	272.0	0.0	272.0	185.9	0.0	272.0	0.0	272.0	0.0	2
1132+93.00	TO	1143+27.00	1,034.0	413.6	1,034.0	0.0	258.5	2,068.0	1,154.9	1,034.0	0.0	258.5	2,068.0	0.0	13
1143+27.00	TO	1146+67.00	340.0	136.0	0.0	0.0	85.0	650.0	256.4	0.0	0.0	85.0	650.0	0.0	4
1146+67.00	TO	1156+66.00	999.0	399.6	999.0	0.0	249.8	1,998.0	1,115.8	999.0	0.0	249.8	1,998.0	0.0	12
1156+66.00	TO	1157+19.00	53.0	21.2	0.0	106.0	0.0	106.0	72.4	0.0	106.0	0.0	106.0	0.0	1
1157+19.00	TO	1167+92.00	1,073.0	429.2	1,073.0	0.0	268.3	2,146.0	1,198.4	1,073.0	0.0	268.3	2,146.0	0.0	13
1167+92.00	TO	1227+22.00	5,930.0	2,372.0	0.0	0.0	1,482.5	11,800.0	4,626.1	0.0	0.0	1,482.5	11,800.0	0.0	74
1227+22.00	TO	1236+46.00	924.0	369.6	924.0	0.0	231.0	1,798.0	1,015.3	924.0	0.0	231.0	1,798.0	0.0	12
1236+46.00	TO	1237+11.00	65.0	0.0	0.0	0.0	16.3	130.0	48.8	0.0	0.0	16.3	130.0	0.0	1
1237+11.00	TO	1245+87.00	876.0	350.4	876.0	0.0	219.0	1,752.0	978.4	876.0	0.0	219.0	1,752.0	0.0	11
1245+87.00	TO	1253+49.00	762.0	304.8	0.0	0.0	190.5	1,524.0	597.0	0.0	0.0	190.5	1,524.0	0.0	10
1253+49.00	TO	1264+85.00	1,136.0	454.4	1,136.0	0.0	284.0	2,272.0	1,268.8	1,136.0	0.0	284.0	2,272.0	0.0	14
1264+85.00	TO	1265+55.00	70.0	28.0	0.0	0.0	17.5	140.0	54.8	0.0	0.0	17.5	140.0	0.0	1
1265+55.00	TO	1275+58.00	1,003.0	401.2	1,003.0	0.0	250.8	2,006.0	1,120.2	1,003.0	0.0	250.8	2,006.0	0.0	13
1275+58.00	TO	1290+65.00	1,507.0	602.8	0.0	0.0	376.8	3,014.0	1,180.7	0.0	0.0	376.8	3,014.0	0.0	19
1290+65.00	TO	1295+34.37	469.4	187.7	0.0	0.0	117.3	938.7	367.7	0.0	0.0	117.3	938.7	0.0	6
1295+34.37	=	1295+38.60	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0
1295+38.60	TO	1296+00.00	61.4	24.6	0.0	0.0	15.3	122.8	48.1	0.0	0.0	15.3	122.8	0.0	1
1296+00.00	TO	1300+40.60	440.6	176.2	0.0	0.0	110.2	0.0	0.0	0.0	0.0	0.0	0.0	110.2	6
1300+40.60	=	1300+36.37	0.0	0.0	0.0	0.0	0.0	0.0	68.4	0.0	0.0	0.0	0.0	0.0	0
1300+36.37	TO	1306+22.20	585.8	234.3	0.0	0.0	146.5	0.0	0.0	0.0	0.0	0.0	0.0	146.5	7
1306+22.20	=	1306+28.50	0.0	0.0	0.0	0.0	0.0	0.0	128.8	0.0	0.0	0.0	0.0	0.0	0
1306+28.50	TO	1317+32.26	1,103.8	441.5	0.0	0.0	275.9	0.0	0.0	0.0	0.0	0.0	0.0	275.9	14
SHEET TOTALS			19,487	7,769	7,963	378	4,824	34,522	16,495	7,963	378	4,292	34,522	533	244
PROJECT TOTALS			68,538.0	27,390	21,425	2,328	16,843	131,315	59,547	21,425	2,328	16,311	131,315	533	857