SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNIT	100% STATE URBAN TOTAL QUANTITY	CONSTRUCTION TYPE CODE: LANDSCAPING 0031			
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	238	238			
20101100	TREE TRUNK PROTECTION	EACH	11	11			
20101700	SUPPLEMENTAL WATERING	UNIT	200	200			
25000312	SEEDING, CLASS 4A	ACRE	14.00	14.00			
25000322	SEEDING, CLASS 5A	ACRE	1.75	1.75			
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	650	650			
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	1,300	1,300			
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	1,300	1,300			
25000700	AGRICULTURAL GROUND LIMESTONE	TON	26	26			
25000775	SELECTIVE MOWING STAKES	EACH	210	210			
25100630	EROSION CONTROL BLANKET	SQ YD	139,150	139,150			
28000305	TEMPORARY DITCH CHECKS	FOOT	270	270			
28000400	PERIMETER EROSION BARRIER	FOOT	9,415	9,415			
28000500	INLET AND PIPE PROTECTION	EACH	7	7			

• DENOTES SPECIALTY ITEMS ■ 0042