

LOCATION 2 & 3 PAVEMENT MARKING SCHEDULE

LOCATION STATION TO STATION	THERMOPLASTIC PAVEMENT MARKING					SHORT TERM PAVEMENT MARKING				NOTES		
	4" WHITE EDGELINE		4" SOLID YELLOW LINE		4" YELLOW SKIP DASH	4" SKIP DASH	4" DIAGONAL EDGELINE					
	LEFT	RIGHT	LEFT	RIGHT			LEFT	RIGHT				
	FEET	FEET	FEET	FEET	FEET	FEET	FEET	FEET	FEET			
FAP 42 (IL 13/127)												
LOCATION 2, STA 1229+00 TO STA 1262+53												
	1229+00	TO	1234+80.8			581	581				NPZ	
	1234+80.8	TO	1237+44.8	214		264	264				NPZ	
	1237+44.8	TO	1239+60	165		215		54	22		NPZ	
EQ. STA 1239+60 BK = STA 1240+24 AH												
	1240+24	TO	1240+61.6	38		38		9	4		NPZ	
	1240+61.6	TO	1262+53	1941				548	219			
LOCATION 2 TOTALS:				2358		1097	845	611	244			
LOCATION 3, STA 190+00 TO STA 498+65.8												
	190+00	TO	191+58.4	158	158			40	16	6	6	
	191+58.4	TO	197+92	634	634	634		158	63	25	25	NPZ
	197+92	TO	228+12.16	3020	3020			755	302	121	121	
	228+12.16	TO	239+57.92	1146	1146		1146	286	115	46	46	NPZ
	239+57.92	TO	254+94.4	1462	1536	1537	1537	384	154	58	61	NPZ
	254+94.4	TO	262+33.6	739	739	739		185	74	30	30	NPZ
	262+33.6	TO	272+11.372	978	978			244	98	39	39	
OMISSION SN 073-0025												
	273+58.62	TO	281+06.09	748	748			187	75	30	30	
OMISSION SN 073-0026												
	283+45.09	TO	344+65.12	6060	6077			1530	612	242	243	
	344+65.12	TO	349+93.12	523	523		523	131	52	21	21	NPZ
	349+93.12	TO	353+09.90	317	278			79	32	13	11	
	353+09.90	TO	360+43.84	734	734	734		183	73	29	29	NPZ
	360+43.84	TO	365+77.12	533	533			133	53	21	21	
	365+77.12	TO	377+38.72	1162	1162		1162	290	116	46	46	NPZ
	377+38.72	TO	380+55.52	317	256	317	317	79	32	13	10	NPZ
	380+55.52	TO	390+05.92	950	950	950		238	95	38	38	NPZ
	390+05.92	TO	454+84.5	6356	6324			1620	648	254	253	
EQ. STA 454+84.5 BK = STA 455+00 AH												
	455+00	TO	498+65.8	4340	4313			1091	437	174	173	TEMPORARY PAVEMENT MARKERS, 4"
LOCATION 3 TOTALS:				21291	21149	2001	2001	5375	2150	852	846	
LOCATION 2 & 3 TOTALS:				23649	21149	3099	2846	5986	2394	852	846	
TOTAL FOR EACH TYPE				56729				4092				56729

- TEMPORARY PAVEMENT MARKING - LINE 4" QUANTITY IS EQUAL TO THERMOPLASTIC PAVEMENT MARKING - LINE 4" FOR ALL STATIONS
- WORK ZONE PAVEMENT MARKING REMOVAL INCLUDES TEMPORARY AND SHORT TERM PAVEMENT MARKINGS
- FOR LOCATION 1, EDGELINE SIGNIFIES LINE THAT SEPERATES DRIVING LANE FROM PARKING LANE.
- FOR LOCATION 1, THERE IS NO EDGELINE ON RIGHT SIDE.