SUMMARY OF QUANTITIES

		COUNTY		JACKSON	PERRY		
		LOCATION		1	2		3
		ROUTE		IL 127 (FAU 9668/9669)	IL 13/127 (FAP 42)		IL 127 (FAP42)
		CONSTRUCTION TYPE		0005	0005		0005
		FUNDING		80% FED/ 20% STATE	80% FED / 20% STATE	80% FED / 20% CITY	80% FED / 20% STATE
CODE NUMBER	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	URBAN	URBAN	CITY	RURAL
				QUANTITY	QUANTITY	QUANTITY	QUANTITY
				L20EU, 01	L05EL, 01	L05EL, 02	L05EC, 01
X 63000001	STEEL PLATE BEAM GUARDRAIL, TYPE A, 6 FOOT POSTS	FOOT	400				400
X 63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	8				8
X 63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	8				8
63200310	GUARDRAIL REMOVAL	FOOT	800				800
67100100	MOBILIZATION	L SUM	1.0	0.25	0.25	0.25	0.25
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1.0	0.50			0.50
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1.0				1.00
70100600	TRAFFIC CONTROL AND PROTECTION, STANDARD 701336	L SUM	1.0				1.00
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1.0	0.333		0.333	0.334
70300100	SHORT TERM PAVEMENT MARKING	FOOT	4336	244	244		3848
70300220	TMEPORARY PAVEMENT MARKING - LINE 4"	FOOT	64787	8058	4911		51818
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	64	64			
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	23168	2895	1718		18555
X 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	64787	8058	4911		51818
X 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	64	64			
X 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	450	35	34		381
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	450	35	34		381
Z0034105	MATERIAL TRANSFER DEVICE	TON	6824				6824

XSPECIALTY ITEM

*FAP 42/FAU 9668/9669 *PERRY & JACKSON

FILE NAME = c:\pw_work\pwidot\lavenderba\d0302467\78292-sht-plan.dgn	USER NAME = $USER$	DESIGNED -	REVISED -
		DRAWN -	REVISED -
	PLOT SCALE = 100.0000 ' / in.	CHECKED -	REVISED -
	PLOT DATE = 3/22/2012	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: SHEET OF SHEETS STA. TO STA.

F.A.* RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	(8,103) RS-2; (12-2) RS-2	*	19	6

CONTRACT NO. 78292

ILLINOIS FED. AID PROJECT