STORM SEWER PIPE SCHEDULE

LOCATION	PRECAST REINFORCED CONCRETE FLARED END SECTIONS	STORM SEWERS, CLASS A, TYPE 1					STORM SEWERS CLASS A, TYPE 2		STORM SEWERS TYPE 1 REINFORCED CONCRETE ELLIPTICAL PIPE
	18" (EACH)	12" (FOOT)	15" (FOOT)	18" (FOOT)	24" (FOOT)	30" (FOOT)	24" (FOOT)	30" (FOOT)	SPAN 53, RISE 34 (FOOT)
STA 0+30 TO 0+68 LT						38			
STA 0+68 TO 1+25 LT						57			
STA 1+25		55							
STA 1+25 TO 2+00 LT						75			
STA 2+00		75							
STA 2+00 TO 3+75 LT						175			
STA 3+75		75							
STA 3+75 TO 5+50 LT						175			
STA 5+50		75							
STA 5+50 TO 7+70 LT					220				
STA 7+70		75							
STA 7+70 TO 10+10 LT							240		
STA 10+10		75							
STA 10+10 TO 11+75 LT					165				
STA 11+75		75							
STA 11+75 TO 13+75 LT					200				
STA 13+75		75							
STA 13+75 TO 15+00 LT					125				
STA 15+00		75							
STA 15+00 TO 16+70 LT					170				
STA 16+70		75							
STA 16+70 TO 18+30 LT				165					
STA 18+30		75							
STA 18+30 TO 21+38 LT			303						
STA 21+38		75							
STA 21+38 TO 23+00 LT			162						
STA 23+00		75							
STA 23+00 TO 25+00 LT		200							
STA 25+00		75							
STA 25+00 TO 26+50 LT		150							
STA 26+50		55							
STA 30+50		55							
STA 30+50 TO 32+10 RT		160							
STA 32+10		75							
STA 32+10 TO 33+58 RT			148						
STA 93+85 TO 94+40 RT						55			
STA 94+40 TO 94+98 RT						58			
STA 94+98 TO 95+67 RT						69			
STA 95+67 TO 99+31 RT								364	
STA 99+31 TO 100+33 RT						102			
STA 100+33 TO 101+22 RT	1			89					
STA 316+70 TO 320+62									392
TOTAL	**1**	**1725**	**613**	**254**	**880**	**804**	**240**	**364**	**392**

PAVEMENT MARKING SCHEDULE

LOCATION	THERMOPLASTIC PAVEMENT MARKING					
	LETTERS AND SYMBOLS (SQ FT)	LINE 4" (FOOT)	LINE 8" (FOOT)	LINE 12" (FOOT)	LINE 24" (FOOT)	
STA 0+47			180	180		CROSS WALK WHITE
STA 0+54					42	STOP BAR WHITE
STA 0+54 TO 2+00			146			LINE WHITE
STA 0+54 TO 2+53		398		6		LINE YELLOW
STA 0+70	15.6					LEFT ARROW WHITE
STA 1+95	15.6					LEFT ARROW WHITE
STA 2+00 TO 3+00			25			DOTTED LINE WHITE
STA 4+36 TO 5+57			30			DOTTED LINE WHITE
STA 5+04 TO 6+72		336		6		LINE YELLOW
STA 5+57 TO 6+92			115			LINE WHITE
STA 5+65	15.6					LEFT ARROW WHITE
STA 6+55	15.6					LEFT ARROW WHITE
STA 6+72					12	STOP BAR WHITE
STA 7+19 LT			48	48	12	CROSSWALK WHITE AND STOP BAR
STA 7+19 RT			80	78	20	CROSS WALK WHITE AND STOP BAR
STA 7+65					12	STOP BAR WHITE
STA 7+66 TO 8+81			115			LINE WHITE
STA 7+66 TO 9+34		336		6		LINE YELLOW
STA 7+80	15.6					LEFT ARROW WHITE
STA 8+81 TO 9+81			25			DOTTED LINE WHITE
STA 8+75	15.6					LEFT ARROW WHITE
STA 10+74 TO 11+74			25			DOTTED LINE WHITE
STA 11+21 TO 12+89		336		6		LINE YELLOW
STA 11+74 TO 12+89			115			LINE WHITE
STA 11+80	15.6					LEFT ARROW WHITE
STA 12+75	15.6					LEFT ARROW WHITE
STA 12+89					12	STOP BAR WHITE
STA 12+97			98	96		CROSS WALK WHITE
STA 13+27 LT			60	60		CROSS WALK WHITE
STA 13+57			88	84		CROSS WALK WHITE
STA 18+13 TO 19+13			25			DOTTED LINE WHITE
STA 18+60 TO 20+28		336		6		LINE YELLOW
STA 19+13 TO 20+28			115			LINE WHITE
STA 19+20	15.6					LEFT ARROW WHITE
STA 20+15	15.6					LEFT ARROW WHITE
STA 20+28					12	STOP BAR WHITE
STA 20+66			100	96		CROSS WALK WHITE
STA 20+88 RT			60	60	14	CROSS WALK WHITE AND STOP BAR
STA 20+91 LT			60	60		CROSS WALK WHITE
STA 21+23			100	96		CROSS WALK WHITE
STA 21+50					12	STOP BAR WHITE
STA 21+50 TO 22+65			115			LINE WHITE
STA 21+50 TO 23+18		336		6		LINE YELLOW
STA 21+65	15.6					LEFT ARROW WHITE
STA 22+60	15.6					LEFT ARROW WHITE
STA 22+65 TO 23+65			25			DOTTED LINE WHITE
STA 26+01			62	48		CROSS WALK WHITE AND STOP BARS
STA 31+73 TO 32+73			25			DOTTED LINE WHITE
STA 32+20 TO 33+88		336		6		LINE YELLOW
STA 32+73 TO 33+88			115			LINE WHITE
STA 32+80	15.6					LEFT ARROW WHITE
STA 33+70	15.6					LEFT ARROW WHITE
STA 33+88					12	STOP BAR WHITE
TOTAL	**218.4**	**2414**	**1952**	**948**	**160**	

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	**	KANKAKEE	36	6

CONTRACT NO. 87315

FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT

* BURNS ROAD WEST – FAU 6212
** 03-00058-01-FP

TYSON ENGINEERING, INC.
CONSULTING CIVIL ENGINEERS
LAND SURVEYORS
DESIGN FIRM LICENSE #184-001136
367 SOUTH SCHUYLER AVENUE
KANKAKEE, ILLINOIS 60901
PHONE (815) 932-7406

This document and the ideas and designs incorporated herein, as an instrument of professional service, is the property of Tyson Engineering Inc. and is not to be used in whole or in part, for any other project without written authorization of Tyson Engineering Inc.

Do not scale drawings. Use dimensions only.

Contractor shall be responsible for verifying all dimensions.

Information hereon and herein is confidential.

REVISIONS

NO.	DATE	BY	DESCRIPTION

SCHEDULE OF QUANTITIES

PROJECT:
PROPOSED IMPROVEMENTS FOR
BURNS ROAD WEST
FROM CAREER CENTER ROAD
TO BURNING BUSH DRIVE

SECTION
03-00058-01-FP

DATE:	3/23/12	JOB NO.	E05055
SCALE:	N/A	FILE NO.	
DRAWN BY:	MRG	SHEET	6
CHECKED BY:	SRM		36