WIRING SCHEDULE

POLE NUMBER	LOCATION	CONDUIT UNDERGROUND	ELECTRIC CABLE IN CONDUIT, 600V (XPL-TYPE USE)	
		2" DIA PVC (FOOT)	3-1C NO.4 (FOOT)	5-1C NO.2 (FOOT)
1 TO 2	STA 0-28 TO 0+65	105		111
2 TO 3	STA 0+65 TO 1+54	144		150
3 TO 4	STA 1+54 TO 2+56	136		142
4 TO 5	STA 2+56 TO 3+93	141		147
5 TO 6	STA 3+93 TO 5+00	111		117
6 TO 7	STA 5+00 TO 6+68	198		204
7 TO 8	STA 6+68 TO 6+68	56		62
8 TO 9	STA 6+68 TO 7+75	111		117
9 TO 10	STA 7+75 TO 8+35	114		120
10 TO 11	STA 8+35 TO 9+37	126		132
11 TO 12	STA 9+37 TO 10+76	143		149
12 TO 13	STA 10+76 TO 11+93	146		152
13 TO 14	STA 11+93 TO 12+65	126		132
14 TO 15	STA 12+65 TO 13+90	154		160
15 TO 16	STA 13+90 TO 15+45	159		165
16 TO 17	STA 15+45 TO 17+02	161		167
17 TO 18	STA 17+02 TO 18+57	159		165
18 TO 19	STA 18+57 TO 19+67	144		150
19 TO 20	STA 19+67 TO 20+44	131		137
20 TO 21	STA 20+44 TO 20+67	99		105
21 TO 22	STA 20+67 TO 21+31 RT	84		90
22 TO 23	STA 21+31 TO 21+88	111		117
23 TO 24	STA 21+88 TO 22+71	137		143
24 TO 25	STA 22+71 TO 23+82	140		146
25 TO 26	STA 23+82 TO 25+93	215		221
26 TO CONT.	STA 25+93 TO 26+08	57		63
CONT. TO 27	STA 26+08 TO 27+42	176	182	
27 TO 28	STA 27+42 TO 28+92	154	160	
28 TO 29	STA 28+92 TO 30+41	153	159	
29 TO 30	STA 30+41 TO 31+90	153	159	
30 TO 31	STA 31+90 TO 32+95	136	142	
31 TO EXIST.	STA 32+95 TO 34+09	168	174	
	TOTAL	4348	976	3564

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	**	KANKAKEE	36	9

CONTRACT NO. 87315

FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT

* BURNS ROAD WEST – FAU 6212
** 03-00058-01-FP

TYSON ENGINEERING, INC.
CONSULTING CIVIL ENGINEERS
LAND SURVEYORS
DESIGN FIRM LICENSE #184-001136
367 SOUTH SCHUYLER AVENUE
KANKAKEE, ILLINOIS 60901
PHONE (815) 932-7406

This document and the ideas and designs incorporated herein, as an instrument of professional service, is the property of Tyson Engineering Inc. and is not to be used in whole or in part, for any other project without written authorization of Tyson Engineering Inc.

Do not scale drawings. Use dimensions only.

Contractor shall be responsible for verifying all dimensions.

Information hereon and herein is confidential.

REVISIONS

NO.	DATE	BY	DESCRIPTION

SCHEDULE OF QUANTITIES

PROJECT:
PROPOSED IMPROVEMENTS FOR
BURNS ROAD WEST
FROM CAREER CENTER ROAD
TO BURNING BUSH DRIVE

SECTION
03-00058-01-FP

DATE:	3/23/12	JOB NO. E05055
SCALE:	N/A	FILE NO.
DRAWN BY:	MRG	SHEET 9
CHECKED BY:	SRM	36