LIGHTING SCHEDULE

POLE NUMBER	LOCATION	LUMINAIRE SODIUM VAPOR HORZ. MOUNT		LIGHT POLE ALUMINUM		LIGHT POLE FOUNDATION 24" DIA. (FOOT)	BREAKAWAY DEVICE, COUPLING WITH ALUMINUM SKIRT (EACH)
		150 WATT (EACH)	250 WATT (EACH)	33 FT. M.H. 10 FT. TRUSS ARM (EACH)	33 FT. M.H. 10 FT. TRUSS ARM - TWIN (EACH)		
1	STA 0-28		1	1		5.5	4
2	STA 0+65 - 39 RT		1	1		5.5	4
3	STA 1+54 - 26 LT	1		1		5.5	4
4	STA 2+56 - 3 RT	2			1	5.5	4
5	STA 3+93	2			1	5.5	4
6	STA 5+00 - 3 LT	2			1	5.5	4
7	STA 6+68 - 26 RT	1		1		5.5	4
8	STA 6+68 - 26 LT	1		1		5.5	4
9	STA 7+75 - 26 LT		1	1		5.5	4
10	STA 8+35 - 26 RT	1		1		5.5	4
11	STA 9+37 - 4 RT	2			1	5.5	4
12	STA 10+76 - 1 LT	2			1	5.5	4
13	STA 11+93 - 26 RT	1		1		5.5	4
14	STA 12+65 - 27 LT		1	1		5.5	4
15	STA 13+90		2		1	5.5	4
16	STA 15+45	2			1	5.5	4
17	STA 17+02	2			1	5.5	4
18	STA 18+57 - 3 LT	2			1	5.5	4
19	STA 19+67 - 26 RT	1		1		5.5	4
20	STA 20+44 - 30 LT		1	1		5.5	4
22	STA 21+31 - 30 RT		1	1		5.5	4
21	STA 20+67 - 78 RT	1		1		5.5	4
23	STA 21+88 - 26 LT	1		1		5.5	4
24	STA 22+71 - 26 RT	1		1		5.5	4
25	STA 23+82	2			1	5.5	4
26	STA 25-93	2			1	5.5	4
27	STA 27+42	2			1	5.5	4
28	STA 28+92	2			1	5.5	4
29	STA 30+41	2			1	5.5	4
30	STA 31+90 - 2 LT	2			1	5.5	4
31	STA 32+95 - 26 RT	1		1		5.5	4
	TOTAL	38	8	16	15	170.5	124

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	**	KANKAKEE	36	10

CONTRACT NO. 87315

FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT

* BURNS ROAD WEST - FAU 6212
** 03-00058-01-FP

TYSON ENGINEERING, INC.
CONSULTING CIVIL ENGINEERS
LAND SURVEYORS
DESIGN FIRM LICENSE #184-001136
367 SOUTH SCHUYLER AVENUE
KANKAKEE, ILLINOIS 60901
PHONE (815) 932-7406

This document and the ideas and designs incorporated herein, as an instrument of professional service, is the property of Tyson Engineering Inc. and is not to be used in whole or in part, for any other project without written authorization of Tyson Engineering Inc.

Do not scale drawings. Use dimensions only.

Contractor shall be responsible for verifying all dimensions.

Information hereon and herein is confidential.

REVISIONS

NO.	DATE	BY	DESCRIPTION

SCHEDULE OF QUANTITIES

PROJECT:
PROPOSED IMPROVEMENTS FOR
BURNS ROAD WEST
FROM CAREER CENTER ROAD
TO BURNING BUSH DRIVE

SECTION
03-00058-01-FP

DATE:	3/23/12	JOB NO.	E05055
SCALE:	N/A	FILE NO.	
DRAWN BY:	MRG	SHEET	10
CHECKED BY:	SRM		36