

CHAMLIN & ASSOCIATES, INC. © 2010  
 Drawing Name: G:\Users\G\Area\66022-01-Diamond-Will-Road-&-L-113-Enr-Survey\CAD\3D\PLANS-EXTENDED\006-500.dwg Last Modified: Apr 11, 2012 - 12:45pm Plotted on: Apr 16, 2012 - 9:45am by nnsdq

ITEM NO.	DESCRIPTION	UNIT	TOTAL QUANTITY	PARTICIPATING	NON-PARTICIPATING
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	38	23	15
* 81028350	UNDERGROUND CONDUIT, PVC, 2" DIA.	FOOT	1629	1629	—
* 81702120	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 8	FOOT	3426	3426	—
* 81702140	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 4	FOOT	3426	3426	—
* 84200804	REMOVAL OF POLE FOUNDATION	EACH	8	8	—
* 84400105	RELOCATE EXISTING LIGHTING UNIT	EACH	8	8	—
* 84500130	REMOVAL OF LIGHTING CONTROLLER FOUNDATION	EACH	1	1	—
Δ Z0013798	CONSTRUCTION LAYOUT	L SUM	1	0.8	0.2
Δ Z0032900	LAND SECTION MARKERS	EACH	4	4	—
Δ Z0056608	STORM SEWER (WATER MAIN REQUIREMENTS) 12 INCH	FOOT	289	18	271
Δ Z0056610	STORM SEWER (WATER MAIN REQUIREMENTS) 15 INCH	FOOT	4	4	—
Δ Z0056612	STORM SEWER (WATER MAIN REQUIREMENTS) 18 INCH	FOOT	485	485	—
Δ Z0056620	STORM SEWER (WATER MAIN REQUIREMENTS) 30 INCH	FOOT	52	52	—
Δ Z0076600	TRAINEES	HOURL	1000	1000	—
X2130010	EXPLORATION TRENCH, SPECIAL	FOOT	300	100	200
Δ X5010520	REMOVE CONCRETE BOX CULVERT END SECTION	EACH	2	2	—
Δ * X8360110	LIGHT POLE FOUNDATION, SPECIAL	FOOT	55	55	—
Δ * X8950077	REMOVE AND RELOCATE EXISTING LIGHTING CONTROLLER	EACH	1	1	—
Δ * XX007393	DECORATIVE LIGHT TYPE A	EACH	3	3	—

\* - SPECIALTY ITEM  
 Δ - SPECIAL PROVISION  
 Λ - 0042

DRAWN BY: NV	REVISIONS		
CHECKED BY: JKC	LEVEL	BY	DATE
DATE: 02/12			



FAS 301 / FAU 383  
 SECTION 11-00007-00-WR  
 VILLAGE OF DIAMOND  
 GRUNDY AND WILL COUNTIES

SUMMARY OF QUANTITIES

<b>CONSTRUCTION PLANS</b>	CONTRACT NO. 87520	
	CURRENT AS OF: 02/12	SHEET 8
	SCALE: AS NOTED	FILE NO.: 66022.01 Y- OF 96