

PAVEMENT WIDENING SCHEDULE					
LOCATION	PAVED SHOULDER REMOVAL SQ. YD.	PAVEMENT REMOVAL SQ. YD.	SUB-BASE GRAN. MATL. TYPE A 12" SQ. YD.	AGREGATE BASE COURSE, TYPE A TON	HOT-MIX ASPHALT BASE COURSE, 7 3/4" SQ. YD.
MAINLINE					
STA. 154+50 TO STA. 160+34	---	56.1	1511.2	---	1086.1
STA. 160+30 TO STA. 167+50	295.9	---	2354.7	---	1440.2
STA. 167+50 TO STA. 175+25	334.8	---	2013.3	---	1118.6
SIDE STREETS					
WILL ROAD - SOUTH	---	408.3	---	455.0	---
WILL ROAD - NORTH	---	1270.9	---	948.4	---
TOTAL	631	1735	5879	1403	3645

PAVEMENT PATCHING SCHEDULE		
LOCATION	PAVEMENT PATCHING, TYPE II, 8 INCH SQ YD.	PAVEMENT PATCHING, TYPE IV, 8 INCH SQ YD.
LT STA. 159+63	10.5	---
RT STA. 159+63	10.5	---
LT STA. 161+56.34	---	92.9
RT STA. 161+56.34	---	126.7
TOTAL	21	220

HMA SURFACE REMOVAL		
LOCATION	HMA SURFACE REMOVAL - BUTT JOINT SQ. YD.	HMA SURFACE REMOVAL - 1/2" 1 SQ. YD.
MAINLINE		
STA. 154+50 TO STA. 156+00	---	431.6
STA. 174+85 TO STA. 175+25	194.3	---
SIDE STREETS		
CURTIS STREET (LT STA. 156+40)	178.6	---
WILL ROAD - NORTH	---	---
WILL ROAD - SOUTH	---	447.9
TOTAL	373	879

DRIVEWAY SCHEDULE						
LOCATION	NEW DRIVEWAY WIDTH FOOT	DRIVEWAY PAVEMENT REMOVAL SQ YD.	PCC DRIVEWAY PAVEMENT 6" SQ YD.	PCC DRIVEWAY PAVEMENT 8" SQ YD.	AGGREGATE FOR TEMPORARY ACCESS TON	AGGREGATE SURFACE COURSE, TYPE B TON
MAINLINE						
STA. 155+73.74, RT	36	51.2	---	33.2	11.4	---
STA. 156+80.42, RT	26	74.3	---	51.6	17.6	---
STA. 158+03.88, LT	12	35.7	74.4	---	25.4	---
STA. 163+19.55, RT	14	---	---	100.3	34.3	31.8
STA. 163+61.39, LT	14	---	---	102.8	35.1	53.0
STA. 174+52.85, LT	26	114.9	---	90.8	31.0	---
SIDE STREETS						
STA. 96+40.30, LT	30	---	---	48.2	16.5	---
STA. 96+95.33, LT	35	71.7	---	55.4	18.9	---
STA. 97+62.97, LT	26	---	---	42.6	14.5	---
STA. 98+05.62, LT	17	---	---	28.6	9.8	---
STA. 202+03.45, LT	12	---	28.7	---	9.8	---
TOTAL	INFO ONLY	348	103	553	224	85

STORM SEWER STRUCTURE SCHEDULE																						
STRUCTURE NUMBER	STATION	OFFSET	RIM ELEV.	FLOW LINE ELEVATION				PRECAST REINFORCED CONCRETE FLARED END SECTIONS, 12"	PRECAST REINFORCED CONCRETE FLARED END SECTIONS, 24"	PRECAST REINFORCED CONCRETE FLARED END SECTIONS, 30"	MANHOLES, TYPE A, 4'- DIAMETER, TYPE 1 FRAME, CLOSED LID	MANHOLES, TYPE A, 4'- DIAMETER, TYPE 3 FRAME AND GRATE	MANHOLES, TYPE A, 4'- DIAMETER, TYPE 8 GRATE	MANHOLES, TYPE A, 5'- DIAMETER, TYPE 1 FRAME, OPEN LID	MANHOLES, TYPE A, 5'- DIAMETER, TYPE 1 FRAME, CLOSED LID	MANHOLES, TYPE A, 5'- DIAMETER, TYPE 3 FRAME AND GRATE	INLETS, TYPE A, TYPE 3 FRAME AND GRATE	INLETS, TYPE A, TYPE 8 GRATE	INLETS, TYPE B, TYPE 3 FRAME AND GRATE	INLETS, TYPE B, TYPE 8 GRATE	CONCRETE COLLAR	REMARKS
				NORTH	SOUTH	EAST	WEST															
1	201+32.55	53.63' RT	--	--	--	--	549.65	---	---	1	---	---	---	---	---	---	---	---	---	---	---	---
2	201+32.55	29.59' RT	556.00	--	--	550.12	550.12	---	---	---	---	---	---	---	---	1	---	---	---	---	---	---
3	201+32.55	13' LT	556.33	--	550.57	550.57	--	---	---	---	---	---	---	---	---	1	---	---	---	---	---	---
4	200+79.81	40.79' LT	554.50	551.16	551.16	--	--	---	---	---	---	---	---	---	---	1	---	---	---	---	---	---
5	159+63.50	30.93' LT	557.40	551.70	551.70	--	--	---	---	---	---	---	---	---	---	1	---	---	---	---	---	---
6	159+63.10	24.50' LT	557.68	551.78	552.40	--	552.28	---	---	---	---	---	---	---	---	1	---	---	---	---	---	---
7	159+63.84	23.46' RT	557.55	553.40	553.40	--	--	---	---	---	---	---	---	---	---	---	---	---	---	1	---	---
8	159+55.08	37.84' RT	555.55	553.55	--	--	--	---	---	---	---	---	---	---	---	---	---	---	---	---	1	---
9	99+06.00	38.40' RT	--	--	--	--	551.74	1	---	---	---	---	---	---	---	---	---	---	---	---	---	---
10	99+16.40	18.6' RT	556.33	--	--	552.61	552.61	---	---	---	---	---	---	---	---	---	---	---	---	1	---	---
11	99+16.40	29.01' LT	556.12	--	--	553.12	553.12	---	---	---	---	---	---	---	---	---	---	---	---	1	---	---
12	99+16.40	48.07' LT	555.80	--	--	553.80	--	---	---	---	---	---	---	---	---	---	---	---	---	---	1	---
13	97+78.00	39.58' RT	--	--	--	--	551.89	1	---	---	---	---	---	---	---	---	---	---	---	---	---	---
14	97+78.00	28.00' LT	556.80	--	--	553.80	--	---	---	---	---	---	---	---	---	---	---	---	---	---	1	---
15	96+00.00	42.40' RT	--	--	--	--	552.09	---	1	---	---	---	---	---	---	---	---	---	---	---	---	---
16	96+00.00	28.00' LT	557.50	--	--	554.00	--	---	---	---	---	---	---	---	---	---	---	---	---	---	---	1
17	157+82.30	26.00' LT	557.78	555.27	553.28	553.28	553.28	---	---	---	---	---	---	---	---	---	---	---	---	---	---	---
18	157+85.00	44.00' LT	557.45	--	555.45	--	--	---	---	---	---	---	---	---	---	---	---	---	---	---	1	---
19	157+82.30	19.00' LT	558.36	553.74	553.74	--	--	---	---	---	---	---	---	---	---	---	---	---	---	---	---	---
SUBTOTAL								2	1	1	0	0	0	1	1	3	0	3	4	2	0.00	

STORM SEWER REMOVAL & ADJUSTMENT SCHEDULE								
LOCATION	STORM SEWER REMOVAL 12" FOOT	STORM SEWER REMOVAL 18" FOOT	STORM SEWER REMOVAL 24" FOOT	STORM SEWER REMOVAL 30" FOOT	MANHOLES TO BE ADJUSTED EACH	INLETS TO BE ADJUSTED EACH	REMOVING MANHOLES EACH	REMOVING INLETS EACH
MAINLINE								
RT STA. 155+97 TO STA. 156+51	53	---	---	---	---	---	---	---
LT STA. 156+07	---	---	---	---	---	1	---	---
RT STA. 156+51	10	---	---	---	---	---	---	2
LT STA. 156+65	---	---	---	---	1	---	---	---
RT STA. 157+80	---	---	---	---	---	---	---	2
LT STA. 157+82	10	---	---	---	1	---	---	1
LT STA. 159+67 TO STA. 159+90	---	---	22	---	---	---	1	---
LT STA. 159+90 TO STA. 160+03	---	14	---	---	---	---	---	1
RT STA. 160+02	---	9	---	---	---	---	---	1
LT STA. 159+60 TO STA. 160+72	---	---	83	---	---	---	---	---
RT STA. 160+02	---	---	---	---	1	---	---	---
LT STA. 160+71	---	5	---	---	---	---	---	---
SIDE STREETS								
STA. 95+83	---	---	40	---	---	---	---	1
TOTAL	73	28	62	83	3	1	1	8

PIPE CULVERT REMOVAL SCHEDULE	
LOCATION	PIPE CULVERT REMOVAL FOOT
RT STA. 161+08	86
RT STA. 203+84	50
LT STA. 174+50 (NON-PARTICIPATING)	46
TOTAL	182

PIPE UNDERDRAIN SCHEDULE	
LOCATION	PIPE UNDERDRAINS 4" FOOT
SIDE STREET	
STA. 99+16	48
STA. 201+33	42
TOTAL	90

CHAMLIN & ASSOCIATES, INC. © 2010
Drawing Name: C:\Users\A\66022-01 -Diamond-Will-Road-11-3-Env-Survey\CAD\PLANS-EXTENDED\09-SCHEDULE.dwg Last Modified: Apr 10, 2012 - 12:17pm Plotted on: Apr 10, 2012 - 12:30pm by nancq

DRAWN BY: NV	REVISIONS			
CHECKED BY: JKC	LEVEL	BY	DATE	DESCRIPTION
DATE: 02/12				



FAS 301 / FAU 383
SECTION 11-00007-00-WR
VILLAGE OF DIAMOND
GRUNDY AND WILL COUNTIES

SCHEDULE OF QUANTITIES

CONSTRUCTION PLANS	CONTRACT NO. 87520	
	CURRENT AS OF: 02/12	
	SCALE: AS NOTED	SHEET 10
	FILE NO.: 66022.01 Y-	OF 96