



- |  |                                             |  |                                              |
|--|---------------------------------------------|--|----------------------------------------------|
|  | HOT-MIX ASPHALT SURFACE REMOVAL, BUTT JOINT |  | SIDWALK REMOVAL                              |
|  | HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"     |  | PAVEMENT REMOVAL & DRIVEWAY PAVEMENT REMOVAL |
|  | SHOULDER REMOVAL                            |  | COMBINATION CONCRETE CURB & GUTTER REMOVAL   |

- A - MANHOLE OR INLET TO BE ADJUSTED
- R - MANHOLE, INLET OR LIGHT POLE BASE TO BE REMOVED
- RL - LIGHT POLE, LIGHTING CONTROLLER, FIRE HYDRANT, AND WATER VALVE TO BE RELOCATED (SEE LIGHTING AND WATER MAIN PLANS)
- STORM SEWER TO BE REMOVED
- X - TREE REMOVAL

NOTE: IN ADDITION TO THE ITEMS SHOWN TO BE REMOVED, RELOCATED OR ADJUSTED HERE, UTILITIES OWNED BY OTHERS MUST ALSO BE REMOVED, RELOCATED OR ADJUSTED. THE CONTRACTOR SHALL COORDINATE HIS WORK WITH THOSE UTILITIES.

CHAMBLIN & ASSOCIATES, INC. © 2011  
 Drawing Name: C:\Users\Will-Morris\Documents\113-Enr-Survey\Survey\CAD\2D\PLANS-EXTENDED\113-REM-158-163.dwg Last Modified: Feb 09, 2012 - 8:57am Plotted on: Mar 27, 2012 - 1:34pm by nareq

DRAWN BY: NV	REVISIONS			
CHECKED BY: JKC	LEVEL	BY	DATE	DESCRIPTION
DATE: 02/12				

CHAMBLIN & ASSOCIATES PERU MORRIS ILLINOIS

FAS 301 / FAU 383  
 SECTION 11-00007-00-WR  
 VILLAGE OF DIAMOND  
 GRUNDY AND WILL COUNTIES

REMOVAL PLAN - IL 113  
 STA. 158+00 TO STA. 163+00

<b>CONSTRUCTION PLANS</b>	CONTRACT NO. 87520	
	CURRENT AS OF: 02/12	
	SCALE: AS NOTED	SHEET 13
	FILE NO.: 66022.01 Y-	OF 96