

PAY ITEM #	DESCRIPTION	UNIT	TOTAL	05-15103-00-BR	05-15106-01-BR
20200100	EARTH EXCAVATION	CU YD	10491	1996	8495
20400800	FURNISHED EXCAVATION	CU YD	15057	5044	10013
20800150	TRENCH BACKFILL	CU YD	178	74	104
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	16330	5348	10982
25000210	SEEDING, CLASS 2A	ACRE	2.25	0.70	1.55
25000305	SEEDING, CLASS 3A	ACRE	1.25	0.42	0.83
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	315	101	214
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	315	101	214
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	315	101	214
25100115	MULCH, METHOD 2	ACRE	2.25	0.70	1.55
25100630	EROSION CONTROL BLANKET	SQ YD	6427	2414	4013
25100900	TURF REINFORCEMENT MAT	SQ YD	1379	353	1026
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	339	111	228
28000305	TEMPORARY DITCH CHECKS	FOOT	1201.5	553.5	648
28000400	PERIMETER EROSION BARRIER	FOOT	2063	827	1236
28000500	INLET AND PIPE PROTECTION	EACH	5	1	4
28100105	STONE RIPRAP, CLASS A3	SQ YD	58	58	0
28100107	STONE RIPRAP, CLASS A4	SQ YD	938	0	938
28100125	STONE RIPRAP, CLASS B3	SQ YD	9	9	0
28200200	FILTER FABRIC	SQ YD	1062	124	938
35100100	AGGREGATE BASE COURSE, TYPE A	TON	2588	863	1725
40200100	AGGREGATE SURFACE COURSE, TYPE A	TON	140	0	140
40201000	AGGREGATE FOR TEMPORARY ACCESS	TON	8	0	8
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	41	41	0
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	33	33	0
44000100	PAVEMENT REMOVAL	SQ YD	3778	1311	2467
48100500	AGGREGATE SHOULDERS, TYPE A 6"	SQ YD	1106	375	731
50100100	REMOVAL OF EXISTING STRUCTURES	EACH	1	0	1
50105220	PIPE CULVERT REMOVAL	FOOT	151	62	89
50200100	STRUCTURE EXCAVATION	CU YD	390	191	199
50300225	CONCRETE STRUCTURES	CU YD	223.6	170.9	52.7
50300255	CONCRETE SUPERSTRUCTURE	CU YD	205.3	10.4	194.9
50300260	BRIDGE DECK GROOVING	SQ YD	269	0	269
50300280	CONCRETE ENCASMENT	CU YD	6.8	3.4	3.4
50300300	PROTECTIVE COAT	SQ YD	369	69	300
50400505	PRECAST PRESTRESSED CONCRETE DECK BEAMS (27" DEPTH)	SQ FT	4010	4010	0
50400735	FURNISHING AND ERECTING PRECAST PRESTRESSED CONCRETE BULB T-BEAMS 63"	FOOT	436	0	436
50800105	REINFORCEMENT BARS	POUND	14020	14020	0

PAY ITEM #	DESCRIPTION	UNIT	TOTAL	05-15103-00-BR	05-15106-01-BR
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	69890	23800	46090
50800515	BAR SPLICERS	EACH	50	0	50
50900205	STEEL RAILING, TYPE S1	FOOT	265	0	265
50900305	STEEL RAILING, TYPE T1	FOOT	339	339	0
51100100	SLOPE WALL 4 INCH	SQ YD	27	27	0
51201600	FURNISHING STEEL PILES HP 12X53	FOOT	284	284	0
51201610	FURNISHING STEEL PILES HP 12X63	FOOT	416	0	416
51202305	DRIVING PILES	FOOT	700	284	416
51203600	TEST PILE STEEL HP 12X53	EACH	2	2	0
51203610	TEST PILE STEEL HP 12X63	EACH	2	0	2
51204650	PILE SHOES	EACH	20	10	10
51500100	NAME PLATES	EACH	2	1	1
51603000	DRILLED SHAFT IN SOIL	CU YD	43.6	43.6	0
51604000	DRILLED SHAFT IN ROCK	CU YD	36.3	36.3	0
542C1060	PIPE CULVERTS, CLASS C, TYPE 2 15"	FOOT	24	0	24
542C1069	PIPE CULVERTS, CLASS C, TYPE 2 24"	FOOT	50	0	50
542C1909	PIPE CULVERTS, CLASS C, TYPE 3 24"	FOOT	157	0	157
542C3370	PIPE CULVERTS, CLASS C, TYPE 5 15"	FOOT	111.5	111.5	0
54213450	END SECTIONS 15"	EACH	4	2	2
54213459	END SECTIONS 24"	EACH	4	0	4
58100200	WATERPROOFING MEMBRANE SYSTEM	SQ YD	409	409	0
58300100	PORTLAND CEMENT MORTAR FAIRING COURSE	FOOT	1171	1171	0
59100100	GEOCOMPOSITE WALL DRAIN	SQ YD	92	0	92
60240301	INLETS, TYPE B, TYPE 8 GRATE	EACH	1	0	1
63000003	STEEL PLATE BEAM GUARDRAIL, TYPE A, 9 FOOT POSTS	FOOT	1175	425	750
63100075	TRAFFIC BARRIER TERMINAL, TYPE 5A	EACH	8	4	4
63300725	STEEL PLATE BEAM GUARDRAIL (SHORT RADIUS)	FOOT	137.5	0	137.5
66600105	FURNISHING AND ERECTING RIGHT OF WAY MARKERS	EACH	23	7	16
78200410	GUARDRAIL MARKERS, TYPE A	EACH	24	7	17
78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	6	2	4
X2070304	POROUS GRANULAR EMBANKMENT, SPECIAL	CU YD	89	0	89
X7010216	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	L SUM	1	0.5	0.5
XX000856	MAILBOX REMOVAL AND RELOCATION	EACH	1	0	1
Z0001900	ASBESTOS BEARING PAD REMOVAL	EACH	42	0	42
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	0.5	0.5
Z0022800	FENCE REMOVAL	FOOT	2703	808	1895
Z0046304	PIPE UNDERDRAINS FOR STRUCTURES 4"	FOOT	132	0	132
Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1	1	0
Z0065704	BITUMINOUS COATED AGGREGATE SLOPEWALL 6"	SQ YD	348	348	0
67100100	MOBILIZATION	L SUM	1	0.5	0.5
LR631020	TRAFFIC BARRIER TERMINAL TYPE 1	EACH	6	2	4

△ SPECIALTY ITEMS