

SUMMARY OF QUANTITIES

SP	PAY ITEM #	PAY ITEM NAME	UNIT	TOTAL
^	20101000	TEMPORARY FENCE	FOOT	1546
^Δ	20101200	TREE ROOT PRUNING	EACH	7
	20200100	EARTH EXCAVATION	CU YD	5266
	20201200	REMOVAL & DISPOSAL OF UNSUITABLE MATERIAL	CU YD	3802
	21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	26665
	21400100	GRADING & SHAPING DITCHES	FOOT	6220
Δ	25000100	SEEDING, CLASS 1	ACRES	5
Δ	25000400	NITROGEN FERTILIZER NUTRIENT	POUND	323
Δ	25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	647
Δ	25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	323
Δ	25100630	EROSION CONTROL BLANKET	SQ YD	14875
Δ	25200100	SODDING, SALT TOLERANT	SQ YD	2113
Δ	25200200	SUPPLEMENTAL WATERING	UNIT	82
	35101800	AGGREGATE BASE COURSE, TYPE B, 6"	SQ YD	10422
	40200100	AGGREGATE SURFACE COURSE, TYPE A	TON	9
	40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX C, N50	TON	1751
	42300200	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT - 6 INCHES	SQ YD	14
^	42400200	PORTLAND CEMENT CONCRETE SIDEWALK, 5 INCH	SQ FT	4307
	42400800	DETECTABLE WARNINGS	SQ FT	320
	44000100	PAVEMENT REMOVAL	SQ YD	311
	44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	114
	44000500	COMBINATION CONCRETE CURB AND GUTTER REMOVAL	FOOT	164
	44000600	SIDEWALK REMOVAL	SQ FT	4480
	44201335	CLASS C PATCHES, TYPE IV, 8 INCH	SQ YD	114
	54213867	STEEL END SECTION 12"	EACH	14
	60200805	CATCH BASIN, TYPE A, 4-FOOT DIAMETER, TYPE 8 FRAME	EACH	3
	60207605	CATCH BASIN, TYPE C, TYPE 8 GRATE	EACH	1
	60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	164
Δ	66900200	NON-SPECIAL WASTE DISPOSAL	CU YD	50
	67100100	MOBILIZATION	LSUM	1
	72000100	SIGN PANEL - TYPE 1	SQ FT	208
	72400100	REMOVE SIGN PANEL ASSEMBLY, TY A.	EACH	2
^	73400100	CONCRETE FOUNDATION	CU YD	6
Δ	78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	1088
Δ	78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	131
	542C0217	PIPE CULVERTS, CLASS C, TYPE 1 12"	FOOT	364
	550B0050	STORM SEWERS, CLASS B, TYPE 1, 12"	FOOT	361

SP	PAY ITEM #	PAY ITEM NAME	UNIT	TOTAL
Δ	B2000116	TREE, ACER CAMPESTER (HEDGE MAPLE), 2" CALIPER, TREE FORM, BALLED AND BURLAPPED	EACH	3
Δ	B2000666	TREE, AMELANCHIERX GRANDIFLORA (APPLE SERVICEBERRY), 6' HEIGHT, SHRUB FORM, BALLED AND BURLAPPED	EACH	6
Δ	B2002220	TREE, CRATAEGUS VIRDIS WINTER KING (WINTER KING GREEN HAWTHORN), 2-1/2" CALIPER, TREE FORM, BALLED AND BURLAPPED	EACH	4
Δ	B2003016	TREE, MALUS BRANDYWINE (BRANDYWINE CRAB APPLE), 2" CALIPER, TREE FORM, BALLED AND BURLAPPED	EACH	4
Δ	K0026830	SHRUB REMOVAL	EACH	23
	X2800500	INLET PROTECTION, SPECIAL	EACH	12
^	X7010216	TRAFFIC CONTROL AND PROTECTION (SPECIAL)	LSUM	1
	Z0003850	BENCHES	EACH	1
	Z0003855	BICYCLE RACKS	FOOT	6
	Z0004002	BOLLARDS	EACH	5
	Z0013798	CONSTRUCTION LAYOUT	LSUM	1
	Z0023204	SEDIMENT CONTROL, SILT FENCE	FOOT	5369
	Z0048900	RAILROAD TRACK REMOVAL	FOOT	165

Δ SPECIALTY ITEMS

PLAN
 DESIGNED BY: _____ DATE: _____
 CHECKED BY: _____ DATE: _____
 NOTE BOOK NO. _____
 ALIGNMENT CHECKED BY: _____
 CADD FILE NAME: _____

PROFILE
 DESIGNED BY: _____ DATE: _____
 CHECKED BY: _____ DATE: _____
 NOTE BOOK NO. _____
 GRADES CHECKED BY: _____
 STRUCTURE NOTATIONS DEVD: _____