SUMMARY OF QUANTITIES

	CODE NUMBER	ITEM	UNIT	TOTAL QUANTITY	SURFACE TRANSPORTATION URBAN (STU)	NON PARTICIPATING
	20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	244	244	
	20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	253	253	
	20100500	TREE REMOVAL, ACRES	ACRES	0.4	0.4	
	20200100	EARTH EXCAVATION	CU YD	1971	1971	
*	20300100	CHANNEL EXCAVATION	CU YD	2495	2495	
	20400800	FURNISHED EXCAVATION	CU YD	7075	7075	
Δ*	20800150	TRENCH BACKFILL	CU YD	36		36
	21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	4979	4979	
*	25100630	EROSION CONTROL BLANKET	SQ YD	1606	1606	
	28000200	EARTH EXCAVATION FOR EROSION CONTROL	CU YD	8	8	
	28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	60	60	
	28000315	AGGREGATE DITCH CHECKS	TON	101	101	
	28000400	PERIMETER EROSION BARRIER	FOOT	2262	2262	
	28000500	INLET AND PIPE PROTECTION	EACH	4	4	
	28100107	STONE RIPRAP, CLASS A4	SQ YD	1548	1548	
	28200200	FILTER FABRIC	SQ YD	2165	2165	
	30200650	PROCESSING MODIFIED SOIL 12"	SQ YD	2914	2914	
	30201700	PORTLAND CEMENT	TON	124	124	
*	40201000	AGGREGATE FOR TEMPORARY ACCESS	TON	971	971	
	40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	438	438	
	40603085	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N70	TON	924	924	
	40603315	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N70	TON	300	300	
	42300200	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 6 INCH	SQ YD	347	347	
	44000100	PAVEMENT REMOVAL	SQ YD	1079	1079	
	44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	544	544	

* DENOTES SPECIAL PROVISION
Δ SPECIALTY ITEMS

URS
345 EAST ASH AVENUE, SUITE B
DECATUR, ILLINOIS 62526
PH. 217-875-4800