

SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNIT	URBAN - MONROE COUNTY FEDERAL 75% CITY 25% TOTAL QUANTITY
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	8
20200100	EARTH EXCAVATION	CU. YD.	2,010
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU. YD.	1,384
20900110	POROUS GRANULAR BACKFILL	CU. YD.	672.5
21101505	TOPSOIL EXCAVATION AND PLACEMENT	CU. YD.	194
25000110	SEEDING, CLASS 1A	ACRE	0.36
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	33
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	33
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	33
25000700	AGRICULTURAL GROUND LIMESTONE	TON	0.8
25100635	HEAVY DUTY EROSION CONTROL BLANKET	SQ. YD.	1,740
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	36
28000305	TEMPORARY DITCH CHECKS	FOOT	28
28000400	PERIMETER EROSION BARRIER	FOOT	450
28000500	INLET AND PIPE PROTECTION	EACH	103
31100300	SUB-BASE GRANULAR MATERIAL, TYPE A, 4"	SQ. YD.	6,778.1
31100700	SUB-BASE GRANULAR MATERIAL, TYPE A, 8"	SQ. YD.	551.3
31100910	SUB-BASE GRANULAR MATERIAL, TYPE A, 12"	SQ. YD.	567.2
40200700	AGGREGATE SURFACE COURSE, TYPE A B"	SQ. YD.	18.2
40201000	AGGREGATE FOR TEMPORARY ACCESS	TON	826
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	503
40600300	AGGREGATE (PRIME COAT)	TON	5
40603085	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N70	TON	212.9
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	113.6
42000301	PORTLAND CEMENT CONCRETE PAVEMENT 8" (JOINTED)	SQ. YD.	5,667.1
42300200	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 6 INCH	SQ. YD.	71.1
42300400	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH	SQ. YD.	244.5
42400100	PORTLAND CEMENT CONCRETE SIDEWALK 4 INCH	SQ. FT.	12,548.9
42400800	DETECTABLE WARNINGS	SQ. FT.	115.6
44000100	PAVEMENT REMOVAL	SQ. YD.	847
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	2,323.8
44000600	SIDEWALK REMOVAL	SQ. FT.	7,251
54216185	REINFORCED CONCRETE PIPE TEE, 15" PIPE WITH 12" RISER	EACH	1
54216200	REINFORCED CONCRETE PIPE TEE, 24" PIPE WITH 12" RISER	EACH	3
54216220	REINFORCED CONCRETE PIPE TEE, 36" PIPE WITH 12" RISER	EACH	8
54216253	REINFORCED CONCRETE PIPE TEE, 54" PIPE WITH 12" RISER	EACH	8
54216623	REINFORCED CONCRETE PIPE TEE, 54" PIPE WITH 15" RISER	EACH	1
54216960	REINFORCED CONCRETE PIPE TEE, 36" PIPE WITH 18" RISER	EACH	2
54216993	REINFORCED CONCRETE PIPE TEE, 54" PIPE WITH 18" RISER	EACH	1
54248510	CONCRETE COLLAR	CU YD	6.1
550A0050	STORM SEWERS, CLASS A, TYPE 1 12"	FOOT	71.0
550A0070	STORM SEWERS, CLASS A, TYPE 1 15"	FOOT	45.3
550A0090	STORM SEWERS, CLASS A, TYPE 1 18"	FOOT	13.0
550A0120	STORM SEWERS, CLASS A, TYPE 1 24"	FOOT	33.8
550A0200	STORM SEWERS, CLASS A, TYPE 1 54"	FOOT	229.0
550A0340	STORM SEWERS, CLASS A, TYPE 2 12"	FOOT	282.7
550A0360	STORM SEWERS, CLASS A, TYPE 2 15"	FOOT	58.5
550A0380	STORM SEWERS, CLASS A, TYPE 2 18"	FOOT	14.0
550A0410	STORM SEWERS, CLASS A, TYPE 2 24"	FOOT	194.1
550A0450	STORM SEWERS, CLASS A, TYPE 2 36"	FOOT	305.6
550B0090	STORM SEWERS, CLASS B, TYPE 1 18"	FOOT	29.0
550B0120	STORM SEWERS, CLASS B, TYPE 1 24"	FOOT	35.0
550B0360	STORM SEWERS, CLASS B, TYPE 2 15"	FOOT	10.0
550B0380	STORM SEWERS, CLASS B, TYPE 2 18"	FOOT	47.4
550B0410	STORM SEWERS, CLASS B, TYPE 2 24"	FOOT	9.6

CODE NO.	ITEM	UNIT	URBAN - MONROE COUNTY FEDERAL 75% CITY 25% TOTAL QUANTITY
55100300	STORM SEWER REMOVAL 8"	FOOT	92
55100500	STORM SEWER REMOVAL 12"	FOOT	163
55100900	STORM SEWER REMOVAL 18"	FOOT	596
55101200	STORM SEWER REMOVAL 24"	FOOT	606
56500300	DOMESTIC METER VAULTS TO BE ADJUSTED	EACH	6
60100085	GEOTECHNICAL FABRIC FOR FRENCH DRAINS	SQ. YD.	1,222
60100915	PIPE DRAINS 6"	FOOT	452.0
60100925	PIPE DRAINS 8"	FOOT	147.0
60223800	MANHOLES, TYPE A, 6'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	4
60235300	INLETS, TYPE A, TYPE 1 FRAME, CLOSED LID	EACH	4
60266600	VALVE BOXES TO BE ADJUSTED	EACH	25
60500040	REMOVING MANHOLES	EACH	1
60500060	REMOVING INLETS	EACH	10
60604400	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.18	FOOT	2,537.7
67100100	MOBILIZATION	L. SUM	1
78008210	POLYUREA PAVEMENT MARKING TYPE I - LINE 4"	FOOT	5,385
78008230	POLYUREA PAVEMENT MARKING TYPE I - LINE 6"	FOOT	509
78008250	POLYUREA PAVEMENT MARKING TYPE I - LINE 12"	FOOT	85
X0322024	TRENCH DRAIN	EACH	4
X0324450	SEGMENTAL CONCRETE BLOCK WALL, SPECIAL	SQ. FT.	368.4
X0326694	PLUG EXISTING STORM SEWER	CU. YD.	0.5
X0327037	SPECIAL GRATE NO. 1	EACH	24
X2090215	SELECT GRANULAR BACKFILL, SPECIAL	CU. YD.	2,309.8
X6011705	PIPE DRAINS 6" (SPECIAL)	FOOT	58.5
X6011805	PIPE DRAINS 8" (SPECIAL)	FOOT	38.0
X6020074	INLETS, TYPE A, TYPE 3V FRAME AND GRATE	EACH	21
X6020075	INLETS, TYPE B, TYPE 3V FRAME AND GRATE	EACH	4
X6020101	MANHOLES, 9'-DIAMETER, TYPE 1 FRAME, CLOSED LID (SPECIAL)	EACH	1
X6022930	MANHOLES, TYPE A, 5'-DIAMETER WITH SEPCIAL FRAME AND GRATE	EACH	1
X6023212	INLETS, TYPE A, WITH SPECIAL FRAME AND GRATE, SPECIAL	EACH	5
X6024242	INLETS, SPECIAL, NO. 1	EACH	13
X6024244	INLETS, SPECIAL, NO. 2	EACH	2
X6024246	INLETS, SPECIAL, NO. 3	EACH	4
X6024502	INLETS, TYPE B, WITH SPECIAL FRAME AND GRATE	EACH	1
X6026050	SANITARY MANHOLES TO BE ADJUSTED	EACH	3
X6029000	JUNCTION BOX	L. SUM	1
X7010216	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	L. SUM	1
X7010226	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501, SPECIAL	L. SUM	1
XX001848	CURB BOXES TO BE ADJUSTED	EACH	27
Z0012450	CONCRETE STEPS	CU. YD.	6.0
Z0013302	SEGMENTAL CONCRETE BLOCK WALL	SQ. FT.	2660.0
Z0042300	PORTLAND CEMENT CONCRETE SIDEWALK CURB	FOOT	62.6
Z0056608	STORM SEWER (WATER MAIN REQUIREMENTS) 12 INCH	FOOT	75.0
Z0064562	SEGMENTAL BLOCK RETAINING WALL REPAIR	SQ. FT.	260.0
Z0075496	CONCRETE RETAINING WALL REMOVAL	FOOT	239.0
X5460401	PRECAST CONCRETE BOX CULVERT, 4' x 4' (SPECIAL)	FOOT	234.0

* DENOTES SPECIAL PROVISION ITEMS
 Δ DENOTES SPECIAL SPECIALTY ITEMS

HMG ENGINEERS, INC., 1075 LAKE ROAD, PO BOX 70, CARLYLE, IL 62231 PHONE (618) 594-3711 WWW.HMGENGINEERS.COM