SUMMARY OF QUANTITIES

SUMMARY OF QUANTITIES

CODE NO.	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY
40201000	AGGREGATE FOR TEMPORARY ACCESS	TON	25
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	1855
40600300	AGGREGATE (PRIME COAT)	TON	29
40600990	TEMPORARY RAMP	SQ YD	754
40603090	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N90	TON	1249
40603345	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N90	TON	1249
42001300	PROTECTIVE COAT	SQ YD	859
42300400	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH	SQ YD	14
42400100	PORTLAND CEMENT CONCRETE SIDEWALK 4 INCH	SQ FT	6174
42400800	DETECTABLE WARNINGS	SQ FT	402
44000159	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/2"	SQ YD	10805
44000165	HOT-MIX ASPHALT SURFACE REMOVAL, 4"	SQ YD	4395
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	14
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	523
44000600	SIDEWALK REMOVAL	SQ FT	5545
44201353	CLASS C PATCHES, TYPE II, 10 INCH	SQ YD	74
44201357	CLASS C PATCHES, TYPE III, 10 INCH	SQ YD	151
44201359	CLASS C PATCHES, TYPE IV, 10 INCH	SQ YD	1063
44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	1122
55100500	STORM SEWER REMOVAL 12"	FOOT	8
60240324	INLETS, TYPE B, TYPE 20 FRAME AND GRATE	EACH	1
60500060	REMOVING INLETS	EACH	1
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	454
60600605	CONCRETE CURB, TYPE B	FOOT	73
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	4
67100100	MOBILIZATION	L SUM	1
70300240	TEMPORARY PAVEMENT MARKING-LINE 6"	FOOT	1380
70300260	TEMPORARY PAVEMENT MARKING-LINE 12"	FOOT	385

SUMMARY OF QUANTITIES

	CODE NO.	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY
	70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	1075
*	72000100	SIGN PANEL - TYPE 1	SQ FT	6
*	72900200	METAL POST - TYPE B	FOOT	13
*	78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	1380
*	78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	385
	X7010216	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	L SUM	1

* SPECIALTY ITEMS